


Robert B. Grossman

The Art of Writing Reasonable Organic Reaction Mechanisms

Third Edition



EXTRAS ONLINE

 Springer

The Art of Writing Reasonable Organic Reaction Mechanisms

Robert B. Grossman

The Art of Writing Reasonable Organic Reaction Mechanisms

Third Edition

 Springer

Robert B. Grossman
Department of Chemistry
University of Kentucky
Lexington, KY, USA

ISBN 978-3-030-28732-0 ISBN 978-3-030-28733-7 (eBook)
<https://doi.org/10.1007/978-3-030-28733-7>

1st edition: © Springer-Verlag New York 1999

2nd edition: © Springer Science+Business Media New York 2003

3rd edition: © Springer Nature Switzerland AG 2019

This work is subject to copyright. All rights are reserved by the Publisher, whether the whole or part of the material is concerned, specifically the rights of translation, reprinting, reuse of illustrations, recitation, broadcasting, reproduction on microfilms or in any other physical way, and transmission or information storage and retrieval, electronic adaptation, computer software, or by similar or dissimilar methodology now known or hereafter developed.

The use of general descriptive names, registered names, trademarks, service marks, etc. in this publication does not imply, even in the absence of a specific statement, that such names are exempt from the relevant protective laws and regulations and therefore free for general use.

The publisher, the authors and the editors are safe to assume that the advice and information in this book are believed to be true and accurate at the date of publication. Neither the publisher nor the authors or the editors give a warranty, expressed or implied, with respect to the material contained herein or for any errors or omissions that may have been made. The publisher remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

This Springer imprint is published by the registered company Springer Nature Switzerland AG
The registered company address is: Gewerbestrasse 11, 6330 Cham, Switzerland

Preface: To the Student

The purpose of this book is to help you learn how to draw reasonable mechanisms for organic reactions. A *mechanism* is a story that we tell to explain how compound **A** is transformed into compound **B** under given reaction conditions. Imagine being asked to describe how you traveled from New York to Los Angeles (an overall reaction). You might tell how you traveled through New Jersey to Pennsylvania, across to St. Louis, over to Denver, then through the Southwest to the West Coast (the mechanism). You might include details about the mode of transportation you used (reaction conditions), cities where you stopped for a few days (intermediates), detours you took (side reactions), and your speed at various points along the route (rates). To carry the analogy further, there is more than one way to get from New York to Los Angeles; at the same time, not every story about how you traveled from New York to Los Angeles is believable. Likewise, more than one reasonable mechanism can often be drawn for a reaction, and one of the purposes of this book is to teach you how to distinguish a reasonable mechanism from a whopper.

It is important to learn how to draw reasonable mechanisms for organic reactions because mechanisms are the framework that makes organic chemistry make sense. Understanding and remembering the bewildering array of reactions known to organic chemists would be completely impossible were it not possible to organize them into just a few basic mechanistic types. The ability to formulate mechanistic hypotheses about how organic reactions proceed is also required for the discovery and optimization of new reactions.

The general approach of this book is to familiarize you with the classes and types of reaction mechanisms that are known and to give you the tools to learn how to draw mechanisms for reactions that you have never seen before. The body of each chapter discusses the more common mechanistic pathways and suggests practical tips for drawing them. The discussion of each type of mechanism contains both worked and unworked problems. You are urged to work the unsolved problems yourself. **Common error alerts** are scattered throughout the text to warn you about common pitfalls and misconceptions that bedevil students. Pay attention to these alerts, as failure to observe their strictures has caused many, many exam points to be lost over the years.

Occasionally, you will see indented, tightly spaced paragraphs such as this one. The information in these paragraphs is usually of a parenthetical nature, either because it deals with formalisms, minor points, or exceptions to general rules, or because it deals with topics that extend beyond the scope of the textbook.

Extensive problem sets are found at the end of all chapters. The *only way* you will learn to draw reaction mechanisms is to *work the problems!* If you do not work problems, you will not learn the material. The problems vary in difficulty from relatively easy to very difficult. Many of the reactions covered in the problem sets are classical organic reactions, including many “name reactions.” All examples are taken from the literature. Additional problems may be found in other textbooks. Ask your librarian, or consult some of the books discussed below.

Detailed answer keys are provided in separate PDF files that are available for download from the Springer web site at no additional cost. (Find a link at <http://www.uky.edu/~rbgros1/textbook.html>.) It is important for you to be able to work the problems *without* looking at the answers. Understanding what makes *Pride and Prejudice* a great novel is not the same as being able to write a great novel yourself. The same can be said of mechanisms. If you find you have to look at the answer to solve a problem, be sure that you work the problem again a few days later. Remember, you will have to work problems like these on exams. If you cannot solve them at home without looking at the answers, how do you expect to solve them on exams when the answers are no longer available?

This book assumes you have studied (and retained) the material covered in two semesters of introductory organic chemistry. You should have a working familiarity with hybridization, stereochemistry, and ways of representing organic structures. You do not need to remember specific reactions from introductory organic chemistry, although it will certainly help. If you find that you are weak in certain aspects of introductory organic chemistry or that you don't remember some important concepts, you should go back and review that material. There is no shame in needing to refresh your memory occasionally. Scudder's *Electron Flow in Organic Chemistry*, 2nd ed. (Wiley, 2013) provides basic information supplemental to the topics covered in this book.

This book definitely does not attempt to teach specific synthetic procedures, reactions, or strategies. Only rarely will you be asked to *predict* the products of a particular reaction. This book also does not attempt to teach physical organic chemistry (i.e., how mechanisms are proven or disproven in the laboratory). Before you can learn how to determine reaction mechanisms experimentally, you must learn what qualifies as a reasonable mechanism in the first place. Isotope effects, Hammett plots, kinetic analysis, and the like are all left to be learned from other textbooks.

Errors occasionally creep into any textbook, and this one is no exception. I have posted a page of errata at this book's Web site (<http://www.uky.edu/~rbgros1/textbook.html>). If you find an error that is not listed there, please contact me (robert.grossman@uky.edu). In gratitude and as a reward, you will be immortalized on the Web page as an alert and critical reader.

Graduate students and advanced undergraduates in organic, biological, and medicinal chemistry will find the knowledge gained from a study of this book invaluable for both their graduate careers, especially cumulative exams, and their professional work. Chemists at the bachelor's or master's level who are working in industry will also find this book very useful.

Lexington, KY, USA
March 2019

Robert B. Grossman

Preface: To the Instructor

Intermediate organic chemistry textbooks generally fall into two categories. Some textbooks survey organic chemistry rather broadly, providing some information on synthesis, some on drawing mechanisms, some on physical organic chemistry, and some on the literature. Other textbooks cover either physical organic chemistry or organic synthesis in great detail. There are many excellent textbooks in both of these categories, but as far as I am aware, there are only a handful of textbooks that teach students how to write a reasonable mechanism for an organic reaction. Carey and Sundberg, *Advanced Organic Chemistry, Part A*, 5th ed. (Springer, 2007), Lowry and Richardson's *Mechanism and Theory in Organic Chemistry*, 3rd ed. (Addison Wesley, 1987), and Carroll's *Perspectives on Structure and Mechanism in Organic Chemistry*, 2nd ed. (Wiley, 2014), are all physical organic chemistry textbooks. They teach students the experimental basis for elucidating reaction mechanisms, not how to draw reasonable ones in the first place. March's *Advanced Organic Chemistry*, 7th ed. (Wiley, 2013) by Smith provides a great deal of information on mechanism, but its emphasis is synthesis, and it is more a reference book than a textbook. Scudder's *Electron Flow in Organic Chemistry*, 2nd ed. (Wiley, 2013) is an excellent textbook on mechanism, but it is suited more for introductory organic chemistry than for an intermediate course. Edenborough's *Writing Organic Reaction Mechanisms: A Step by Step Approach*, 2nd ed. (CRC Press, 1998) is a good self-help book, but it does not lend itself to use in an American context. Savin's *Writing Reaction Mechanisms in Organic Chemistry*, 3rd ed. (Elsevier, 2014) is the textbook most closely allied in purpose and method to the present one. This book provides an alternative to Savin and to Edenborough.

Existing textbooks usually fail to show how common mechanistic steps link seemingly disparate reactions, or how seemingly similar transformations often have wildly disparate mechanisms. For example, substitutions at carbonyls and nucleophilic aromatic substitutions are usually dealt with in separate chapters in other textbooks, despite the fact that the mechanisms are essentially identical. This textbook, by contrast, is organized according to mechanistic types, not according to overall transformations. This rather unusual organizational structure, borrowed from Savin, is better suited to teaching students how to draw reasonable mechanisms than the more traditional structures, perhaps because the all-important first steps of mechanisms are usually more closely related to the conditions under which

the reaction is executed than they are to the overall transformation. The first chapter of the book provides general information on such basic concepts as Lewis structures, resonance structures, aromaticity, hybridization, and acidity. It also shows how nucleophiles, electrophiles, and leaving groups can be recognized, and it provides practical techniques for determining the general mechanistic type of a reaction and the specific chemical transformations that need to be explained. The following five chapters examine polar mechanisms taking place under basic conditions, polar mechanisms taking place under acidic conditions, pericyclic reactions, free-radical reactions, and transition-metal-mediated and -catalyzed reactions, giving typical examples and general mechanistic patterns for each class of reaction along with practical advice for solving mechanism problems.

This textbook is *not* a physical organic chemistry textbook! The sole purpose of this textbook is to teach students how to come up with reasonable mechanisms for reactions that they have never seen before. As most chemists know, it is usually possible to draw more than one reasonable mechanism for any given reaction. For example, both an S_N2 and a single electron transfer mechanism can be drawn for many substitution reactions, and either a one-step concerted or a two-step radical mechanism can be drawn for [2 + 2] photocycloadditions. In cases like these, my philosophy is that the student should develop a good command of simple and generally sufficient reaction mechanisms before learning the modifications that are necessitated by detailed mechanistic analysis. I try to teach students how to draw reasonable mechanisms by *themselves*, not to teach them the “right” mechanisms for various reactions.

Another important difference between this textbook and others is the inclusion of a chapter on the mechanisms of transition-metal-mediated and -catalyzed reactions. Organometallic chemistry has pervaded organic chemistry in the past few decades, and a working knowledge of the mechanisms of such reactions as metal-catalyzed hydrogenation, Suzuki couplings, and olefin metathesis is absolutely indispensable to any self-respecting organic chemist. Many organometallic chemistry textbooks discuss the mechanisms of these reactions, but the average organic chemistry student may not take a course on organometallic chemistry until fairly late in his or her studies, if at all. This textbook is the first on organic mechanisms to discuss these very important topics.

In all of the chapters, I have made a great effort to show the forest for the trees and to demonstrate how just a few concepts can unify disparate reactions. This philosophy has led to some unusual pedagogical decisions. For example, in the chapter on polar reactions under acidic conditions, protonated carbonyl compounds are depicted as carbocations in order to show how they undergo the same three fundamental reactions (addition of a nucleophile, fragmentation, and rearrangement) that other carbocations undergo. This philosophy has led to some unusual organizational decisions, too. $S_{RN}1$ reactions and carbene reactions are treated in the chapter on polar reactions under basic conditions. Most books on mechanism discuss $S_{RN}1$ reactions at the same time as other free-radical reactions, and carbenes are usually discussed at the same time as carbocations, to which they bear some similarities. I decided to locate these reactions in the chapter on polar reactions

under basic conditions because of the book's emphasis on teaching practical methods for drawing reaction mechanisms. Students cannot be expected to look at a reaction and know immediately that its mechanism involves an electron-deficient intermediate. Rather, the mechanism should flow naturally from the starting materials and the reaction conditions. $S_{\text{RN}}1$ reactions usually proceed under strongly basic conditions, as do most reactions involving carbenes, so these classes of reactions are treated in the chapter on polar reactions under basic conditions. However, Favorskii rearrangements are treated in the chapter on pericyclic reactions, despite the basic conditions under which these reactions occur, to emphasize the pericyclic nature of the key ring contraction step.

Stereochemistry is not discussed in great detail, except in the context of the Woodward–Hoffmann rules. Molecular orbital theory is also given generally short shrift, again except in the context of the Woodward–Hoffmann rules. I have found that students must master the basic principles of drawing mechanisms before additional considerations such as stereochemistry and MO theory are loaded onto the edifice. Individual instructors might wish to put more emphasis on stereoelectronic effects and the like as their tastes and their students' abilities dictate.

I agonized a good deal over which basic topics should be covered in the first chapter. I finally decided to review a few important topics from introductory organic chemistry in a cursory fashion, reserving detailed discussions for common misconceptions. A basic familiarity with Lewis structures and electron-pushing is assumed. I rely on Weeks's excellent workbook, *Pushing Electrons*, 4th ed. (Cengage, 2014), to refresh students' electron-pushing abilities. If Weeks fails to bring students up to speed, an introductory organic chemistry textbook should probably be consulted.

I have written the book in a very informal style. The second person is used pervasively, and an occasional first-person pronoun creeps in, too. Atoms and molecules are anthropomorphized constantly. The style of the book is due partly to its evolution from a series of lecture notes, but I also feel strongly that anthropomorphization and exhortations addressed directly to the student aid greatly in pushing students to think for themselves. I vividly remember my graduate physical organic chemistry instructor asking, "What would you do if *you* were an electron?", and I remember also how much easier mechanisms were to solve after he asked that question. The third person and the passive tense certainly have their place in scientific writing, but if we want to encourage students to take intellectual control of the material themselves, then maybe we should stop talking about our theories and explanations as if they were phenomena that happened only "out there" and instead talk about them as what they are: our best attempts at rationalizing the bewildering array of phenomena that Nature presents to us.

I have not included references in this textbook for several reasons. The primary literature is full of reactions, but the mechanisms of these reactions are rarely drawn, and even when they are, it is usually in a cursory fashion, with crucial details omitted. Moreover, as stated previously, the purpose of this book is not to teach students the "correct" mechanisms, it is to teach them how to draw *reasonable* mechanisms using their own knowledge and some basic principles and

mechanistic types. In my opinion, references in this textbook would serve little or no useful pedagogical purpose. However, some general guidance as to where to look for mechanistic information is provided at the end of the book. All of the chapters in this book except for the one on transition-metal-mediated and catalyzed reactions can be covered in a one-semester course.

The present third edition of this book has some improvements over the second edition. For example, I no longer draw two-center, three-electron bonds as intermediates in reactions involving electron transfer. (On the other hand, physical organic chemists will be distressed to learn that I have retained the use of $C\pm$ to indicate a singlet carbene.) I have colored all of the electron-flow arrows blue and added color judiciously elsewhere, and I believe these changes make the drawings significantly easier to read. I have also added more discussion of the mechanisms of some common biological reactions, and I have added a new section on C–H activation reactions in the chapter on reactions of transition metals.

I would like to thank all those readers who alerted me to errors in the second edition of this book and who made suggestions about what to add in the third edition. I would also like to thank my colleagues and students here at the University of Kentucky and at companies and universities across the country and around the world for their enthusiastic embrace of the previous editions of this book. Their response was unexpected and overwhelming. I hope they find this new edition equally satisfactory.

Lexington, KY, USA
March 2019

Robert B. Grossman

Contents

1 The Basics	1
1.1 Structure and Stability of Organic Compounds	1
1.1.1 Conventions of Drawing Structures. Grossman's Rule	2
1.1.2 Lewis Structures. Resonance Structures	4
1.1.3 Molecular Shape. Hybridization	11
1.1.4 Aromaticity	15
1.2 Brønsted Acidity and Basicity	18
1.2.1 pK_a Values	18
1.2.2 Tautomerism	21
1.3 Kinetics and Thermodynamics	22
1.4 Getting Started in Drawing a Mechanism	25
1.4.1 Reading and Balancing Organic Reaction Equations	25
1.4.2 Determining Which Bonds Are Made and Broken in a Reaction	26
1.5 Classes of Overall Transformations	28
1.6 Classes of Mechanisms	30
1.6.1 Polar Mechanisms	31
1.6.2 Free-Radical Mechanisms	45
1.6.3 Pericyclic Mechanisms	48
1.6.4 Transition-Metal-Catalyzed and -Mediated Mechanisms	49
1.7 Summary	50
1.8 Problems	51
2 Polar Reactions Under Basic Conditions	61
2.1 Introduction to Substitution and Elimination	61
2.1.1 Substitution by the S_N2 Mechanism	63
2.1.2 β -Elimination by the E2 and E1cb Mechanisms	66
2.1.3 Predicting Substitution Versus Elimination	69
2.2 Addition of Nucleophiles to Electrophilic π Bonds	72
2.2.1 Addition to Carbonyl Compounds	72
2.2.2 Conjugate Addition. The Michael Reaction	83

2.3	Substitution at $C(sp^2)-X$ σ Bonds	86
2.3.1	Substitution at Carbonyl C	86
2.3.2	Substitution at Alkenyl and Aryl C	93
2.3.3	Metal Insertion, Halogen–Metal Exchange	98
2.4	Substitution and Elimination at $C(sp^3)-X$ σ Bonds, Part II	100
2.4.1	Substitution by the $S_{RN}1$ Mechanism	100
2.4.2	Substitution by the Elimination–Addition Mechanism	102
2.4.3	Substitution by the One-Electron Transfer Mechanism	103
2.4.4	Metal Insertion, Halogen–Metal Exchange	104
2.4.5	α -Elimination. Generation and Reactions of Carbenes	105
2.5	Base-Promoted Rearrangements	109
2.5.1	Migration from C to C	110
2.5.2	Migration from C to O	112
2.5.3	Migration from C to N	113
2.5.4	Migration from B to C or O	114
2.6	Two Multistep Reactions	114
2.6.1	The Swern Oxidation	115
2.6.2	The Mitsunobu Reaction	116
2.7	Summary	118
2.8	Problems	121
3	Polar Reactions Under Acidic Conditions	131
3.1	Carbocations	131
3.1.1	Carbocation Energy	132
3.1.2	Carbocation Generation. The Role of Protonation	136
3.1.3	Typical Reactions of Carbocations. Rearrangements	139
3.2	Substitution and β -Elimination Reactions at $C(sp^3)-X$	145
3.2.1	Substitution by the S_N1 and S_N2 Mechanisms	145
3.2.2	β -Elimination by the E1 Mechanism	149
3.2.3	Predicting Substitution Versus Elimination	151
3.3	Electrophilic Addition to Nucleophilic $C=C$ π Bonds	151
3.4	Substitution at Nucleophilic $C=C$ π Bonds	154
3.4.1	Electrophilic Aromatic Substitution	154
3.4.2	Diazonium Ions	161
3.4.3	Electrophilic Aliphatic Substitution	163
3.5	Nucleophilic Addition to and Substitution at Electrophilic π Bonds	164
3.5.1	Heteroatom Nucleophiles	164
3.5.2	Carbon Nucleophiles	170
3.6	Catalysis Involving Iminium Ions	175
3.7	Summary	182
3.8	Problems	183

4	Pericyclic Reactions	193
4.1	Introduction	193
4.1.1	Classes of Pericyclic Reactions	193
4.1.2	Polyene MOs	200
4.2	Electrocyclic Reactions	202
4.2.1	Typical Reactions	202
4.2.2	Stereospecificity	210
4.2.3	Stereoselectivity	216
4.3	Cycloadditions	218
4.3.1	Typical Reactions	218
4.3.2	Regioselectivity	233
4.3.3	Stereospecificity	235
4.3.4	Stereoselectivity	242
4.4	Sigmatropic Rearrangements	247
4.4.1	Typical Reactions	247
4.4.2	Stereospecificity	254
4.4.3	Stereoselectivity	259
4.5	Ene Reactions	264
4.6	Summary	268
4.7	Problems	270
5	Free-Radical Reactions	283
5.1	Free Radicals	283
5.1.1	Stability	283
5.1.2	Generation from Closed-Shell Species	286
5.1.3	Typical Reactions	292
5.1.4	Chain Versus Nonchain Mechanisms	300
5.2	Chain Free-Radical Reactions	301
5.2.1	Substitution Reactions	301
5.2.2	Addition and Fragmentation Reactions	306
5.3	Nonchain Free-Radical Reactions	316
5.3.1	Photochemical Reactions	317
5.3.2	Reductions and Oxidations with Metals	319
5.3.3	Cycloaromatizations	328
5.4	Miscellaneous Radical Reactions	329
5.4.1	1,2-Anionic Rearrangements. Lone Pair Inversion	329
5.4.2	Triplet Carbenes and Nitrenes	330
5.5	Summary	332
5.6	Problems	332
6	Transition-Metal-Mediated and -Catalyzed Reactions	341
6.1	Introduction to the Chemistry of Transition Metals	341
6.1.1	Conventions of Drawing Structures	342
6.1.2	Counting Electrons	343

6.1.3	Typical Reactions	348
6.1.4	Stoichiometric Versus Catalytic Mechanisms	355
6.2	Addition Reactions	356
6.2.1	Late-Metal-Catalyzed Hydrogenation and Hydrometallation (Pd, Pt, Rh)	356
6.2.2	Hydroformylation (Co, Rh)	359
6.2.3	Hydrozirconation (Zr)	360
6.2.4	Alkene Polymerization (Ti, Zr, Sc, and Others)	361
6.2.5	Cyclopropanation, Epoxidation, and Aziridination of Alkenes (Cu, Rh, Mn, Ti)	363
6.2.6	Dihydroxylation and Aminohydroxylation of Alkenes (Os)	365
6.2.7	Nucleophilic Addition to Alkenes and Alkynes (Hg, Pd)	368
6.2.8	Conjugate Addition Reactions (Cu)	370
6.2.9	Reductive Coupling Reactions (Ti, Zr)	371
6.2.10	Pauson–Khand Reaction (Co)	375
6.2.11	Dötz Reaction (Cr)	377
6.2.12	Metal-Catalyzed Cycloaddition and Cyclotrimerization (Co, Ni, Rh)	380
6.3	Substitution Reactions	384
6.3.1	Hydrogenolysis (Pd)	384
6.3.2	Carbonylation of Alkyl Halides (Pd, Rh)	385
6.3.3	Heck Reaction (Pd)	388
6.3.4	Metal-Catalyzed Nucleophilic Substitution Reactions: Kumada, Stille, Suzuki, Negishi, Buchwald–Hartwig, Sonogashira, and Ullmann Reactions (Ni, Pd, Cu)	389
6.3.5	Allylic Substitution (Pd, Ir)	394
6.3.6	Pd-Catalyzed Nucleophilic Substitution of Alkenes. Wacker Oxidation	396
6.3.7	C–H Activation Reactions (Pd, Ru, Rh)	398
6.3.8	Tebbe Reaction (Ti)	400
6.3.9	Propargyl Substitution in Co-Alkyne Complexes	401
6.4	Rearrangement Reactions	402
6.4.1	Alkene Isomerization (Rh)	402
6.4.2	Olefin and Alkyne Metathesis (Ru, W, Mo, Ti)	402
6.5	Elimination Reactions	405
6.5.1	Oxidation of Alcohols (Cr, Ru)	405
6.5.2	Decarbonylation of Aldehydes (Rh)	406
6.6	Summary	406
6.7	Problems	407

7 Mixed-Mechanism Problems	415
A Final Word	421
Index	423

1.1 Structure and Stability of Organic Compounds

If science is a language that is used to describe the universe, then Lewis structures, the sticks, dots, and letters that are used to represent organic compounds, are the vocabulary of organic chemistry, and reaction mechanisms are the stories that are told with that vocabulary. As with any language, it is necessary to learn how to use the organic chemistry vocabulary properly in order to communicate one's ideas. The rules of the language of organic chemistry sometimes seem capricious or arbitrary; for example, you may find it difficult to understand why RCO_2Ph is shorthand for a structure with one terminal O atom, whereas RSO_2Ph is shorthand for a structure with two terminal O atoms, or why it is so important that \leftrightarrow and not \rightleftharpoons be used to indicate resonance. But organic chemistry is no different in this way from languages such as English, French, or Chinese, which all have their own capricious and arbitrary rules, too. (Have you ever wondered why I, you, we, and they walk, while he or she walks?) Moreover, just as you need to do if you want to make yourself understood in English, French, or Chinese, you must learn to use proper organic chemistry grammar and syntax, no matter how tedious or arbitrary it is, if you wish to make yourself clearly understood when you tell stories about (i.e., draw mechanisms for) organic reactions. The first section of this introductory chapter should reacquaint you with some of the rules and conventions that are used when organic chemistry is "spoken". Much of this material will be familiar to you from previous courses in organic chemistry, but it is worth reiterating.

Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_1) contains supplementary material, which is available to authorized users.

1.1.1 Conventions of Drawing Structures. Grossman's Rule


When organic structures are drawn, the H atoms attached to C are usually omitted. (On the other hand, H atoms attached to heteroatoms are *always* shown.) It is extremely important for you not to forget that they are there!

Common error alert: *Don't lose track of the undrawn H atoms.* There is a big difference between isobutane, the *t*-butyl radical, and the *t*-butyl cation, but if you lose track of your H atoms you might confuse the two. For this reason, I have formulated what I modestly call Grossman's rule: **Always draw all bonds and all hydrogen atoms near the reactive centers.** The small investment in time required to draw the H atoms will pay huge dividends in your ability to draw the mechanism.

It's easy to confuse these structures ...



... but it's much more difficult to confuse these!



Abbreviations are often used for monovalent groups that commonly appear in organic compounds. Some of these are shown in Table 1.1. *Aryl* may be phenyl, a substituted phenyl, or a heteroaromatic group like furyl, pyridyl, or pyrrolyl. *Tosyl* is shorthand for *p*-toluenesulfonyl, *mesyl* is shorthand for methanesulfonyl, and *triflyl* is shorthand for trifluoromethanesulfonyl. TsO^- , MsO^- , and TfO^- are abbreviations for the common leaving groups tosylate, mesylate, and triflate, respectively.

Common error alerts: *Don't confuse Ac (one O) with AcO (two O atoms), or Ts (two O atoms) with TsO (three O atoms).* Also don't confuse Bz (benzoyl) with Bn (benzyl). (One often sees Bz and Bn confused even in the literature.)





Table 1.1 Common abbreviations for organic substructures


Me	methyl	CH_3-	Ph	phenyl	C_6H_5-
Et	ethyl	CH_3CH_2-	Ar	aryl	(<i>see text</i>)
Pr	propyl	$\text{CH}_3\text{CH}_2\text{CH}_2-$	Ac	acetyl	$\text{CH}_3\text{C}(=\text{O})-$
<i>i</i> -Pr	isopropyl	$\text{Me}_2\text{CH}-$	Bz	benzoyl	$\text{PhC}(=\text{O})-$
Bu, <i>n</i> -Bu	butyl	$\text{CH}_3\text{CH}_2\text{CH}_2\text{CH}_2-$	Bn	benzyl	PhCH_2-
<i>i</i> -Bu	isobutyl	$\text{Me}_2\text{CHCH}_2-$	Ts	tosyl	$4\text{-Me}(\text{C}_6\text{H}_4)\text{SO}_2-$
<i>s</i> -Bu	<i>sec</i> -butyl	$(\text{Et})(\text{Me})\text{CH}-$	Ms	mesyl	CH_3SO_2-
<i>t</i> -Bu	<i>tert</i> -butyl	$\text{Me}_3\text{C}-$	Tf	triflyl	CF_3SO_2-

Sometimes the ways that formulas are written in texts confuse students. The more important textual representations are shown below.




Common error alert: *It is especially easy to misconstrue the structure of a sulfone (RSO₂R) as being analogous to that of an ester (RCO₂R).*

Conventions for the representation of stereochemistry are also worth noting. A *heavy* or *bold* bond indicates that a substituent is pointing *toward* you, out of the plane of the paper. A *hashed* bond indicates that a substituent is pointing *away* from you, behind the plane of the paper. Sometimes a *dashed* line is used for the same purpose as a hashed line, but the predominant convention is that a dashed line designates a partial bond (as in a transition state), not stereochemistry. A *wavy* line indicates that there is a mixture of *both* stereochemistries at that stereocenter, i.e., that the substituent is pointing toward you in some fraction of the sample and away from you in the other fraction. A *plain* line is used when the stereochemistry is unknown or irrelevant.



Bold and hashed lines may be drawn either in tapered (wedged) or untapered form. The predominant convention is that tapered lines show *absolute* stereochemistry, whereas untapered lines show *relative* stereochemistry. European and U.S. chemists generally differ on whether the thick or thin end of the tapered hashed line should be at the substituent. Bear in mind that these conventions for showing stereochemistry are not universally followed! A particular author may use a dialect that is different from the standard.



1.1.2 Lewis Structures. Resonance Structures

The concepts and conventions behind Lewis structures were covered in your previous courses, and there is no need to recapitulate them here. One aspect of drawing Lewis structures that often creates errors, however, is the proper assignment of formal charges. A formal charge on any atom is calculated as follows:

$$\begin{aligned} \text{formal charge} &= (\text{valence electrons of element}) \\ &\quad - (\text{number of } \pi \text{ and } \sigma \text{ bonds}) \\ &\quad - (\text{number of unshared valence electrons}) \end{aligned}$$

This calculation always works, but it is a bit ponderous. In practice, correct formal charges can usually be assigned just at a glance. Carbon atoms “normally” have four bonds, N three, O two, and halogens one, and atoms with the “normal” number of bonds do not carry a formal charge. Whenever you see an atom that has an “abnormal” number of bonds, you can immediately assign a formal charge. For example, a N atom with two bonds can immediately be assigned a formal charge of -1 . Formal charges for the common elements are given in Tables 1.2 and 1.3. It is very rare to find a nonmetal with a formal charge of ± 2 or greater, although the S atom occasionally has a charge of $+2$.

Table 1.2 Formal charges of even-electron atoms

Atom	1 bond	2 bonds	3 bonds	4 bonds
C		0*	+1 (no lp) [‡] -1 (one lp)	0
N, P	0**	-1	0	+1
O, S	-1	0	+1	0 or +2 [†]
Hal	0	+1		
B, Al			0 [‡]	-1

*Carbene

**Nitrene

[†]See inset below for discussion of S

[‡]has an empty orbital

lp = lone pair

Table 1.3 Formal charges of odd-electron atoms

Atom	0 bonds	1 bond	2 bonds	3 bonds
C				0
N, P			0	+1
O, S		0	+1	
Hal	0	+1		

The formal charges of quadruply bonded S can be confusing. A S atom with *two single bonds and one double bond* (e.g., DMSO, $\text{Me}_2\text{S}=\text{O}$) has one lone pair and no formal charge, but a S atom with *four single bonds* has no lone pairs and a formal charge of +2. A S atom with six bonds total has no formal charge and no lone pairs, as does a P atom with five bonds total. There is a more complete discussion of S and P Lewis structures in the next section.

Formal charges are called “formal” for a reason. They have more to do with the language that is used to describe organic compounds than they do with chemical reality. (Consider the fact that electronegative elements often have formal positive charges, as in NH_4^+ , H_3O^+ , and $\text{MeO}^+=\text{CH}_2$.) Formal charges are a very useful tool for ensuring that electrons are not gained or lost in the course of a reaction, but they are not a reliable guide to chemical reactivity. For example, both NH_4^+ and CH_3^+ have formal charges on the central atoms, but the reactivity of these two atoms is completely different.


To understand chemical reactivity, one must look away from formal charges and toward other properties of the atoms of an organic compound such as *electropositivity*, *electron-deficiency*, and *electrophilicity*.

- *Electropositivity* (or electronegativity) is a property of an element and is mostly independent of the bonding pattern of that element.
- An atom is *electron-deficient* if it lacks an octet of electrons in its valence shell (or, for H, a duet of electrons).
- An *electrophilic* atom is one that has an empty orbital that is relatively low in energy. (Electrophilicity is discussed in more detail later in this chapter.)

Common error alert: *The properties of electropositivity, electron-deficiency, electrophilicity, and formal positive charge are independent of one another and must not be confused.* The C and N atoms in CH_3^+ and NH_4^+ both have formal positive charges, but the C atom is electron-deficient, and the N atom is not. The C and B atoms in $\cdot\text{CH}_3$ and BF_3 are both electron-deficient, but neither is formally charged. B is electropositive and N is electronegative, but BH_4^- and NH_4^+ are both stable ions, as the central atoms are electron-sufficient. The C atoms in $^+\text{CH}_3$, CH_3I , and $\text{H}_2\text{C}=\text{O}^+$ are all electrophilic, but only the C in $^+\text{CH}_3$ is electron-deficient. The O atom in $\text{MeO}^+=\text{CH}_2$ has a formal positive charge, but the C atoms are electrophilic, not O.

For each σ bonding pattern, there are often several ways in which π and non-bonding electrons can be distributed. These different ways are called *resonance structures*. Resonance structures are alternative descriptions of a single compound. Each resonance structure has some contribution to the real structure of the compound, but no one resonance structure is the true picture. Letters and lines and dots are words in a language that has been developed to describe molecules, and, as in any language, sometimes one word is inadequate, and several different words must be used to give a complete picture of the structure of a molecule. The fact that resonance structures have to be used at all is an artifact of the language used to describe chemical compounds.

The true electronic picture of a compound is a weighted average of the different resonance structures that can be drawn (*resonance hybrid*). The weight assigned to each resonance structure is a measure of its importance to the description of the compound. The *dominant resonance structure* is the structure that is weighted most heavily. Two descriptions are shown to be resonance structures by separating them with a double-headed arrow (\leftrightarrow). **Common error alert:** *The double-headed arrow is used only to denote resonance structures. It must not be confused with the symbol for a chemical equilibrium (\rightleftharpoons or \rightleftharpoons) between two or more different species.* Again, resonance structures are alternative descriptions of a single compound. There is no going “back and forth” between resonance structures as if there were an equilibrium. Do not even think of it that way!



Low-energy resonance structures of a compound provide better descriptions of the compound’s electronic nature than do high-energy resonance structures. The rules for evaluating the stability of resonance structures are the same as those for any other Lewis structure.

1. No first-row atom (B, C, N, O) can have more than eight electrons in its valence shell. (The octet rule is less sacred for heavier main group elements such as P and S, and it does not hold at all for transition metals.)
2. **Common error alert:** *Resonance structures in which all atoms are surrounded by an octet of electrons are almost always lower in energy than resonance structures in which one or more atoms are electron-deficient.* However, if there are electron-deficient atoms, they should be electropositive (C, B), not electronegative (N, O, halogen).
3. Resonance structures with charge separation are usually higher in energy than those in which charges can be neutralized.
4. If charge is separated, then electronegative atoms should gain the formal negative charge and electropositive ones should gain the formal positive charge.


These rules are listed in order of importance. For instance, consider $\text{Me}\overset{\oplus}{\text{O}}\text{--}\overset{\oplus}{\text{C}}\text{H}_2 \leftrightarrow \text{Me}\overset{\oplus}{\text{O}}=\overset{\oplus}{\text{C}}\text{H}_2$. The second resonance structure is more important to the description of the ground state of this compound, because it is more important that all atoms have an octet (rule 2) than that the more electropositive element C has the formal positive charge instead of O (rule 4). As another example, consider $\text{Me}_2\text{C}=\text{O} \leftrightarrow \text{Me}_2\overset{\oplus}{\text{C}}\text{--}\overset{\ominus}{\text{O}} \leftrightarrow \text{Me}_2\overset{\oplus}{\text{C}}\text{--}\overset{\oplus}{\text{O}}$. The third structure is unimportant, because an electronegative element is made electron-deficient. The second structure is less important than the first one, because the second one has charge separation (rule 3) and an electron-deficient atom (rule 2). Nevertheless, the second structure does

contribute *somewhat* toward the overall description of the ground state electronic structure of acetone.

Resonance structures are almost universally defined by organic chemists as structures differing only in the placement of π bonds and lone pairs. The σ network remains unchanged. If the σ networks of two structures differ, then the structures represent *isomers*, not alternative resonance descriptions.

How do you generate a resonance structure of a given Lewis structure?

- Look for an electron-deficient atom next to a lone-pair-bearing atom. The lone pair can be shared with the electron-deficient atom as a new π bond. Note the changes in formal charge when pairs of electrons are shared! Also note that the atom accepting the new bond must be *electron-deficient*.




Common error alert: A formal positive charge is irrelevant to whether an atom can accept a new bond.

The electron-flow arrow convention is used to show how electrons in one resonance structure can be moved around to generate a new resonance structure. Electron-flow arrows are entirely a formalism; electrons do not actually move from one location to another, because the real compound is a weighted average of the different resonance structures, not an equilibrium mixture of different resonance structures. Electron-flow arrows help you not to lose or gain electrons as you draw different resonance structures.

- Look for an electron-deficient atom *adjacent to* a π bond. The electrons in the π bond can be moved to the electron-deficient atom to give a new π bond, and the distal atom of the former π bond then becomes electron-deficient. Again, note the changes in formal charges!




- Look for a radical *adjacent to* a π bond. The lone electron and one electron in the π bond can be used to make a new π bond. The other electron of the π bond goes to the distal atom to give a new radical. There are no changes in formal charges.




Half-headed arrows (fishhooks) are used to show the movement of single electrons.

- Look for a lone pair *adjacent* to a π bond. Push the lone pair toward the π bond, and push the π bond onto the farther atom to make a new lone pair. The atom with the lone pair may or may not have a formal negative charge.



When lone pairs of heteroatoms are omitted in structural drawings, a formal negative charge on a heteroatom can double as a lone pair. Thus, an electron-flow arrow will often begin at a formal negative charge rather than at a lone pair.

- In aromatic compounds, π bonds can often be moved around to generate a new resonance structure that has no change in the total number of bonds, lone pairs or unpaired electrons, electron-deficient atoms, or formal charges but that is nevertheless not the same structure.




- The two electrons of a π bond can be divided evenly or unevenly between the two atoms making up that bond, i.e., $A=B \leftrightarrow \overset{+}{A}-\overset{-}{B} \leftrightarrow \overset{-}{A}-\overset{+}{B} \leftrightarrow \overset{+}{A}-\overset{-}{B}$. The process usually generates a higher energy structure. In the case of a π bond between two different atoms, push the pair of electrons in the π bond toward the more electronegative of the two.



Two other important rules to remember when drawing resonance structures are the following:

- A lone pair or empty orbital cannot interact with a π bond to which it is orthogonal, i.e., perpendicular. The resonance structures in such cases often look hopelessly strained.




- Two resonance structures *must* have the same number of electrons (and atoms, for that matter). The formal charges in both structures must add up to the same number.


Common error alerts:

- *Tetravalent C or N atoms (i.e., quaternary ammonium salts) have no lone pairs or π bonds, so they do not participate in resonance.*
- *Electronegative atoms like O and N must have their octet. Whether they have a formal positive charge is not an issue. Like banks with money, electronegative atoms are willing to share their electrons, but they will not tolerate electrons being taken away.*


An electronegative atom is happy to share its electrons, even if it gains a formal positive charge...



... and it can give up a pair of electrons if it gets another pair from another source...




... but it will not give up a pair of electrons entirely, because then it would become electron-deficient.




- *If you donate one or two electrons to an atom that already has an octet, regardless of whether it has a formal positive charge, another bond to that atom must break. For example, in nitrones ($\text{PhCH}=\overset{+}{\text{N}}\text{R}-\overset{-}{\text{O}}$) the N atom has its octet. A lone pair from O can be used to form a new $\text{N}=\text{O}$ π bond only if the electrons in the $\text{C}=\text{N}$ π bond leave N to go to C, i.e., $\text{PhCH}=\overset{+}{\text{N}}\text{R}-\overset{-}{\text{O}} \leftrightarrow \text{PhCH}-\overset{+}{\text{N}}\text{R}=\overset{-}{\text{O}}$. In the second resonance structure, N retains its octet and its formal positive charge.*

- In bridged bicyclic compounds, a π bond between a bridgehead atom and its neighbor is forbidden due to ring strain unless one of the rings of the bicyclic compound has more than eight or nine atoms (Bredt's rule). Resonance structures in which such a π bond exists are very poor descriptions of the compound.

Problem 1.1 Which of the two resonance structures is a better description of the ground state of the following compound?



Problem 1.2 Draw as many reasonable resonance structures for each of the following compounds as you can.




The second-best resonance structure often provides the key to understanding the chemical behavior of that compound. For example, the second-best resonance structure for acetone tells you that the carbonyl C is slightly electron-deficient and susceptible to attack by electron-rich species. This point will be revisited later.

In general, the more low-energy resonance structures a compound has, the lower its energy.

The ability to look at one structure and see its resonance structures is extremely important for drawing organic reaction mechanisms. If you require it, Chaps. 1–3 of Daniel P. Weeks, *Pushing Electrons*, 4th ed. (Cengage, 2014), can help you acquire the necessary practice.


Compounds with a terminal O attached to S or P are fairly common in organic chemistry. Resonance structures in which S and P have extended the capacity of their valence shells (using relatively low energy 3d orbitals) to accommodate more than eight electrons are often written for these compounds. The extended-shell description can be very confusing; for example, DMSO (below) seems to be analogous to acetone, but the S in DMSO has a lone pair, whereas the C in acetone is moderately electron-deficient. The dipolar resonance structures are a better description of the ground state of these compounds, but old habits die hard among organic chemists. In any case, when you see S=O or P=O “ π ” bonds, be aware that the valence shell may have been extended beyond eight electrons and that you may not be looking at a conventional π bond.




1.1.3 Molecular Shape. Hybridization

Molecules are three-dimensional objects, and as such they have shapes. You must always keep the three-dimensional shapes of organic compounds when you draw reaction mechanisms. Often something that seems reasonable in a flat drawing will manifest itself as totally unreasonable when the three-dimensional nature of the reaction is considered, and vice versa.

*This tricyclic compound
looks horribly strained...*



*... until you look at its
three-dimensional structure!*




Organic chemists use the concept of atom *hybridization* to rationalize and understand molecular shape. The concept of hybridization is itself a strange hybrid of Lewis theory and molecular orbital (MO) theory, and there are serious questions about its basis in reality. Nevertheless, organic chemists use hybridization almost universally to rationalize structure and reactivity, because it is easy to understand and apply, and because it works!

Before hybridization is discussed, a brief review of the basics of MO theory is in order. The following discussion is meant to be a quick, qualitative recap, not a comprehensive treatment.


Electrons do not orbit nuclei like planets around a star, as one early theory of the nucleus proposed. A better analogy is that electrons around a nucleus are like a cloud of gnats buzzing around one's head on a summer day. To carry the analogy further, it is not possible to locate one gnat and define its location precisely; instead, one can only describe the likelihood of finding a gnat at a particular distance from one's mouth or nostrils. Likewise, the position of particular electrons cannot be defined; instead, a mathematical function called an *orbital* describes the *probability* of finding an electron of a certain energy in a particular region of space. The actual probability is given by the *square* of the value of the orbital at a particular point in space.

The atoms with which organic chemists are most concerned (C, N, O) have four valence *atomic orbitals* (AOs), one *s* and three *p* orbitals, each of which can contain no, one, or two electrons. Electrons in the valence *s* orbital of an atom are lower in energy than electrons in the valence *p* orbitals. The *s* orbital is spherical, whereas

p orbitals are dumbbell-shaped and mutually perpendicular (*orthogonal*; i.e., they do not overlap). A p orbital has two *lobes*; in the mathematical function that defines these orbitals, one lobe has a value less than zero (negative), and the other has a value greater than zero (positive). (These arithmetical values should not be confused with charge.)




Each p orbital describes a distribution of electrons centered around an x -, y -, or z -axis, so the three p orbitals are mutually perpendicular, but when the three p orbitals are squared and added together, a spherical distribution of electrons is again described.




Heavier elements may also have valence d and f orbitals. They need not concern you here.

When two atoms are close in space, the energies and probability distributions of the electrons on each atom change in response to the presence of the other nucleus. The AOs, which describe the electrons' probability distribution and energies, are simply mathematical functions, so the *interaction* of two spatially proximate AOs is expressed by arithmetically adding and subtracting the AO functions to generate two new functions, called *molecular orbitals* (MOs). The additive (in-phase) combination of AOs, a *bonding MO*, is lower in energy than either of the two starting AOs. The subtractive (out-of-phase) combination, an *antibonding MO*, is higher in energy than either of the two starting AOs. In fact, the destabilization of the antibonding MO is greater than the stabilization of the bonding MO.



Why must two AOs interact in both a constructive and a destructive manner? The physical reality is that two individual AOs describe the distribution of four electrons in space. When two individual AOs interact, the resulting equations must *still* describe the distribution of four electrons in space. Two AOs, therefore, interact to give two MOs, three AOs interact to give three MOs, and so on.

When two AOs interact, if each AO has one electron, both electrons can go into the bonding MO. Because the total energy of the electrons is lower than it was in the separated system, a *chemical bond* is now present where there was none before. In contrast, if each AO is full, then two electrons go into the bonding MO and two into the antibonding MO; the total energy of the electrons is increased, the atoms repel one another, and no bond is formed.




The valence electrons of any element in the main-group block reside in the four valence AOs. For example, a C atom has four valence electrons. One of these electrons can go into each valence orbital. The four half-filled AOs can then interact with four AOs from other atoms to form four bonds. Oxygen, by contrast, has six valence electrons. It has only two half-filled orbitals, so it makes only two bonds.

This simple picture is incomplete, though. Consider CH_4 . If C used one s and three p AOs to make four bonds to H, one would expect that one of the C–H bonds would be different from the other three. This is not the case, though: most measures of molecular properties of CH_4 indicate that all four bonds are exactly equivalent. Why is this? Because all four bonding orbitals in CH_4 are equivalent, and the four AOs of C are simply mathematical functions, organic chemists hypothesize that the four AOs are “averaged”, or *hybridized*, to make four new, equivalent AOs called sp^3 hybrid orbitals (because each one consists of one part s and three parts p). The four original AOs together describe a spherical distribution of electrons, so when this sphere is divided into four equal sp^3 orbitals, a *tetrahedral* array of four orbitals is created.

sp^2 hybrid orbital:
large lobe is used in bonding



Tetrahedral array of sp^3 orbitals
(back lobes omitted for clarity)




The AOs can be hybridized in other ways, too. One s and two p AOs can be averaged to give *three* new hybrid orbitals and *one unchanged* p orbital; this procedure is called sp^2 hybridization. Alternatively, one s and one p AO can be

averaged to give *two* new hybrid orbitals and *two unchanged* p orbitals; this procedure is called *sp hybridization*. In summary, the characteristics of the three kinds of hybridization are as follows:

- sp^3 hybridization: The s and all three p orbitals are averaged to make four sp^3 orbitals of equal energy. The four orbitals point to the four corners of a tetrahedron and are 109° apart. The energy of each sp^3 orbital is three-fourths of the way from the energy of the s AO to the energy of a p AO.
- sp^2 hybridization: The s and two p orbitals are averaged to make three sp^2 orbitals of equal energy, and one p orbital is left unchanged. The three hybrid orbitals point to the three corners of an equilateral triangle and are coplanar and 120° apart; the unhybridized p orbital is perpendicular to the plane of the hybrid orbitals. The energy of each sp^2 orbital is two-thirds of the way from the energy of the s AO to the energy of a p AO.
- sp hybridization. The s and one p orbital are averaged to make two sp orbitals of equal energy, and two p orbitals are left unchanged. The sp orbitals point 180° apart from each other. The two unhybridized p orbitals are perpendicular to each other and to the line containing the sp orbitals. The energy of each sp orbital is halfway between the energy of the s AO and the energy of a p AO.


h = hybrid orbital.
 p^+ and p^- = lobes of p orbitals.
 Back lobes of hybrid orbitals omitted for clarity.



The drawings of hybrid orbitals shown are simplistic. The sp^3 , sp^2 , and sp orbitals do not actually have identical shapes. Better pictures of the actual shapes of these orbitals can be found in Lowry & Richardson, *Mechanism and Theory in Organic Chemistry*, 3rd ed. (Addison Wesley, 1987).

The hybridization of an atom is determined as follows. Hybrid orbitals are used to make σ bonds and to hold lone pairs *not* used in resonance; p orbitals are used to make π bonds, to hold lone pairs used in resonance, and as empty orbitals. To determine the hybridization of an atom, add up the number of lone pairs not used in resonance and the number of σ bonds (i.e., atoms to which it is bound). If the sum is four, the atom is sp^3 -hybridized. If the sum is three, it is sp^2 -hybridized. If the sum is two, it is sp -hybridized.

Problem 1.3 Determine the hybridization of the C, N, and O atoms in each of the following compounds. (The black dot in the center of the final structure indicates a C atom.)




It is important to remember to think about the p orbitals as well as the hybrid orbitals when you think about the hybridization of an atom. It is also important to remember that the hybridization of an atom affects its properties and reactivity! This point will be illustrated many times in the future.

1.1.4 Aromaticity


A decrease or increase in energy is associated with a compound that has a *cyclic* array of continuously overlapping p orbitals. Such a compound may have a ring with alternating single and multiple bonds, or the ring may contain both alternating π bonds and one or more atoms with a lone pair or an empty orbital. If the number of pairs of electrons in the cyclic array of orbitals is odd, then the compound is especially low in energy (as compared to the corresponding acyclic system with two additional H atoms), and it is said to be *aromatic*. If the number of pairs of electrons is even, then the compound is especially high in energy, and it is said to be *antiaromatic*. If there is no cyclic array of continuously overlapping p orbitals, then the question of aromaticity does not apply, and the compound is *nonaromatic*.

The simplest case of an aromatic compound is benzene. Each of the C atoms in benzene is sp^2 -hybridized, so each has a p orbital pointing perpendicular to the plane of the ring. The six p orbitals make a cyclic array. Each C atom contributes one electron to its p orbital, so there is a total of three pairs of electrons in the system. Because three is odd, benzene is aromatic. In fact, benzene is about 30 kcal/mol lower in energy than 1,3,5-hexatriene, its acyclic analog.




There are many aromatic hydrocarbons other than benzene. Many are made up of fused benzene rings. All have an odd number of pairs of electrons in a cyclic array of orbitals.


Some aromatic hydrocarbons:



naphthalene



phenanthrene



azulene

Furan, thiophene, pyrrole, and pyridine are all examples of heterocyclic aromatic compounds (heteroaromatic compounds). The heteroatoms in some of these compounds (furan, thiophene, pyrrole) contribute one lone pair to the aromatic system, whereas in others (pyridine) they contribute none. You can determine how many lone pairs a heteroatom contributes to the aromatic system by examining the effect of lone pair donation on the hybridization of the heteroatom. For example, if the N atom of pyridine used its lone pair to participate in resonance, it would have to be sp -hybridized (one p orbital required for the $N=C$ π bond, one for the lone pair used in resonance), but sp hybridization requires 180° bond angles, which is not possible in this compound. Therefore, the N atom must be sp^2 -hybridized, and the N lone pair must be in a hybrid orbital that is orthogonal to the cyclic array of p orbitals. In pyrrole, by contrast, if the N atom uses its lone pair in resonance, the N atom must be sp^2 -hybridized, which is reasonable. Therefore, there is a cyclic array of p orbitals in pyrrole occupied by six electrons (two from each of the $C=C$ π bonds, and two from the N lone pair), and pyrrole is aromatic.

Some aromatic heterocycles:



furan



thiophene



pyrrole



imidazole




pyridine


Problem 1.4 What is the hybridization of the O atom in furan? In what kind of orbitals do the lone pairs reside? How many lone pairs are used in resonance?

As is true with aromatic hydrocarbons, aromatic heterocyclic compounds are often fused with other aromatic hydrocarbons or heterocycles to make larger aromatic compounds. Some of these compounds are very important in biology and synthetic and materials chemistry.


Some polycyclic aromatic heterocycles:




indole



purine




benzothiazole



isoquinoline


Certain charged compounds are aromatic also. The electron-deficient C atom in the tropylium and cyclopropenium ions is sp^2 -hybridized and has an empty p orbital. The tropylium ion has a cyclic array of seven p orbitals containing three pairs of electrons, and the cyclopropenium ion has a cyclic array of three p orbitals containing one pair of electrons, and therefore both ions are aromatic. (Note that cyclopropene itself is nonaromatic, because it doesn't have a cyclic array of p orbitals!) Similarly, the lone pair-bearing C atom in the cyclopentadienide anion is sp^2 -hybridized so that the lone pair can be used in resonance; as a result, the cyclopentadienide anion has a cyclic array of five p orbitals containing three pairs of electrons, and it is aromatic, too.

Some aromatic ions:




Antiaromatic compounds are especially high in energy compared with their acyclic analogs. Cyclobutadiene is isolable only in an inert matrix at very low temperatures. In 1,4-dihydropyrazine, the two N-based lone pairs combine with the two C=C π bonds to create an eight-electron system that is particularly high in energy. The cyclopentadienyl cation is particularly high in energy, too, as there are only two pairs of electrons in the cyclic array of five p orbitals (including the empty p orbital from the electron-deficient C). However, cyclooctatetraene, which at first glance appears to be antiaromatic, avoids antiaromaticity by bending into a tub shape so that its p orbitals do not overlap continuously.

Some antiaromatic compounds:



Some compounds have partial aromatic or antiaromatic character due to the presence of a minor aromatic or antiaromatic resonance structure. Tropone (cycloheptatrienone) is much lower in energy than one would expect from a highly unsaturated ketone because its $\overset{+}{C}=\overset{-}{O}$ resonance structure is aromatic. On the other hand, cyclopentadienone is extremely high in energy because its $\overset{+}{C}=\overset{-}{O}$ resonance structure is antiaromatic.




To give you an idea of how strong the energy-lowering effect of aromaticity can be, consider 1,3-pentadiene and 1,3-cyclopentadiene. Both compounds are nonaromatic. Deprotonation of 1,3-pentadiene gives a nonaromatic compound, but deprotonation of 1,3-cyclopentadiene gives an aromatic compound. The acidity of cyclopentadiene ($pK_a = 15$) is about *20 orders of magnitude* greater than that of 1,3-pentadiene and is about the same as that of water. The establishment of an aromatic ring where there was none before provides an important driving force for many organic reactions.

The energy-lowering effect of aromaticity is greatest when the number of electron pairs is small. Naphthalene, a ten-electron aromatic system, is not lowered in energy as much as benzene, a six-electron aromatic system. Also, all-carbon systems are lowered in energy more than those with heteroatoms such as N, O, or S.

1.2 Brønsted Acidity and Basicity

An acid-base reaction involves the transfer of a proton H^+ from a Brønsted acid to a Brønsted base. Some examples of some acid-base reactions follow:



A few points should be noted. (1) Bases may be anionic or neutral, and acids may be neutral or cationic. (2) The acid–base reaction is an equilibrium. The equilibrium may lie far to one side or the other, but it is still an equilibrium. (3) There is both an acid and a base on *both* sides of the equilibrium. (4) This equilibrium is not to be confused with resonance. (5) Proton transfer reactions are usually very fast, especially when the proton is transferred from one heteroatom to another. **Common error alert:** *The proton H^+ is not to be confused with the hydrogen atom (or radical) $H\cdot$ or the hydride ion H^- .*

1.2.1 pK_a Values

Acidities are quantified by pK_a values. The pK_a of an acid HX is defined as:

$$pK_a = -\log\left(\frac{[H^+][X^-]}{[HX]}\right)$$

The larger the pK_a , the less acidic the compound. It is important that you develop a sense of the pK_a values of different classes of compounds and how variations in structure affect the pK_a . It is especially important for you to memorize the starred numbers in Table 1.4 in order for you to have a sense of relative acidities and basicities.

Table 1.4 Approximate pK_a values for some organic acids in H_2O

CCl_3CO_2H	0	$EtOH$	*17
CH_3CO_2H	*4.7	CH_3CONH_2	17
$pyrH^+$	*5	$t-BuOH$	19
$PhNH_3^+$	5	CH_3COCH_3	*20
$HC\equiv N$	9	$CH_3SO_2CH_3$	23
$N\equiv CCH_2CO_2Et$	9	$HC\equiv CH$	*25
Et_3NH^+	*10	CH_3CO_2Et	*25
$PhOH$	10	CH_3CN	26
CH_3NO_2	10	CH_3SOCH_3	31
$EtSH$	11	NH_3	*35
$MeCOCH_2CO_2Et$	11	$C_6H_6, H_2C=CH_2$	*37
$EtO_2CCH_2CO_2Et$	*14	$CH_3CH=CH_2$	37
HOH	*15	Alkanes	*40–44
Cyclopentadiene	*15		

Note pyr = pyridine

You will sometimes see other pK_a values cited for certain compounds, especially alkanes. The pK_a of a compound changes dramatically with solvent, and it also depends on temperature and method of measurement. Approximate differences between acidities matter when organic reaction mechanisms are drawn, so the values given here suffice for the purposes of this text. For a more detailed discussion of acidity, see any physical organic chemistry textbook.

When comparing the acidity of two different elements in similar compounds (or in two parts of the same compound), use the following trends, which are listed in decreasing order of importance.

- All else being equal, acidity *increases* as you go *down* the periodic table (cf. $EtOH$ with $EtSH$) and size increases. This trend is opposite that for electronegativity. The trend is due to the increasingly poor overlap of the very small H (*s*) orbital with the increasingly large valence orbital of the atom to which it is bound. **Common error alert:** *Overlap effects come into play only when the acidic proton is directly attached to the heteroatom. Otherwise, inductive effects dominate.*
- All else being equal, acidity *increases* as you move to the *right* in the periodic table (cf. H_3CH , H_2NH , HOH), as electronegativity increases.

When comparing the acidity of the same element in two similar compounds (or in two parts of the same compound), use the following trends, which are listed in decreasing order of importance.

- All else being equal, a given atom is usually more acidic when it bears a formal positive charge than when it is neutral (cf. NH_4^+ with NH_3). However, it is *not* true that all positively charged acids are more acidic than all neutral acids (cf.

R_3NH^+ with CH_3CO_2H). Conversely, an atom is usually more basic when it bears a formal negative charge than when it is neutral.

- Nonaromatic HA is much more acidic if its conjugate base is *aromatic* than nonaromatic HA whose conjugate base is *nonaromatic* (cf. 1,3-cyclopentadiene to propene). Conversely, a substance is a very poor base if protonation results in loss of aromaticity (e.g., pyrrole). The magnitude of these effects can be enormous.
- HA is much more acidic when the lone pair of the conjugate base can participate in resonance (cf. PhOH with EtOH, $PhNH_3^+$ with Et_3NH^+ , and $\underline{C}H_3CH=CH_2$ with alkanes). HA is *especially* acidic when the lone pair can be delocalized into a carbonyl group, and even more so when it can be delocalized into two carbonyl groups (cf. alkanes, CH_3COCH_3 , and $EtO_2CCH_2CO_2Et$). The most common anion-stabilizing group is the C=O group, but nitro groups ($-NO_2$) and sulfonyl groups ($-SO_2R$) are also very good at stabilizing anions (cf. CH_3NO_2 , CH_3COCH_3 , and $CH_3SO_2CH_3$). Nitro groups are even more anion-stabilizing than carbonyl groups because of a greater inductive effect.
- For a given atom A, acidity *increases* with *increased s character* of the A–H bond; that is, $A(sp)-H$ is more acidic than $A(sp^2)-H$, which is more acidic than $A(sp^3)-H$ (cf. $pyrH^+$ with R_3NH^+ and $HC\equiv CH$, benzene, and alkanes). The lone pair of the conjugate base of an sp -hybridized atom is in a lower energy orbital than that of an sp^3 -hybridized atom.
- The acidity of HA increases when inductively electron-withdrawing groups are attached to A and decreases when inductively electron-donating groups are attached to A (cf. CCl_3CO_2H with CH_3CO_2H , and HOH with EtOH).
- For uncharged acids, acidity *decreases* with *increased steric bulk* (cf. EtOH with *t*-BuOH). As the conjugate base becomes more hindered, the ability of the solvent to organize itself around the base to partly neutralize the charge by dipolar effects or hydrogen bonds becomes increasingly compromised. As a result, the conjugate base becomes higher in energy, and the acid becomes weaker.

An inductive effect is often cited as the reason why *t*-BuOH is less acidic than EtOH. In fact, in the gas phase, where solvation plays no role, *t*-BuOH is *more* acidic than EtOH. Solvent effects play a very important role in determining acidity in the liquid phase, where most chemists work, but they are often ignored because they are difficult to quantify.


Common error alert: *The rate of proton transfer from an acid to a base is not perceptibly slowed by steric hindrance.* The attenuation of acidity by steric bulk is a ground-state, thermodynamic effect.

You can use these principles and the tabulated acidity constants to make an educated guess about the pK_a of a compound that you haven't seen before. It is important to know pK_a values because the first step in an organic reaction is often a proton transfer, and you need to know which proton in a compound is most likely to be removed.

Carbonyl compounds are perhaps the most important acidic organic compounds, so it is worth pointing out some of the factors that make them more or less acidic.

The energy of a carbonyl compound is largely determined by the energy of its $R_2\overset{+}{C}-\overset{-}{O}$ resonance structure. The greater the ability of a group R to stabilize this resonance structure by lone pair donation, hyperconjugation, or inductive effects, the lower in energy the carbonyl compound is. The $\overset{+}{C}-\overset{-}{O}$ resonance structure, though, is much less important in the corresponding enolates, and as a result, most enolates have approximately the same energy. Since the acidity of a compound is determined by the difference in energy between its protonated and deprotonated forms, it turns out that acidities of carbonyl compounds correlate very well with their energies: *the lower in energy a carbonyl compound is, the less acidic it is.* (This correlation is not true of all compounds.) Thus, the order of increasing acidity is, carboxylates < amides < esters < ketones < aldehydes < acyl anhydrides < acyl chlorides.

Common error alert: α,β -Unsaturated carbonyl compounds are not particularly acidic at the α -carbon atoms. The C=O π bond prefers to be in conjugation and coplanar with the C=C π bond, so the C-H σ orbital does not overlap with the C=O π orbital. An unfavorable conformational change is required before deprotonation of the α -C can even begin. Note that the low acidity of α,β -unsaturated carbonyl compounds as compared with their saturated congeners is an exception to the general rule that $C(sp^2)$ is more acidic than $C(sp^3)$, all else being equal.




It is often more convenient to talk about basicities than acidities. In this textbook, the pK_b of a base is defined as the pK_a of its conjugate acid.¹ For example, according to this book's definition, NH_3 has a pK_b of 10 (because NH_4^+ has a pK_a of 10) and a pK_a of 35. The strength of a base correlates directly with the weakness of its conjugate acid. Factors that increase acidity decrease basicity, and factors that decrease acidity increase basicity. For example, EtS^- is less basic than EtO^- , just as $EtSH$ is more acidic than $EtOH$.

1.2.2 Tautomerism

When a base deprotonates acetone (CH_3COCH_3), a compound is obtained that has a lone pair and a formal negative charge on C. One can draw a resonance structure for

¹This definition differs from the standard one that $pK_b = 14 - pK_a(\text{conjugate acid})$. (The 14 derives from the dissociation constant of H_2O .) The standard definition is much less convenient than the one used here, because it requires that you learn two different numbering systems for what is essentially the same property. However, be careful not to use this book's definition in a different context; you are likely to be misunderstood.

this compound in which the lone pair and formal negative charge are on O. The true structure of the anion, of course, is a weighted average of these two resonance structures. If this anion reacts with H^+ , the H atom may bind to either O or C. If the H atom binds to C, acetone is obtained again, but if it attaches to O, a compound (an *enol*) is obtained that differs from acetone only in the position of attachment of the H atom and the associated π system. Acetone and the enol are called *tautomers*.




Tautomers are isomers. They have different σ -bond networks, which clearly distinguishes them from resonance structures. The most important kinds of tautomers are carbonyl–enol tautomers, as in the preceding example. Tautomerization is a chemical equilibrium that occurs very rapidly in acidic or basic media; it should not be confused with resonance, which is not an equilibrium at all.

1.3 Kinetics and Thermodynamics

Energies and rates are important aspects of reaction mechanisms. A reaction might be described as favorable or unfavorable, fast or slow, and reversible or irreversible. What does each of these terms mean?


A *favorable* reaction is one for which the *free energy* (ΔG°) is less than zero (the free energy of the products is lower than the free energy of the starting materials). When $\Delta G^\circ > 0$, the reaction is *unfavorable*. The free energy of a reaction is related to the *enthalpy* (ΔH°) and *entropy* (ΔS°) of that reaction by the equation $\Delta G^\circ = \Delta H^\circ - T\Delta S^\circ$. In practice, enthalpies, not free energies, are usually used to determine whether a reaction is favorable or unfavorable, because ΔH° is easier to measure and because $T\Delta S^\circ$ is small compared to ΔH° for most reactions at ordinary temperatures ($< 100^\circ\text{C}$). A reaction with $\Delta H^\circ < 0$ is *exothermic*; one with $\Delta H^\circ > 0$ is *endothermic*.



Of course, starting materials have to go through an energy barrier to become products; if there were no barrier, they could not exist! The energy required for the starting materials to reach the top of the barrier is called the *activation energy* (ΔG^\ddagger).


The arrangement of the reactants at the top of the barrier, where they can go either backward to starting materials or forward to products, is called the *transition state* (TS). The *rate* of a reaction is dependent on the size of the activation barrier, *not* on the energy difference between the starting materials and the products. A reaction is fast if the activation energy is low, and it is slow if the activation energy is high.

Common error alert: *The rate of a reaction (depends on ΔG^\ddagger) and the overall energetics of a reaction (depends on ΔG°) are independent of one another.* It is possible to have a fast, unfavorable reaction or a slow, favorable reaction. An example of the former is the addition of water to the π bond of acetone to give the hydrate. An example of the latter is the reaction of gasoline with O_2 to give CO_2 and water at room temperature. The energy of the products does *not necessarily* influence the activation energy of a reaction.



A reaction is in equilibrium when the rate of the forward reaction equals the rate of the reverse reaction. Such a reaction is *reversible*. In principle, all reactions are reversible, but in fact, some reactions have equilibria that lie so far to the right that no starting material can be detected at equilibrium. As a rule of thumb, if the equilibrium constant (K) is 10^3 or greater, then the reaction is irreversible. Reactions can also be made to proceed irreversibly in one direction by removing a gaseous, insoluble, or distillable product from the reaction mixture (LeChâtelier's principle). When starting materials and products or two different products are in equilibrium, their ratio is determined by the difference in free energy between them. However, if an equilibrium is not established, then their ratio may or may not be related to the difference in free energy.


Common error alert: *If a reaction can give two products, the product that is obtained most quickly (the kinetic product) is not necessarily the product that is lowest in energy (the thermodynamic product).* For example, maleic anhydride reacts with furan to give a tricyclic product. If the progress of this reaction is monitored, it is seen that initially the more sterically crowded, higher energy *endo* product is obtained, but as time goes on this product is converted into the less crowded, lower energy *exo* product. The reason that the kinetic product goes away with time is that it is in equilibrium with the starting materials and with the thermodynamic product; the equilibrium, once established, favors the lower energy product. However, there are numerous cases in which a kinetic product is *not* in equilibrium with the thermodynamic product, and the latter is not observed. In other cases, the thermodynamic product is also the one that is obtained most quickly. One of the joys of organic chemistry is designing conditions under which only the kinetic or only the thermodynamic product is obtained.



In the preceding example, initially, equal amounts of kinetic and thermodynamic products are obtained. However, if the energy in the system is sufficiently high, the kinetic product can establish an equilibrium with the starting materials and eventually convert completely to the thermodynamic product.

Many reactions proceed through unstable, high-energy intermediates with short lifetimes (e.g., carbocations). An *intermediate* is a valley in the reaction coordinate diagram. It is not to be confused with a TS, a peak in the reaction coordinate diagram. Transition states do not exist for longer than one molecular vibration and therefore cannot be isolated, whereas intermediates may last anywhere from five molecular vibrations to milliseconds to minutes. Some reactions proceed through no intermediates, whereas others proceed through many.

It is very hard to get information about TSs, because they do not exist for more than about 10^{-14} s, but information about TSs is extremely important in thinking about relative rates and the like. The Hammond postulate states that a TS structurally resembles whichever of the two ground-state species (starting materials, intermediates, or products) immediately preceding and following is higher in energy. The higher energy the species, the more it resembles the TS. For example, consider the reaction of isobutylene with HCl. This reaction proceeds through a high-energy intermediate, the carbocation. The rate-limiting step is formation of the carbocation. The Hammond postulate says that the energy of the TS leading to the carbocation is directly related to the energy of that carbocation; therefore, the rate of the reaction is related to the energy of the carbocation.




Common error alert: *The Hammond postulate relates the structure and energy of the higher energy of the two ground state species immediately preceding and following the TS to the structure and energy of the TS.* For this reason, the TS of an exothermic reaction is not easily compared with the products of that reaction, because in an exothermic reaction the products are lower in energy than the starting materials.

The term *stable* is ambiguous in organic chemistry parlance. When a compound is said to be “stable”, it sometimes means that it has low energy (G°), i.e., is thermodynamically stable, and it sometimes means that the barrier for its conversion to other species is high (ΔG^\ddagger), i.e., is kinetically stable. For example, both benzene and tetra-*t*-butyltetrahedrane are surprisingly stable. The former is both kinetically and thermodynamically stable, whereas the latter is kinetically stable and thermodynamically unstable. Certain kinds of compounds, like hemiacetals, are kinetically unstable and thermodynamically stable. In general, “stable” usually means “kinetically stable,” but you should always assure yourself that that is what is meant. When in doubt, ask.


1.4 Getting Started in Drawing a Mechanism

1.4.1 Reading and Balancing Organic Reaction Equations

Three features of the way organic reactions are written sometimes make it difficult for students to figure out what is going on. First, compounds written over or under the arrow are sometimes stoichiometric reagents, sometimes catalysts, and sometimes just solvents. Second, organic reactions are often not balanced. “Little” things like salts, water, or gaseous coproducts are often omitted from the right side of the equation (but usually not the left). Balancing an unbalanced equation will often help you determine the overall reaction, and knowing the overall reaction may narrow your choice of mechanisms. Third, the product written on the right side of the equation is usually the product that is obtained *after aqueous workup*. Aqueous workup converts ionic products into neutral ones, usually by protonation or deprotonation. Be aware of these conventions.



When reagents are separated by a semicolon, it means that the first reagent is added and allowed to react, then the second reagent is added and allowed to react, and so on. When reagents are numbered sequentially, it may mean the same, or it may mean that the reaction mixture is worked up, and the product is isolated, after each individual step is executed.




1.4.2 Determining Which Bonds Are Made and Broken in a Reaction

A chemical reaction involves changes in bonding patterns, so probably the most important step when sitting down to draw a mechanism is *to determine which bonds are made and broken* in the course of the reaction. You can do this very easily as follows: Number all atoms other than H in the starting materials as sequentially as possible; then identify the same atoms in the products, using atom sequences and bonding patterns and minimizing the number of bonding changes. Remember to number carbonyl O atoms and both O atoms of esters, and *obey Grossman's rule!* Looking at the number of H atoms attached to certain C atoms in starting materials and products often helps you figure out how to number the atoms. Sometimes balancing the equation provides important numbering clues, too.


Many students are reluctant to take the time to number the atoms, but the importance of doing it cannot be overemphasized. If you do not number the atoms, you may not be able to determine which bonds are made and broken, and if you cannot do that, you cannot draw a mechanism! The time that you save by knowing which bonds are made and broken more than compensates for the investment of time in numbering the atoms.

Problem 1.5 Balance the following equations, and number all atoms other than H in the starting materials and products.

(a)




(b)



After you have numbered the atoms, make a list of σ bonds between non-H atoms that need to be made and σ bonds between non-H atoms that need to be broken. Do not list bonds to H that are made or broken, and do not list π bonds! This procedure will allow you to focus your attention only on what is important, i.e., the *changes* in bonding patterns that occur in going from starting material to product. Do not worry about the different appearances of starting material and product; all that matters are the changes in bonds between atoms. Products can sometimes look very different from starting materials when in fact only a few bonds have changed.


Problem 1.6 Make a list of all σ bonds made and broken between atoms other than H in the two preceding reactions.

Why should you not include π bonds in your list of bonds to make and break? The reason is that the location of the π bonds will follow naturally from where the σ bonds are made and broken. To illustrate the point, consider the tautomerization of acetone to the corresponding enol under basic conditions.



You might say that the important change in going from starting material to product is that the π bond migrates from C=O to C=C. It is true that the π bond

migrates, but this fact does not tell you what mechanistic steps you need to execute. If you consider only the σ bonds, though, you see that you need to make an O–H σ bond and break a C–H σ bond. Since the conditions are basic, the first step is likely to be that a base deprotonates the acidic C to give an enolate, thus cleaving the C–H σ bond. Then the basic O atom deprotonates EtOH, forming the new O–H σ bond. Once the appropriate σ bonds have been made and broken, the π bond has naturally migrated to the appropriate position.




Note how obeying Grossman's rule makes much clearer which σ bonds are made and broken in the reaction.

Why should you not include element–H σ bonds in your list of bonds to make and break, either? It is much easier to make and break element–H σ bonds than other kinds of σ bonds, especially in polar reactions, and you will usually make and break the necessary element–H σ bonds naturally on the way to making and breaking σ bonds between non-H atoms. After you have made and broken the σ bonds between non-H atoms, if you have not yet arrived at the product, *then* look at the σ bonds involving H atoms.


1.5 Classes of Overall Transformations

Organic chemistry would just be a vast collection of often seemingly contradictory information if there were no way of classifying reactions. One way to classify reactions is according to the relationships of the starting materials and the products, i.e., the overall transformation. There are four basic kinds of overall transformations: *addition*, *elimination*, *substitution*, and *rearrangement*.



- In an *addition* reaction, two starting materials combine to give a single product. Usually a π bond in one starting material is replaced by two new σ bonds.





- In an *elimination* reaction, one starting material is divided into two products. Usually two σ bonds in one starting material are replaced by a new π bond.



- In a *substitution* reaction, an atom or group that is σ -bound to the rest of the starting material is *replaced* by another σ -bound atom or group.



- In a *rearrangement*, one starting material gives one product with a different structure.



Some transformations constitute examples of more than one of these classes. For example, the reaction of esters with Grignard reagents gives alcohols in what is a substitution *and* an addition reaction. Remember that classification schemes are created by people. A compound does not stop and worry about whether a particular reaction fits within the boundaries of human classification schemes before it undergoes the reaction.

1.6 Classes of Mechanisms

A second way to classify reactions is according to the type of mechanism that is operative. The mechanism-based method of classification is used to organize the material in this text. However, it is important not to lose the forest (the overall transformation) for the trees (the mechanistic steps). Both classification methods have advantages, and it is useful to be able to move freely between them.

There are four basic types of organic reaction mechanisms—polar, free-radical, pericyclic, and metal-catalyzed.

- *Polar* reactions proceed by the movement of *pairs* of electrons from areas of high electron density (*nucleophiles*) to areas of low electron density (*electrophiles*), or from filled orbitals to empty orbitals. Polar mechanisms are further divided into those that proceed under basic conditions and those that proceed under acidic conditions.
- *Free-radical* reactions proceed by the movement of *single* electrons. New bonds are often formed using one electron from a half-filled orbital and another electron from a filled orbital. Free-radical reactions can be further divided into those that involve electron-transfer reagents, and those that do not; reactions in the latter group usually proceed by *chain mechanisms*.
- *Pericyclic* reactions are characterized by the movement of electrons in a circle. The substrates of pericyclic reactions are often singly or multiply unsaturated, and they may contain 1,2-dipoles.
- *Metal-mediated* and *metal-catalyzed* reactions require a transition metal. However, certain transition-metal complexes (e.g., TiCl_4 , FeCl_3) act only as Lewis acids in organic reactions, and others (TiCl_3 , SmI_2) act as one-electron reducing agents like Na and Li; reactions promoted by these compounds are classified in polar acidic, pericyclic, or free-radical classes.

The mechanism classification and the overall transformation classification are orthogonal to each other. For example, substitution reactions can occur by a polar acidic, polar basic, free-radical, pericyclic, or metal-catalyzed mechanism, and a reaction under polar basic conditions can produce an addition, a substitution, an elimination, or a rearrangement. Both classification schemes are important for determining the mechanism of a reaction, because knowing the class of mechanism and the overall transformation rules out certain mechanisms and suggests others. For example, under acidic conditions, aromatic substitution reactions take place by electrophilic addition–elimination. Under basic conditions, they usually take place by one of three mechanisms: nucleophilic addition–elimination, elimination–addition, or $\text{S}_{\text{RN}}1$. If you know the class of the overall transformation *and* the class of mechanism, your choices are narrowed considerably.

1.6.1 Polar Mechanisms

In polar reactions, *nucleophiles react with electrophiles*. Furthermore, polar reactions proceed under either acidic or basic conditions.

The terms “nucleophile” and “electrophile” are best used to describe specific atoms within compounds. Unfortunately, chemists sometimes use the terms sloppily to describe whole compounds. For example, a chemist may describe $\text{H}_2\text{C}=\text{O}$ as an electrophile, even though the compound contains both electrophilic (C) and nucleophilic (O) atoms.


The concepts of nucleophilicity and electrophilicity are most useful in understanding polar mechanisms, but they apply to free-radical and pericyclic mechanisms, too.

1.6.1.1 Nucleophiles

A *nucleophile* is a compound that has a relatively high energy pair of electrons available to make a new bond. A nucleophilic atom may be neutral or negatively charged. There are three classes of nucleophiles: lone-pair nucleophiles, σ -bond nucleophiles, and π -bond nucleophiles.

The division of nucleophiles into three types is completely artificial. Nature does not stop to consider whether a nucleophile is a π -bond nucleophile or a lone-pair nucleophile before a reaction proceeds. The distinctions are intended only to train you to spot nucleophilic atoms or functional groups with ease.


- *Lone-pair nucleophiles* contain atoms with lone pairs. The lone pair is used to make a new bond to an electrophilic atom. Alcohols (ROH), alkoxides (RO^-), amines (R_3N), metal amides (R_2N^-), halides (X^-), thiols (RSH), sulfides (R_2S), and phosphines (R_3P) are all examples of lone-pair nucleophiles, as are the O atoms of carbonyl compounds ($\text{X}_2\text{C}=\text{O}$). When these compounds act as nucleophiles, the formal charge of the nucleophilic atom *increases* by 1 in the product.



Electron-flow arrows are used to show the flow of electron density *from* the nucleophile to the electrophile. The base of the arrow should be at the pair of electrons used to make the new bond; if the nucleophile is negatively charged, the charge may substitute for the lone pair. The head of the arrow may point *either* to the electrophilic atom *or between* the two atoms where the new bond is formed.


- *Sigma-bond nucleophiles* contain a bond between a nonmetal and a metal. The electrons of the element–metal bond are used to form a bond to the electrophile.

The formal charge on the nucleophilic atom does not change; the metal increases its formal charge by 1. The nucleophilic atom may be a heteroatom (as in NaNH_2 or KOH), carbon (as in Grignard reagents (RMgBr), organolithium reagents (RLi), and Gilman reagents (R_2CuLi), which have C-Mg , C-Li , and C-Cu bonds, respectively), or hydrogen (as in the complex metal hydrides NaBH_4 and LiAlH_4).




The very polarized bond between a metal and a nonmetal, E-M , is often thought of as being like an ionic bond ($\text{E}^- \text{M}^+$); thus, $\text{PhC}\equiv\text{C-Li}$, $\text{H}_3\text{C-MgBr}$, and LiAlH_4 are sometimes drawn as $\text{PhC}\equiv\text{C}^-$, H_3C^- , and H^- , respectively. By this logic, σ -bond nucleophiles are actually lone-pair nucleophiles.


- *Pi-bond nucleophiles* use the pair of electrons in a π bond, usually a $\text{C}=\text{C}$ bond, to form a σ bond between one of the atoms in the π bond and the electrophilic atom. The formal charge and total electron count of the nucleophilic atom of the π bond do not change, but the other atom of the π bond is made *electron-deficient*, and its formal charge increases by 1. The π bonds of simple alkenes and arenes are weakly nucleophilic; π bonds that are directly attached to heteroatoms, such as in enolates ($\text{C}=\text{C-O}^-$), enols ($\text{C}=\text{C-OH}$), enol ethers ($\text{C}=\text{C-OR}$), and enamines ($\text{C}=\text{C-NR}_2$), are much better nucleophiles.



In principle, either of the $\text{C}(sp^2)$ atoms in an alkene may form a new bond to an electrophile. If the alkene is differentially substituted, though, one is usually more nucleophilic than the other. **Common error alert:** A nucleophilic alkene always reacts with an electrophile such that the carbon less able to be electron-deficient makes the new bond. In alkenes directly substituted with lone-pair-bearing heteroatoms (enolates, enamines, enols, enol ethers), the β -carbon (not attached to heteroatom) is nucleophilic, and the α -carbon (attached to heteroatom) is not. In alkenes substituted only with alkyl groups, the less substituted carbon is more nucleophilic, and the more substituted carbon becomes electron-deficient upon reaction of the π bond with an electrophile.



When one draws an electron-flow arrow that originates at a π bond, it is sometimes difficult to indicate clearly which atom of the π bond is acting as the nucleophile. For this reason, some chemists prefer to use the “Cambridge swoop,” in which the electron-flow arrow starts at the middle of the π bond, moves *away* from the electrophile, then comes back and crosses over the atom of the π bond that is acting as a nucleophile. Despite its greater clarity of meaning, however, the Cambridge swoop has not been adopted by a large number of organic chemists.




Different compounds have different nucleophilicities. The nucleophilicity of a compound is measured by determining how reactive it is toward CH_3Br in water or MeOH at 25°C . Nucleophilicity bears some relationship toward basicity, which measures reactivity toward H^+ , but there are important differences. CH_3Br is uncharged, relatively large, and has a relatively high energy LUMO (lowest unoccupied molecular orbital). The H^+ , on the other hand, is charged, tiny, and has a low-energy LUMO. Moreover, nucleophilicity (the rate of reaction with CH_3Br) is a *kinetic* property, whereas acidity (the equilibrium constant between protonated and unprotonated species) is a *thermodynamic* property. Because of these differences, some good bases are poor nucleophiles, and vice versa. Increases in basicity *generally* parallel increases in nucleophilicity, except in the following ways.

- Nucleophilicity *increases* as you go down the periodic table, whereas basicity *decreases*. Thus, I^- is a great nucleophile, whereas Cl^- is fair, and Et_2S is a very good nucleophile, whereas Et_2O is very poor. In the case of anions (e.g., I^- vs. Cl^-), the reason for the trend is that protic solvents such as MeOH (in which nucleophilicity is traditionally measured) can more strongly hydrogen-bond to


smaller anions, making them less nucleophilic. The evidence for this rationale is that in aprotic solvents and in the gas phase, Cl^- is actually slightly more nucleophilic (*and* more basic) than I^- . In the case of neutral nucleophiles (e.g., Et_2S vs. Et_2O), the lower electronegativity and the greater steric accessibility of the heavier atoms (because of the longer bond lengths) explain their greater nucleophilicity.

- Nucleophilicity *decreases dramatically* with increased crowding around the nucleophilic atom, whereas basicity *increases slightly*. So although EtO^- is both a good base ($\text{p}K_{\text{b}} = 17$) and a good nucleophile, $t\text{-BuO}^-$ is a better base ($\text{p}K_{\text{b}} = 19$) and a really awful nucleophile.
- Delocalization of a lone pair decreases both its basicity and nucleophilicity, but it decreases the basicity *more*. For example, EtO^- ($\text{p}K_{\text{b}} = 17$) reacts with *s*-BuBr at lower temperatures than AcO^- ($\text{p}K_{\text{b}} = 4.7$), but EtO^- acts mostly as a base to give 2-butene by an E2 elimination (Chap. 2), whereas AcO^- acts mostly as a nucleophile to give *s*-BuOAc by $\text{S}_{\text{N}}2$ substitution. AcO^- is both less basic and less nucleophilic than EtO^- , so it requires higher temperatures to react at all, but when it does react, the proportion of substitution product is greater, because AcO^- is much less basic and only somewhat less nucleophilic than EtO^- . Likewise, simple ester enolates ($\text{p}K_{\text{b}} = 25$) react with secondary alkyl halides such as *i*-PrBr at lower temperatures to give elimination primarily, whereas malonate anion ($\text{p}K_{\text{b}} = 14$) requires higher temperatures to react with *i*-PrBr, but the substitution product is obtained primarily.

EtO⁻ is both more basic and more nucleophilic than AcO⁻...




... but it is a lot more basic and only somewhat more nucleophilic ...




... so the proportion of nucleophilicity to basicity is greater for AcO^- than for EtO^- .

- The absence of hydrogen-bonding in *polar aprotic solvents* (particularly polar, liquid, nonviscous compounds that lack acidic protons) makes anions dissolved therein particularly reactive, and thus both their basicity and nucleophilicity increase, but their nucleophilicity increases more. For example, F^- is extremely unreactive in H_2O because it is so strongly solvated, but in DMSO it is


nucleophilic toward alkyl halides. Common polar aprotic solvents include DMSO, HMPA, DMF, DMA, NMP, DMPU, and pyridine, but not EtOH or H₂O. *Note:* For purposes of drawing mechanisms, it is much more important that you recognize that a particular solvent is polar aprotic than that you know its structure!



Nonnucleophilic bases play a special role in organic chemistry, and it is important to recognize some of the ones that are widely used: *t*-BuOK, LiN(*i*-Pr)₂ (LDA), LiN(SiMe₃)₂ (LiHMDS), KN(SiMe₃)₂ (KHMDS), NaH and KH, EtN(*i*-Pr)₂ (Hünig's base), and DBU. Most of these bases are quite hindered, except for DBU, which in fact has some nucleophilicity toward 1° alkyl halides, and the metal hydrides, which are nonnucleophilic for kinetic reasons. Again, it is more important that you remember the *properties* of these compounds than that you memorize their structures.




Sometimes it is hard to identify the nucleophilic sites in a compound. In this case, obey Meier's rule: **When in doubt, draw in all the lone pairs, and then draw resonance structures until the cows come home.** Often the second-best resonance structure for a compound shows where the nucleophilic sites are in that compound. For example, if resonance structures are drawn for anisole, it is easy to see why reaction with electrophiles always occurs at the ortho or para positions, never at the meta position. Incidentally, Meier's rule applies equally well to identifying electrophilic sites. Thus, you can easily see that acetone (Me₂C=O) is electrophilic at C when you draw its second-best resonance structure.




1.6.1.2 Electrophiles and Leaving Groups

An *electrophile* is a compound that has a relatively low energy empty orbital available for bond-making. An electrophile may be neutral or positively charged. There are three classes of electrophiles: Lewis-acid electrophiles, π -bond electrophiles, and σ -bond electrophiles.

- *Lewis-acid electrophiles* have an atom E that lacks an octet and has a low-energy nonbonding orbital, usually a p orbital. A pair of electrons from the nucleophile is used to form a new bond to E, giving it its octet. The formal charge of E *decreases* by one. Carbocations, boron compounds, and aluminum compounds are common Lewis-acid electrophiles.




- In *π -bond electrophiles*, the electrophilic atom E has an octet, but it is attached by a π bond to an atom or group of atoms that can accept a pair of electrons. Electrophiles of the π bond type commonly have C=O, C=N, or C \equiv N bonds, in which the less electronegative atom is the electrophilic one. C=C and C \equiv C bonds are electrophilic if they are attached to electrophilic atoms (see below). Miscellaneous π -bond electrophiles include SO₃ and RN=O. Certain cationic electrophiles can be classified as either the Lewis acid type or the π -bond type depending on whether the best or second-best resonance description is used (e.g., R₂C=OH⁺ \leftrightarrow R₂C⁺-OH; also, H₂C=N⁺Me₂, RC \equiv O⁺, O=N⁺=O, N \equiv O⁺). When a nucleophile attacks a π -bond electrophile, the π bond breaks, and the electrons move to the *other* atom of the π bond, which decreases its formal charge by 1.




- *Sigma-bond electrophiles* have the structure E-X. The electrophilic atom E has an octet, but it is attached by a σ bond to an atom or group of atoms X, called a *leaving group* (or *nucleofuge*), that wants to take the electrons in the E-X bond


away from E and leave to form an independent molecule. A nucleophile reacts with a σ -bond electrophile by using its pair of electrons to form a bond to the electrophilic atom E, increasing the nucleophile's formal charge by 1. At the same time, X departs with the pair of electrons from the E–X σ bond and decreases its formal charge by 1. There is no change in the overall electron count at E.



Sigma-bond electrophiles E–X can be further subdivided into three types: those where E is C, those where E is a heteroatom, and Brønsted acids, in which E is H. Sigma-bond electrophiles of the first class include alkyl halides, alkyl sulfonates and other pseudohalides, oxonium ions (e.g., $\text{Me}_3\text{COH}_2^+$), and sulfonium ions (e.g., Me_3S^+). Sigma-bond electrophiles of the first class may also undergo spontaneous cleavage of the C–X bond in the absence of a nucleophile to give a carbocation.



Common σ -bond electrophiles of the second class include Br_2 and other elemental halogens, peracids (RCO_3H ; the terminal O of the O–O bond is electrophilic), and RSX and RSeX (X is Br or Cl; S or Se is electrophilic). Sigma-bond electrophiles of the second class do not undergo spontaneous cleavage of the E–X bond because E is usually too electronegative to suffer electron-deficiency.



Heavily substituted halocarbons such as CBr_4 and Cl_3CCl_3 are also electrophilic, but at the halogens, not at C. Br_3C^- and $\text{Cl}_3\text{CCl}_2\text{C}^-$ are fairly good leaving groups—all that electron-withdrawing power stabilizes them—and the C atoms are so buried within all those large halogen atoms that a nucleophile can't possibly reach them.

Leaving groups differ in their *leaving group ability*. The ability of a leaving group to leave is quite closely related to the $\text{p}K_b$ of the group. *The less basic a leaving group is, the better is its leaving group ability*. In general, only excellent and good leaving groups (as defined in Table 1.5) leave at reasonable rates in $\text{S}_\text{N}2$

Table 1.5 Approximate order of leaving group ability

Excellent to good leaving groups	pK_b	Fair to poor leaving groups	pK_b
N_2	<-10	F^-	+3
$CF_3SO_3^-$ (TfO ⁻)	<-10	RCO_2^-	+5
I^-	-10	$^-C\equiv N$	+9
Br^-	-9	NR_3	+10
$ArSO_3^-$ (e.g., TsO ⁻)	-7	RS^-	+11
Cl^-	-7	Stabilized enolates	+9 to +14
RCO_2H	-6	HO^-	+15
$EtOH$	-2.5	EtO^-	+17
H_2O	-1.5	Simple enolates	+20 to 25
		R_2N^-	+35

substitution reactions. Fair and poor leaving groups can be expelled by a neighboring negative charge, as in addition–elimination reactions at carbonyl groups.


Common error alert: *The groups H^- , O^{2-} , and unstabilized carbanions are truly awful leaving groups and almost never leave!*

Looking at pK_b values will not always give you the right order of leaving group ability. For example, one can hydrolyze carboxamides ($RCONR_2$) with strong aqueous base, but one can't hydrolyze alkynyl ketones ($RCOC\equiv CR$), even though the pK_b of $^-NR_2$ is 35, and the pK_b of $RC\equiv C^-$ is 25. The solution to this apparent contradiction is that the N of the carboxamide is probably protonated before it leaves, so that the leaving group is not really $^-NR_2$ at all but is HNR_2 ($pK_b = 10$). For the same reason, the ability of ^-CN to leave is considerably lower (relative to heteroatom leaving groups) than its pK_b would indicate. The electrophile structure, the presence of metal counterions, and the nature of the reaction medium are also crucial factors in leaving group ability.

The relief of strain can increase the leaving ability of a group. For example, under basic conditions, the reactions of three-membered ring ethers (epoxides) with nucleophiles Nu^- to give $NuCH_2CHRO^-$ proceed readily, even though alkoxides are normally very bad leaving groups. By contrast, the reactions of five- or six-membered ring ethers with Nu^- do not proceed at all under the same conditions.

You may have noticed that $C=C$ π bonds can be either nucleophiles or electrophiles. How can you tell whether a particular alkene is nucleophilic or electrophilic? Alkenes are the chameleons of organic chemistry: how they react depends on what is attached to them. Alkenes or arenes that are attached to electrophilic groups such as $^-CR_2$, ^-COR , $^-CO_2R$, $^-C\equiv N$, $^-NO_2$, or $^-CH_2X$ (where X is a leaving group) are electrophilic. Alkenes or arenes that are attached to nucleophilic groups like $R\ddot{O}^-$, $R_2\ddot{N}^-$, or $^-CH_2MgBr$ are nucleophilic. Simple alkenes and arenes are nucleophilic also. **Common error alert:** *Alkenes and arenes that are substituted with electrophilic groups are electrophilic at the β -carbon (i.e., the C not attached to the electrophilic substituent), not at the α -carbon, because the electrons in the π bond need to end up on the α -carbon in order to interact with the*

electrophilic group. This pattern parallels what is seen for alkenes substituted with electron-donating groups, which are nucleophilic at the β -carbon.



Alkenes that are normally nucleophilic can act as electrophiles toward potent-enough nucleophiles, and alkenes that are normally electrophilic can act as nucleophiles toward potent-enough electrophiles. For example, alkyllithium compounds (RLi) add to the “nucleophilic” alkene ethylene, and the “electrophilic” alkene 2-cyclohexen-1-one adds Br₂ across its C=C π bond. These reactions provide additional support for describing alkenes as the chameleons of organic chemistry.

Common error alert: *Do not confuse formal positive charge with electrophilicity.* Consider CH₂= $\overset{+}{O}$ CH₃. The electronegative element O has a formal positive charge, but it is not electron-deficient, so there is no reason to think that it may be electrophilic. Now draw the resonance structure, H₂C⁺–OCH₃. O is neutral, the formal positive charge is on C, and C is electron-deficient. Considering the two resonance structures, which atom is more likely to be attacked by a nucleophile, C or O? The same considerations apply to Me₂N⁺=CH₂I⁻, Me₃O⁺BF₄⁻, and PhCH= $\overset{+}{N}$ (O)Ph. In general, a heteroatom that has an octet and that bears a formal positive charge is not electrophilic; any atom to which it is bound that is more electropositive is electrophilic. An archetypical example readily remembered by students is H₃O⁺. It has an O with a formal positive charge, and it is electrophilic at H.

Carbenes, a class of transient organic species, are formally both nucleophilic and electrophilic, although their electrophilicity dominates their reactivity. Carbenes are divalent, six-electron carbon compounds (CR₂) with one unshared pair of electrons. You can think of them as ±CR₂ or :CR₂. (No formal charge is implied by the ± symbol!) The best-known carbene is CCl₂, which is generated from CHCl₃ and strong base and is used to make dichlorocyclopropanes from alkenes. Carbon monoxide (:O=C: ↔ :O≡C⁺) and isocyanides (R– $\overset{+}{N}$ =C: ↔ R–N≡C⁻) can be described as especially stabilized carbenes. Carbenes are discussed in more detail in Chaps. 2 and 5.

1.6.1.3 Acidic and Basic Reaction Conditions; the pK_a Rule

The conditions under which polar reactions take place can almost always be described as either acidic or basic, and the characteristics of mechanisms that take place under these two sets of conditions are quite different. It is important that you

learn how to determine whether a polar reaction is proceeding under acidic or basic conditions. To determine what are the reaction conditions for a particular reaction, follow these steps *in the order in which they are written*:

1. If an acid is present, the reaction conditions are acidic. The following species are acids that you might typically encounter.
 - A proton, H^+ .
 - A mineral acid such HCl or H_2SO_4 .
 - A carboxylic acid RCO_2H such as HCO_2H , $\text{CH}_3\text{CO}_2\text{H}$ (AcOH), or $\text{CF}_3\text{CO}_2\text{H}$ (TFA).
 - A sulfonic acid RSO_3H such as MsOH , TsOH , CSA, or $\text{CF}_3\text{SO}_3\text{H}$ (TfOH).
 - An ammonium salt with an $^+\text{N}-\text{H}$ bond such as NH_4Cl or $\text{pyrH}^+ \text{TsO}^-$ (PPTS).
 - A Lewis acid such as BF_3 , AlCl_3 , TiCl_4 , ZnCl_2 , SnCl_4 , FeCl_3 , Ag(I) salts, a lanthanide salt such as $\text{Sc}(\text{OTf})_3$, or certain compounds with metal–carbon bonds in which the metal lacks its octet, such as Me_3Al , Et_2AlCl , and Et_2Zn .
2. If the reaction conditions are not acidic, they may be basic. Look for one of the following indicators of basic conditions.
 - Anions without their counterions specified, such as HO^- or ^-CN .
 - Alkali metal salts, such as NaOH , KCN , or LiCl . In these cases, the metal–nonmetal bond dissociates heterolytically, giving the metal cation and the nonmetal anion.
 - Compounds containing a bond between H and an electropositive metal such as NaH , NaBH_4 , and LiAlH_4 .
 - Compounds containing a bond between C and an electropositive metal such as in CH_3Li and PhMgBr , assuming you have not already identified the compound as a Lewis acid.
 - Uncharged amines, amidines, and similar compounds.
3. If none of the above indicators is present, but one of the products of the reaction is a strong acid such as a mineral acid or a sulfonic acid, then the reaction conditions are *covertly acidic*. (I use the term “covertly acidic” because the reaction equation usually omits the acid coproduct.) For example, Me_3CCl will react upon heating in MeOH to give MeOCMe_3 , and it will react upon heating in a polar aprotic solvent to give $\text{H}_2\text{C}=\text{CMe}_2$. Both reactions proceed under covertly acidic conditions, because in both cases, the reaction generates HCl as a coproduct.

4. If still, none of the above indicators is present, then look for a compound that contains a heavy atom, usually uncharged and aprotic, as in Me_2S or Ph_3P . If the reaction mixture contains such a compound, then you can consider the reaction conditions to be basic.


Common error alert: *Water and alcohols, by themselves, do not indicate either acidic or basic conditions.* Either can be present under acidic conditions or basic conditions.

Some nucleophiles are good bases, so they will not be available in reactions that proceed under acidic conditions; instead, under these conditions, they will just react with acid or H^+ to become much less nucleophilic. Conversely, some electrophiles are good acids, so they will not be available in reactions that proceed under basic conditions; instead, under these conditions, they will just react with a base to become much less acidic. As a result, different kinds of nucleophiles and electrophiles are typically seen under basic and acidic conditions.


- Lone-pair nucleophiles that are good bases (RO^- , $\text{RC}\equiv\text{C}^-$, RS^- , R_2N^-) can exist under basic conditions only, but weakly basic lone-pair nucleophiles (halides, RCO_2^- , RSO_3^- , R_2S , R_3P) can exist under either acidic or basic conditions. Water and alcohols can exist under either basic or acidic conditions, but under basic conditions, they are deprotonated before they react with an electrophile, whereas under acidic conditions, they are not. Under acidic conditions, amines (R_3N) exist as their ammonium salts, which lack any lone pairs, and so they must be deprotonated in an unfavorable but rapid equilibrium process before they can act as nucleophiles.
- Most σ -bond nucleophiles (PhMgBr , CH_3Li , LiAlH_4 , NaBH_4) are quite basic, so they are generally used only under basic conditions. Only a handful of σ -bond nucleophiles are compatible with acidic conditions: Lewis acidic nucleophiles such as AlMe_3 , ZnEt_2 , and *i*- Bu_2AlH , and a few non-Lewis acidic H^- sources such as $\text{NaBH}(\text{OAc})_3$ and NaBH_3CN .
- Most π -bond nucleophiles (enols, enol ethers, enamines, as well as simple alkyl-substituted alkenes and arenes) can exist under either acidic or basic conditions, but enolates exist only under basic conditions. Among π -bond nucleophiles, however, only enolates and enamines are reactive enough to attack the electrophiles typically seen under basic conditions.
- Lewis-acid electrophiles are Lewis acids, so they exist under acidic conditions only. **Common error alert:** *Free H^+ and carbocations R_3C^+ should not be drawn in mechanisms occurring under basic conditions.*
- Most π -bond electrophiles can exist under either acidic or basic conditions. Under acidic conditions, though, π -bond electrophiles are usually protonated or coordinated to a Lewis acid before they react with a nucleophile.
- Most σ -bond electrophiles, both of the C–X type (where X is a leaving group) and the heteroatom–heteroatom type, can exist under both basic and acidic conditions. Electrophiles of the C–X type, though, are usually unreactive toward the types of nucleophiles seen under acidic conditions. Under acidic conditions, they are usually converted into carbocations before they react with a nucleophile.

Common error alert: If a reaction is executed under acidic conditions, no strong bases can be present. Any negatively charged species must be weak bases (e.g., Cl^-). Likewise, if a reaction is executed under basic conditions, no strong acids can be present. Any positively charged species must be weak acids.


For example, transesterification can occur under either basic or acidic conditions.



Under *basic* conditions, all species present are *poor acids*. Note the lack of any R_2OH^+ species in this mechanism.




Under *acidic* conditions, all species present are *poor bases*. Note the lack of any RO^- species in this mechanism.




Under either set of conditions, direct attack of ethanol on the ester is not reasonable. The immediate product of such a direct attack would have both RO^- and R_2OH^+ groups, making it both a good acid and a good base. The presence of both a good acid and a good base in a single species creates a situation as untenable as the simultaneous existence of NaOH and H_2SO_4 in a reaction mixture.

INCORRECT:



Reactions that proceed by polar mechanisms often have a protonation or a deprotonation as the first step. If a reaction is run under basic conditions, look for acidic protons in the substrate to remove as a first step. If a reaction is run under acidic conditions, look for basic sites to protonate as a first step.


A weak base can deprotonate a weak acid to generate a stronger base in a rapid, reversible fashion, even though the deprotonation is thermodynamically unfavorable, *as long as the pK_b of the base is no more than 8 units less than the pK_a of the acid*. This “ pK_a rule” is a rule of thumb for determining whether a thermodynamically unfavorable deprotonation step in a mechanism is permissible. For example, it is permissible for OH^- to deprotonate acetone, because the pK_b of OH^- is only 5 units less than the pK_a of acetone, but it is not permissible for OH^- to deprotonate $\text{BuC}\equiv\text{CH}$, because the pK_b of OH^- is 10 units less than the pK_a of $\text{BuC}\equiv\text{CH}$. The same rule applies to protonations, of course, although the rule is not as important for reactions carried out under acidic conditions, because very strong acids are usually used in these reactions.



Problem 1.7 $\text{PhC}\equiv\text{CH}$ can be deprotonated by HO^- in protic solvents, even though $\text{BuC}\equiv\text{CH}$ cannot. What does this tell you about the relative acidities of $\text{PhC}\equiv\text{CH}$ and $\text{BuC}\equiv\text{CH}$?

Often there is more than one basic or acidic site in a molecule. Remember that protonation and deprotonation reactions are very rapid and reversible reactions, so just because a substrate has an acidic or basic site, it doesn't mean that protonation or deprotonation of that site is the first step *in your mechanism*. It's up to you to figure out which site must be deprotonated for the reaction in question to proceed.


Problem 1.8 Which is the most acidic site in the following compound? Which site needs to be deprotonated for the reaction to proceed?




Sometimes basic conditions are specified, but there aren't any acidic protons. You might want to look for protons that are three bonds away from a leaving group X, e.g., $\text{H}-\text{C}-\text{C}-\text{X}$. If there are good nucleophiles present, then you may also need to look for electrophilic atoms. Do not forget that heteroatoms that have their octet and that bear a formal positive charge are not electrophilic!

1.6.1.4 A Typical Polar Mechanism


The reaction of isobutylene (2-methylpropene) with HCl to give *t*-butyl chloride is a typical example of a polar reaction.



HCl is an acid; it dissociates into H^+ and Cl^- . We draw an electron-flow arrow to show the movement of electrons from the bond to the more electronegative element.




Three species are in the reaction mixture now. How would you characterize their reactivity? One (H^+) is an electrophile, and two (Cl^- , isobutylene) are nucleophiles. *Nucleophiles react with electrophiles!* Cl^- can combine with H^+ , but this reaction is simply the reverse of the first reaction. More productively, one of the C atoms of the π bond in isobutylene can use the electrons in the π bond to form a new bond to H^+ and to give a carbocation.



A few points to note about this step. First, there is a net positive charge on the left, so there *must* be a net positive charge on the right. Second, the number of electrons has not changed in going from the left to the right, nor has the number of hydrogen atoms. (Remember Grossman's rule!) Third, the H^+ can attach to either of two C atoms, but it attaches to the more nucleophilic, less substituted C. (Remember Markovnikov's rule!) Fourth, the number of electrons around the nucleophilic carbon (on the right in both starting material and product) does not change in the course of the reaction, but a pair of electrons is taken away from the nonnucleophilic carbon, so this atom is electron-deficient in the product.


The carbocation is an electrophile, and there is still a nucleophile (Cl^-) in the reaction mixture. In the final step of the reaction, a lone pair on Cl^- is used to form a σ bond to the electrophilic C of the carbocation. The product is *t*-BuCl.



1.6.2 Free-Radical Mechanisms


In free-radical reactions, odd-electron species abound. Not all reactions involving free radicals are chain reactions, and not all chain reactions involve free radicals, but the set of free-radical reactions and the set of chain reactions overlap enough that the two subjects are almost always discussed together.

The following reaction is an example of one that proceeds by a chain mechanism.




A chain reaction consists of three parts: *initiation*, *propagation*, and *termination*. In the initiation part of free-radical chain reactions, a small amount of one of the *stoichiometric* starting materials (i.e., a starting material that is required to balance the equation) is converted into a free radical in one or more steps. An *initiator* is sometimes added to the reaction mixture to promote radical formation. In the example, though, no initiator is necessary; light suffices to convert Br_2 , one of the stoichiometric starting materials, into a free radical by σ -bond homolysis.

Initiation:




In the propagation part, the stoichiometric starting materials are converted into the products in one or more steps.

Propagation:




In the termination part of a free-radical mechanism, two radicals react to give one or two closed-shell species by *radical-radical combination* or *disproportionation*.

Termination:




etc.

The propagation part of a chain mechanism is best depicted as a *catalytic cycle*, as shown below. As a catalytic cycle, the propagation part of a free-radical chain mechanism has the following characteristics.



- Every step in the propagation part of the mechanism involves an *odd number* of electrons. **Common error alert:** *Propagation steps do not involve the reaction of two odd-electron compounds with each other.* The only time two odd-electron compounds react with each other in chain reactions is in the termination part.



- The purpose of the initiation part of the chain mechanism is to produce a radical that appears in the propagation. It follows that *one* of the radicals in the propagation will be produced by two different reaction steps: one in the initiation, and one in the propagation.
- All of the starting materials of the reaction (excluding the initiator, if there is one) *must appear* in the propagation part of the mechanism. A corollary of this point is that at least one (usually no more) stoichiometric starting material must appear twice in the mechanism: once in the initiation, and once in the propagation.
- All of the products of the reaction must be produced in the propagation part of the mechanism. (It is common, however, to neglect to draw one or more coproducts.)
- **Common error alert:** *Neither the initiator nor a fragment thereof should appear in the propagation part of the mechanism.* Although it is possible in principle for an initiator to participate in the propagation part of a chain reaction, it is bad practice to write a mechanism in this way. The concentration of initiator is usually very small, and the probability that a radical will encounter it is considerably smaller than the probability that the radical will encounter a stoichiometric starting material. However, in reactions involving O_2 , the O_2 often acts as both an

initiator and as a stoichiometric starting material, so it will appear in both the initiation part and the propagation part.

- Every step in the propagation part must be exothermic or nearly thermoneutral. If a particular step is endothermic, then radicals will accumulate at that point, and they will react with one another to terminate the chain.

How do you recognize that a free-radical chain mechanism is operative? The initiation step usually provides the clue. Most free radicals are very unstable species, and so, when they are used in synthesis, they must be generated in the presence of their reaction partners. There are a limited number of ways of generating free radicals.


- O_2 , a stable 1,2-diradical, can abstract $H\cdot$ from organic compounds to generate radicals, or it can react with Et_3B to give $Et_2BOO\cdot$ and $Et\cdot$. Remember that *air* contains about 20% O_2 !
- Alkyl and acyl peroxides and AIBN (Chap. 5) are common initiators. These compounds readily undergo homolysis under the influence of light ($h\nu$) or heating (Δ) to give free radicals. **Common error alert:** *Hydrogen peroxide (H_2O_2) and alkyl and acyl hydroperoxides ($ROOH$ and RCO_3H) are not free-radical initiators.* The $\cdot OH$ radical is too high in energy to be produced by homolytic cleavage of these compounds at ordinary temperatures.
- Visible light ($h\nu$) has sufficient energy to cause weak σ bonds such as the Br–Br bond to cleave, or to promote an electron from the highest occupied MO of a compound (HOMO), usually a π bond, to the LUMO, generating a 1,2-diradical. Even ambient light may suffice to initiate a free-radical chain reaction if there is a sufficiently weak bond in the substrate (e.g., C–I).
- Weak σ bonds, especially heteroatom–heteroatom σ bonds (O–O, N–O, etc.) and strained σ bonds, can undergo homolytic cleavage simply upon heating.

Some pericyclic reactions require light, so do not assume that a reaction requiring light must proceed by a free-radical mechanism. Also, a few free-radical chain reactions do not require added initiators. These reactions will be discussed as they arise.

Not all free-radical mechanisms are chain reactions, and those that are not do not require initiators. The largest class of *nonchain* free-radical mechanisms are those that utilize one-electron reducing agents such as Li, Na, or Sml_2 (often in liquid NH_3) or one-electron oxidizing agents such as $Ce(NH_3)_2(NO_3)_6$ (CAN) or DDQ. Light-promoted rearrangements of carbonyl compounds also proceed by nonchain free-radical mechanisms. Compounds containing weak σ bonds (typically either heteroatom–heteroatom bonds or very strained bonds) can undergo intramolecular rearrangements by nonchain free-radical mechanisms upon heating. Chapter 5 discusses further the techniques that you can use to distinguish chain and nonchain free-radical mechanisms.


1.6.3 Pericyclic Mechanisms

Pericyclic reactions have a step that involves electrons moving around in a circle. This step usually involves the formation or cleavage of at least one π bond. Often more than one π bond is involved, and often either the starting material or product has two or more conjugated π bonds.




Identifying pericyclic reactions can be difficult. They may be executed under acidic, basic, or neutral conditions, just like polar reactions; in fact, because pericyclic reactions often involve multiply unsaturated compounds, and these compounds are often unstable, many reactions use several polar steps to generate the unsaturated intermediate that undergoes the pericyclic step. Also, sometimes it is quite difficult to figure out the relationship between the starting materials and the products because of the extensive changes in bonding patterns that often occur with pericyclic reactions.

One way to identify a pericyclic mechanism is that they are *stereospecific*. When you start with a *trans* double bond, you get exactly one diastereomeric product; if you start with the *cis* double bond, you get the other diastereomer.




Another way to identify pericyclic reactions is by the products they make. Even when a mechanism has multiple polar steps, it is usually the last step that is pericyclic, so the structure of the product often looks like a compound that could be made by a pericyclic reaction. For example, if a reaction produces a new five-membered heterocyclic compound, and the new heterocycle contains two new bonds in a 1,3-relationship, and when you dissect those two bonds to give a

two-atom component and a three-atom component of the heterocycle, the middle atom of the three-atom component is N or O, then it is likely that the last step of the mechanism is a [3 + 2] (1,3-dipolar) cycloaddition that makes the two new bonds.



As another example, a product that contains two new π bonds in a 1,5-relationship, with a new σ bond connecting atoms 3 and 4, may have been produced by a [3, 3] sigmatropic rearrangement of a compound that contains two different π bonds in a 1,5-relationship, with an original σ bond connecting atoms 3 and 4. Chapter 4 discusses these reactions and more in greater detail.



Another reason why it is sometimes difficult to identify conclusively whether a reaction proceeds by a pericyclic mechanism is that it is usually possible to write very reasonable alternative free-radical or polar mechanisms for the same reaction. In this text, when both pericyclic and nonpericyclic mechanisms can be drawn for a reaction, the pericyclic mechanism will be assumed to be correct unless there is evidence to the contrary.

Some pericyclic reactions require light to proceed or give a particular stereochemical result only in the presence of light. Thus, the use of light may indicate either a free-radical or a pericyclic mechanism. If the bonding changes can be represented by electrons moving around in a circle, then a pericyclic mechanism can usually be drawn for a light-catalyzed reaction.

1.6.4 Transition-Metal-Catalyzed and -Mediated Mechanisms

Some very widely used organic reactions are catalyzed or mediated by transition metals. For example, catalytic hydrogenation of alkenes, dihydroxylation of alkenes, and the Pauson–Khand reaction require Pd, Os, and Co complexes, respectively. The d orbitals of the transition metals allow the metals to undergo all sorts of reactions that have no equivalents among main-group elements. This does not mean that the mechanisms of transition-metal-mediated reactions are difficult to understand. In fact, in some ways they are easier to understand than conventional organic mechanisms. A transition-metal-catalyzed or -mediated reaction is identified by the presence of a transition metal in the reaction mixture.

Some transition-metal complexes are used simply as Lewis acids in organic reactions. Such reactions should be classified as polar acidic, not as transition-metal-mediated. Common Lewis acidic transition-metal complexes include TiCl_4 , FeCl_3 , AgOTf , and certain lanthanide salts such as CeCl_3 and $\text{Sc}(\text{OTf})_3$. Also, a handful of transition-metal complexes are used as one-electron reducing or oxidizing agents, including FeCl_2 , TiCl_3 , SmI_2 , and $(\text{NH}_4)_2\text{Ce}(\text{NO}_3)_6$ (ceric ammonium nitrate, CAN). Reactions that use these compounds are usually best classified as free-radical reactions.

1.7 Summary

Getting started is usually the most difficult part of drawing a mechanism. Follow these simple steps, and you will be well on your way.

- *Label* the heavy atoms in starting material and product.
- *Make a list of which σ bonds* between non-H atoms are made or broken in going from starting material to product. *Do not list π bonds or bonds to H*, as they are easier to make and break at will. *Balance* the equation.
- Classify the overall reaction by looking at the starting materials and products, including coproducts. Is the reaction an addition, an elimination, a substitution, or a rearrangement? Some reactions may combine two or more of these types.
- Classify the mechanism by looking at the reaction conditions. Is it polar under basic conditions, polar under acidic conditions, free-radical, pericyclic, or metal-mediated? Some reactions, especially pericyclic ones, may combine two or more of these types.

Once you have classified the overall reaction and the mechanism, you may have a short series of mechanistic choices. For example, substitution of an aromatic ring under basic conditions generally occurs by one of three mechanisms.

- If the mechanism is polar, determine the nucleophilicity, electrophilicity, and acidity of the atoms to which σ bonds are made and broken. Under basic conditions, the first step is often deprotonation of an acidic atom, rendering it nucleophilic. Under acidic conditions, the first step may be protonation of a leaving group or a π bond.

When faced with a mechanism problem, students often ask, how does one *know* that a particular nucleophile attacks a particular electrophile to give a particular product? The answer to this question is relatively straightforward. A mechanism is a story that you tell about how compound **A** is transformed into compound **B**. To tell the story, you need to know what the product is! If you do not know what the product is, your story will sound something like the game where 15 children in turn add one paragraph to a continuing story, and the final version wanders all over the known universe. Sometimes the product will be a minor or unexpected product, but


a mechanism problem will always give you the product. Organic chemists do need to learn how to predict the product of a reaction, but this skill is deemphasized in this text, whose purpose is to help you to learn how to write mechanisms. Only occasionally will you be asked to *predict* the course of a reaction.

1.8 Problems

Chapters 1–3 in Daniel P. Weeks, *Pushing Electrons*, 4th ed. (Cengage, 2014) are *strongly* recommended for refreshing your skills in drawing Lewis structures, drawing resonance structures, and using electron-flow arrows in simple mechanism problems.



1. Explain each of the following observations.

- Amides (R_2NCOR) are much more nucleophilic on O than they are on N.
- Esters are much less electrophilic at C than ketones.
- Acyl chlorides ($RCOCl$) are much more acidic than esters.
- Compound **1** has a much larger dipole moment than its isomer **2**.
- Compound **3** is much more acidic than **4**.
- Imidazole (**5**) is considerably more basic than pyridine (**6**).
- Fulvene (**7**) is electrophilic at the exocyclic C atom.
- Cyclohexadienone (**8**) is much more prone to tautomerize than most carbonyl compounds. (*Note:* Tautomerizations of carbonyl compounds are almost always very fast, so this question is about thermodynamic propensities, not kinetic ones.)
- Cyclopentadienone (**9**) is extremely unstable.
- The difference between the pK_a values of PhSH and EtSH is much smaller than the difference between those of PhOH and EtOH.
- Furan (**10**) attacks electrophiles exclusively at C2, not at C3.





2. Indicate which of each pair of compounds is likely to be more acidic, and why.



(a)





(b)




(c)





(d)





(e)





(f)





(g)





(h)




(i)





(j)




(k)



(l)




(m)




3. Classify each of the following reactions as polar, free-radical, pericyclic, or transition-metal-catalyzed or -mediated. For the polar reactions, determine whether the conditions are basic or acidic


(a)




(b)




(c)




(d)




(e)




(f)




(g)




(h)




(i)




(j)




(k)



(l)




(m)




4. Most of the heavy atoms in the starting material(s) in each of the following reactions are numbered. Classify each reaction as polar acidic, polar basic, pericyclic, or free-radical. Then number the atoms in the product(s) appropriately, and make a list of bonds made and broken between heavy atoms. Assume aqueous workup in all cases.


(a)




(b)




(c)




(d)




(e)




(f)




(g)




(h)




(i)




(j)




(k)



(l)



























(m)



5. In each of the following compounds, a particular atom is indicated with an arrow. Determine whether this atom is nucleophilic, electrophilic, acidic. Some atoms may have none or more than one of these properties. For the purposes of this problem, "acidic" is defined as $\text{p}K_a \leq 25$.

(a)	(b)	(c)
(d)	(e)	(f)
(g)	(h)	(i)
(j)	(k)	(l)
(m)	(n)	(o)

(p) 	(q) 	(r) 
(s) 	(t) 	(u) 
(v) 	(w) 	(x) 
(y) 	(z) 	(aa) 
(bb) 	(cc) 	(dd) 
(ee) 	(ff) 	(gg) 
(hh) 	(ii) 	(jj) 
(kk) 	(ll) 	(mm) 

Polar Reactions Under Basic Conditions


2

Now that you have learned how to identify the mechanistic class of a particular reaction, you are ready to learn how to write the mechanism itself. This chapter is devoted to polar mechanisms that occur under basic conditions. Archetypical mechanisms will be presented and discussed so that you become familiar with the patterns of reactivity of organic compounds under basic conditions.


Many of the reactions that will be discussed in this and later chapters are “name reactions.” Name reactions are used as examples in this book simply because they are widely used reactions, not because you need to know the name of any reaction to be able to draw a mechanism for it. In fact, one of the goals of this book is to show you that you can draw a mechanism for any reaction *whether or not you have seen it previously*.

2.1 Introduction to Substitution and Elimination

Electrophiles that have leaving groups (X) attached to a C atom can undergo *nucleophilic substitution* or *elimination* reactions. In a *nucleophilic substitution* reaction, a nucleophile–electrophile σ bond replaces the electrophile–X σ bond.




Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_2) contains supplementary material, which is available to authorized users.



In principle, there are three sequences in which the bond-making and bond-breaking can take place. In the first sequence, Nu^- adds, an intermediate is obtained, and then, in a second step, X^- leaves. In the second sequence, Nu^- adds and X^- leaves simultaneously. In the third sequence, X^- leaves, an intermediate is obtained, and then, in a second step, Nu^- adds. All three sequences have been observed under basic conditions. One of the purposes of this chapter is to teach you how to determine which sequence is most likely, given the substrates and the reaction conditions.


In an *elimination* reaction, the leaving group X (with its associated pair of electrons) is removed from a compound along with an electropositive group E (usually H). The most common kind of elimination is β -elimination, in which E and X are attached to adjacent atoms and a new π bond is formed between those atoms in the product.



Elimination reactions generally involve breaking a C–H bond and breaking a C–X bond, where the two C atoms are adjacent. In principle, there are three sequences in which the two bond-breaking steps can take place. In the first sequence, the C–H bond breaks first to give an anionic intermediate, and then the C–X bond breaks. In the second sequence, the two bonds break simultaneously. In the third sequence, the C–X bond breaks to give a cationic intermediate, and then the C–H bond breaks. Under basic conditions, the two bond-breaking events of elimination generally cannot proceed in the third sequence, because this sequence requires the formation of a carbocationic intermediate. (Carbocations are strong Lewis acids, so they cannot form spontaneously under basic conditions.) By contrast, the two bond-breaking events of eliminations can take place in the first and second sequences under basic conditions. Again, one of the purposes of this chapter is to teach you how to determine which sequence is most likely, given the substrates and the reaction conditions.

2.1.1 Substitution by the S_N2 Mechanism

Substitution reactions at 1° and 2° (but not 3°) $C(sp^3)$ usually proceed by the S_N2 mechanism under basic conditions. The nucleophile Nu^- approaches the electrophilic center opposite X and in line with the C–X bond. The lone pair on Nu^- is used to form the C–Nu bond, and the pair of electrons in the C–X bond *simultaneously* leaves with X as the bond breaks. The other three groups on C move away from Nu and towards X as the reaction proceeds, so that when the reaction is complete, the stereochemistry of C is inverted. The charges do not have to be as shown: the nucleophile may be anionic or neutral, and the electrophile may be neutral or cationic.




The electron-flow arrow shows how the pair of electrons moves *from* the nucleophile *to* the electron-deficient center. The nucleophilic atom increases its formal charge by 1, and the leaving group decreases its formal charge by 1. In this drawing, because none of the lone pairs of Nu^- are explicitly drawn, the minus sign on Nu^- doubles as *both* a formal charge *and* a pair of electrons. When the nucleophilic atom has a formal charge of 0, the lone pair is usually shown explicitly.


Common error alert: *Intermolecular substitution by the S_N2 mechanism occurs only at 1° and 2° $C(sp^3)$.* Under basic conditions, intramolecular substitution at 3° $C(sp^3)$ may occur by the S_N2 mechanism, but substitution at $C(sp^2)$ never occurs by the S_N2 mechanism at all. Substitution at an electrophilic $C(sp^2)$ or intermolecular substitution at 3° $C(sp^3)$ *must* proceed by a mechanism other than S_N2 (see below).

Common error alert: F^- , HO^- , RO^- (except epoxides), H^- , and carbanions are almost never leaving groups in S_N2 reactions under basic conditions.


Lone-pair nucleophiles are by far the most enthusiastic participants in S_N2 substitution reactions. Sigma-bond nucleophiles may also participate in S_N2 reactions, but they do not do so as often as lone-pair nucleophiles. By contrast, π -bond nucleophiles do not usually have sufficiently high energy to react with an atom that already has an octet. The major exceptions to this rule are the enamines ($R_2N-CR=CR_2 \leftrightarrow R_2\overset{+}{N}=CR-CR_2$), which are sufficiently nucleophilic at the β position to attack particularly reactive alkyl halides such as CH_3I and allylic and benzylic bromides, and enolates ($O-CR=CR_2 \leftrightarrow O=C\overset{-}{R}-CR_2$), which react with many alkyl halides.




Electrophiles with allylic-leaving groups can undergo either S_N2 or S_N2' substitution. In S_N2' substitution, the lone pair on Nu^- moves to form a bond to the γ -carbon of the allylic system. (The α -carbon is the C attached to the leaving group.) The electrons in the π bond between the β - and γ -carbon atoms move to form a new π bond between the β - and α -carbons, and the leaving group is concomitantly expelled. The double bond *transposition* is key to identifying an S_N2' substitution mechanism. It is very difficult to predict whether a particular allylic halide or pseudohalide will undergo S_N2 or S_N2' substitution with a particular nucleophile.




S_N2 substitution can occur at elements other than C. For example, substitution at a stereogenic S atom leads to inversion of configuration, suggesting an S_N2 mechanism for this process.



In contrast with first-row main-group elements, second-row and heavier atoms such as P, S, and Br can expand their octet, so substitution at these atoms can occur either by an S_N2 mechanism or by a two-step *addition-elimination* mechanism. In the first step, the nucleophile adds to the electrophilic heavy atom to give a hypervalent, 10-electron intermediate. In the second step, the nucleofuge leaves to give the substitution product. The lifetime of the 10-electron intermediate can vary from extremely short to very long, so both the S_N2 and the addition-elimination mechanisms are usually reasonable for S, P, or heavier elements.



Not all substitution reactions under basic conditions occur with simple inversion. Sometimes nucleophilic substitution at stereogenic C proceeds with *retention* of configuration. In such a reaction, two sequential nucleophilic substitutions have usually occurred. For example, the reaction of α -diazoniocarboxylic acids with nucleophiles such as Cl^- occurs with retention. In the first S_N2 substitution, the O^- of the carboxylate acts as a nucleophile, displacing N_2 with inversion to give a three-membered ring (an α -lactone). In the second S_N2 substitution, Cl^- displaces O with inversion to give the product with overall retention.




Sometimes nucleophilic substitution at stereogenic C proceeds with *loss* of configurational purity. Such a reaction may be rationalized mechanistically in one of four ways.


1. The stereocenter in the starting material loses configurational purity before the S_N2 reaction occurs. For example, stereochemically pure 2-bromocyclohexanone may lose its configurational purity by deprotonation and reprotonation of the acidic stereocenter.
2. The stereocenter in the product loses configurational purity after the S_N2 reaction occurs.
3. The nucleophile can also act as a leaving group, or vice versa. This problem is especially severe with reactions involving I^- , which is both an excellent nucleophile and an excellent-leaving group. The preparation of alkyl iodides such as 2-iodobutane in enantiopure form is difficult for this very reason.
4. The substitution may proceed by a non- S_N2 mechanism, e.g., $S_{RN}1$ or elimination-addition. These substitution mechanisms are discussed later in this chapter.

2.1.2 β -Elimination by the E2 and E1cb Mechanisms

$C(sp^3)$ -X electrophiles can undergo β -elimination reactions as well as substitutions. β -Elimination reactions proceed by the E2 or E1cb mechanism under basic conditions. The concerted E2 mechanism is more common. The lone pair of the base atom moves to form a bond to an H atom on a C atom *adjacent to the electrophilic C atom*. The electrons in the H-C bond simultaneously move to form a π bond to the electrophilic C atom. Because this C atom already has its octet and is acquiring a new bond, the bond to the leaving group must break. The electrons in that bond leave with the leaving group to become a new lone pair.




Because the H-C and the C-X bonds break simultaneously in the E2 mechanism, there is a *stereoelectronic requirement* that the orbitals making up these two bonds be *periplanar* (i.e., parallel to each other) in the transition state of the elimination. Acyclic compounds can orient the two bonds in a periplanar fashion in two ways, *synperiplanar* (by eclipsing them at a 0° dihedral angle) and *antiperiplanar* (by staggering them at a 180° angle). The staggered arrangement is much lower in energy than the eclipsed arrangement, so antiperiplanar elimination is far more common than synperiplanar elimination.




In cyclic compounds, there are much greater restrictions on conformational flexibility. In six-membered rings, the antiperiplanar requirement for E2 elimination is satisfied when both the leaving group and the adjacent H atom are *axial*. Compounds in which such a conformation is readily achievable undergo E2 elimination much more readily than those in which it is not. For example, in menthyl chloride, the C-Cl bond is not antiperiplanar to any adjacent C-H bond in the lowest energy conformation, and E2 elimination is therefore much slower than it

is in the diastereomer neomenthyl chloride, in which the C–Cl bond is antiperiplanar to two C–H bonds in the lowest energy conformation. Moreover, two C–H bonds are antiperiplanar to the C–Cl bond in the reactive conformation of neomenthyl chloride, so two products are obtained upon E2 elimination, whereas only one C–H bond is antiperiplanar to the C–Cl bond in the reactive conformation of menthyl chloride, so only one product is obtained.




Not only can 1° , 2° , and 3° $C(sp^3)$ –X undergo β -elimination by the E2 mechanism under basic conditions, but so can $C(sp^2)$ –X systems. Alkenyl halides undergo β -elimination readily. When there are H atoms on either side of an alkenyl halide, either an alkyne or an allene may be obtained. Even alkenyl ethers (enol ethers) can undergo β -elimination to give an alkyne.


Example




Problem 2.1 Draw a mechanism for the following reaction.




$E2'$ eliminations, in which a π bond is interposed between the two C atoms at which bond-breaking occurs, are also seen. In the following example, the base is F^- , and a Me_3Si group replaces the usual H.




β -Elimination sometimes gives high-energy species. Under very strongly basic conditions, halobenzenes undergo β -elimination to give *benzynes*, compounds that are highly strained and reactive. β -Elimination from acyl chlorides occurs under mildly basic conditions to give *ketenes*. Both of these reactions will be revisited later.



When the H is particularly acidic (usually because it is adjacent to a carbonyl) and the leaving group is particularly poor (especially ^-OH and ^-OR), a two-step mechanism called *E1cb* operates. In this mechanism, the acidic proton is removed first to make a stabilized carbanion. Then the lone pair on C moves to make a π bond to the neighboring electrophilic C, expelling the leaving group. The dehydration of an aldol (β -hydroxycarbonyl compound) is the most common example of an elimination reaction that proceeds by the *E1cb* mechanism.



The E1cb elimination is the normal method by which a hemiacetal is converted to a carbonyl compound under basic conditions.



2.1.3 Predicting Substitution Versus Elimination

In principle, any compound with a lone pair can act as either a base or a nucleophile toward $C(sp^3)-X$, causing either E2 elimination or S_N2 substitution to occur. It is possible to predict whether substitution or elimination will occur with moderate accuracy (Table 2.1). Two factors largely determine the course of the reaction: (1) the nucleophilicity and basicity of the lone-pair-bearing compound, and (2) the identity of the substrate: Me or Bn, 1° , 2° , or 3° halide. **Common error alert:** *Whether substitution or elimination occurs is the outcome of a “negotiation” between the nucleophile and the electrophile. Neither the nucleophile nor the electrophile determines the outcome exclusively.*

The first factor that determines whether substitution or elimination occurs is the nucleophilicity and basicity of the lone-pair-bearing compound. The factors that influence nucleophilicity and basicity have already been discussed (Chap. 1). Nucleophiles–bases can be classified very simplistically into good nucleophiles–poor bases, good nucleophiles–good bases, and poor nucleophiles–good bases toward $C(sp^3)$ halides.


- *Second-row or heavier species are good nucleophiles and poor bases.* Cl^- , Br^- , I^- , R_2S , RS^- , and R_3P are in this class.
- *First-row, unhindered species are both good nucleophiles and good bases.* Unhindered RO^- , R_2N^- , and R_3N are in this class, as are small anions such as F^- , ^-CN , and $^-N_3$. Carbon nucleophiles such as enamines, simple enolates, alkynyl anions ($RC\equiv C^-$), and stabilized enolates such as malonate anions and their derivatives are also in this class.

Table 2.1 Predicting substitution versus elimination at $C(sp^3)-X$ under basic conditions


	Poor base, good nucleophile	Good base, good nucleophile	Good base, poor nucleophile
Me or Bn	S_N2	S_N2	S_N2 or N.R.
1°	S_N2	S_N2	E2
2°	S_N2	$S_N2 < E2$	E2
3°	E2, $S_{RN}1$, or N.R.	E2	E2

- *First-row, hindered species are poor nucleophiles and good bases:* $t\text{-BuO}^-$, $i\text{-Pr}_2\text{NLi}$ (LDA), $(\text{Me}_3\text{Si})_2\text{NK}$ (KHMDS), $i\text{-Pr}_2\text{NEt}$ (Hünig's base), and amidines and guanidines such as DBN, DBU, and TMG are in this class, as are many organometallic compounds such as $\text{C}(sp^2)$ and $\text{C}(sp^3)$ Grignard and organolithium reagents. The simple hydrides NaH and KH are also in this class: they do not appear to be hindered, but their insoluble, polymeric form makes them so.


Some common amidine and guanidine bases that are relatively nonnucleophilic:



DBU



DBN



TMG

Obviously, the division of nucleophiles and bases into “good” and “bad” is a gross oversimplification. There is a continuum of nucleophilicity and basicity that runs from “excellent” through “good”, “mediocre”, “poor”, and “awful”. The simplistic classification given above merely provides a *guideline* for prediction of reactivity.

Common error alert: *Don't forget that “good nucleophile” is defined with respect to reactivity toward CH_3Br at 25 °C in H_2O or MeOH as solvent.* Some species, e.g., CH_3MgBr , that are not good nucleophiles toward σ bond electrophiles are quite good nucleophiles toward π bond electrophiles. For a discussion of how the properties of the electrophile influence the nucleophilicity of the nucleophile (hard/soft acid/base theory), see Fleming, Ian, *Frontier Orbitals and Organic Chemical Reactions* (New York: John Wiley & Sons, 1976), pp. 34ff.


The second factor that determines whether substitution or elimination occurs is the structure of the electrophile.

- MeX and BnX cannot undergo elimination (no β -hydrogen atoms) and are good substrates for $\text{S}_{\text{N}}2$ (unhindered; the Bn group also stabilizes the TS for substitution), so these substrates undergo substitution only.
- 1° Alkyl halides love to do $\text{S}_{\text{N}}2$ (relatively unhindered) and do not like to do E2 (relatively unsubstituted alkene product, hence not very low in energy), so they tend to undergo substitution if the nucleophile is a good one, regardless of its basicity. If, however, the nucleophile is really poor but is a good base, they will consent to elimination.
- 3° Alkyl halides hate to do $\text{S}_{\text{N}}2$ (too hindered) and love to do E2 (highly substituted and low-energy alkene product, plus relief of steric congestion), so they tend to undergo elimination if the base is a good one at all, regardless of its nucleophilicity. If, however, the base is really poor but is a very good nucleophile, they might undergo substitution by the $\text{S}_{\text{R}}\text{N}1$ mechanism (see below), or there may be no reaction.
- 2° Alkyl halides are at the cusp. In general, they are perfectly happy to undergo either elimination or substitution, depending on whatever the base/nucleophile prefers.

If neither the electrophile (2° halide) nor the nucleophile (good base/good nucleophile) has a strong preference for substitution or elimination, a situation arises in which each asks the other, "I dunno, whadda you wanna do?" In this case, elimination tends to dominate over substitution, but the actual product ratio varies tremendously depending on substrate structure, solvent, and other factors. These factors include the following.

- The less basic the nucleophile, the more S_N2 product is obtained. For example, an alkynyl anion will give almost exclusively the E2 product when it reacts with bromocyclohexane, but ^-CN , a much weaker base, will give mostly the S_N2 product.
- The proportion of the S_N2 product increases greatly for allylic, benzylic, and propargylic ($C\equiv C-C-X$) 2° halides.
- The proportion of the S_N2 product can also be increased by executing the reaction in a polar aprotic solvent (DMSO, DMF, etc.) or by reducing the basicity of the nucleophile.
- E2 is more prone to occur for cyclic 2° halides than for acyclic 2° halides, but this tendency is ameliorated in polar aprotic solvents.
- Homoallylic substrates ($C=C-C-C-X$) and homopropargylic substrates ($C\equiv C-C-C-X$), regardless of their substitution pattern, are more prone to undergo elimination than other substrates due to the activation of the allylic or propargylic C-H bond toward deprotonation.

Problem 2.2 Explain the difference between the yields of the two reactions, and propose a measure that would improve the yield of the second reaction.




Common error alert: *The leaving group ability of X^- affects the overall rate of both S_N2 and E2 reactions—the better the leaving group, the faster the rates—but it has relatively little influence on which of these pathways is the major one. To determine whether S_N2 or E2 dominates, you must consider the factors enumerated above.*

2.2 Addition of Nucleophiles to Electrophilic π Bonds

2.2.1 Addition to Carbonyl Compounds


Carbonyl compounds $C=O$ have two major resonance structures, $R_2C=O \leftrightarrow R_2\overset{+}{C}-\overset{-}{O}$. In the second resonance structure, C is electron-deficient, so carbonyl compounds are good electrophiles. Carbonyl groups with α -hydrogen atoms are relatively acidic compounds, because the carbanions produced upon removal of the H are lowered in energy by resonance with the carbonyl group: $O=CR-\bar{C}R_2 \leftrightarrow \bar{O}-CR=CR_2$. The enolate anions that are thereby obtained are nucleophilic at the α -carbon and on O. *Under basic conditions, then, carbonyl compounds are electrophilic at the carbonyl carbon and nucleophilic at the α -carbons (if they have H atoms attached).* All of the chemistry of carbonyl compounds derives from this dichotomy.

The thermodynamic energies of carbonyl compounds are directly related to the energies of their $R_2\overset{+}{C}-\overset{-}{O}$ resonance structures. The order of thermodynamic energies of the common types of carbonyl compounds is $RCOCl$ (acyl chlorides) $<$ RCO_2COR (acyl anhydrides) $<$ $RCHO$ (aldehydes) $<$ R_2CO (ketones) $<$ RCO_2R (acids, esters) $<$ $RCONR_2$ (amides) $<$ $ROCO_2R$ (carbonates) $<$ $ROCONR_2$ (urethanes/carbamates) $<$ R_2NCONR_2 (ureas) \approx RCO_2^- (carboxylate salts). Addition of a nucleophile to a carbonyl compound gives an intermediate that has relatively little resonance stabilization, so the process costs most of the resonance stabilization of the carbonyl compound. As a result, the order of kinetic stabilities of carbonyl compounds is the same as the order of thermodynamic energies.




Sigma-bond nucleophiles such as Grignard reagents ($RMgBr$), organolithium compounds (RLi), and complex metal hydrides such as $NaBH_4$ and $LiAlH_4$ add to ketones and aldehydes to give alcohols. The mechanism of addition to ketones and aldehydes is complex and is still being debated, but a very simple picture suffices here. The electrons in the $C-M$ or $H-M$ σ bond move away from the metal M to form a bond between the nucleophilic atom and the electrophilic carbonyl C . At the


same time, the electrons in the $\text{C}=\text{O}$ π bond move to O to become a lone pair. After aqueous workup, an alcohol is obtained.



Grignard reagents and organolithium compounds are very strong bases, too, and you might ask how it can be predicted when they will act as bases toward carbonyl compounds and when as nucleophiles. 1,3-Dicarbonyl compounds are so acidic that they are always deprotonated by these compounds, but for simple ketones and aldehydes, the ratio of deprotonation to addition is substrate-dependent. In general, steric hindrance increases the proportion of deprotonation. The reagent CeCl_3 greatly enhances the amount of addition, even for highly hindered substrates, for reasons that remain unclear.




When the α -carbon of an aldehyde or ketone is a stereocenter, and addition of an organometallic nucleophile to the carbonyl group generates a new stereocenter, then selective formation of one diastereomer over the other is often observed. In many cases, the observed stereoselectivities are consistent with *Felkin-Anh* selectivity. The α -stereocenter of the carbonyl group has a large R_L group, a small R_S group, and H attached to it. Consider the different rotamers about the bond between the carbonyl carbon and the α -carbon. (The best way to understand this argument is to use Newman projections.) The nucleophile Nu^- will want to approach the carbonyl carbon from a trajectory that is as far away from R_L as possible. This condition is best satisfied if the $\text{C}-\text{R}_\text{L}$ and $\text{C}=\text{O}$ bonds are placed at a dihedral angle of 90° , and Nu^- approaches the carbonyl group from opposite R_L . Two rotamers satisfy this condition: one has R_S nearly eclipsing the carbonyl substituent R, and the other has H nearly eclipsing the carbonyl substituent R. The latter rotamer least hinders the approach of Nu^- to the carbonyl carbon. The predominant diastereomer of the product is then the one in which Nu is anti to R_L and OH is anti to H.




The diastereoselectivities of the addition of organometallic compounds to ketones and aldehydes are often quite poor (2:1), and there are numerous cases in which anti-Felkin–Anh selectivity is observed, but the rule is widely invoked anyway.

Water and alcohols add reversibly to ketones and aldehydes under basic conditions to give *hydrates* or *hemiacetals*.

Example




The equilibrium generally favors both ketones and aldehydes over the corresponding hydrates or hemiacetals, but it favors aldehydes less strongly than it does ketones. The equilibrium is pushed toward the hemiacetal by inductively electron-withdrawing groups on the α -carbon and when a five- or six-membered ring can be formed. Both of these factors are present in glucose, fructose, and other carbohydrates.



Both 1° and 2° amines react very rapidly with ketones and aldehydes to give the reactive intermediates, *iminium ions*. When the starting amine is 1° (RNH_2), the iminium ion can be deprotonated by the coproduct HO^- to give an *imine* (Schiff base). The position of the equilibrium between the starting ketone or aldehyde and the product imine depends on the structure of the amine and the carbonyl compound. With alkylamines, the equilibrium favors the carbonyl compound, but it can be driven to the imine by removal of H_2O . With hydrazines (R_2NNH_2) and *N*-hydroxyl- and *N*-alkoxyamines (RONH_2), the equilibrium greatly favors the *hydrazone*, *oxime*, or *oxime ether*, and it is difficult to drive the reaction in the reverse direction.


Example



The mechanisms of many polar reactions feature steps that involve transferring an H^+ from an acidic atom to a basic one. Chemists often omit the electron-flow arrows that indicate this step, often choosing to write " $\sim H^+$ " above the arrow instead, as in the example above. Consult with your instructor to determine whether he or she will permit you to use this shortcut.


An iminium ion derived from a 2° amine (R_2NH) does not bear an acidic H atom on N, so it cannot form an imine. However, if the α -carbon of an iminium ion derived from either a 1° or 2° amine bears an H atom, the H atom can be removed by base to give an *enamine*. The equilibrium favors the enamine for 1,3-dicarbonyl compounds; for other compounds, enamine formation can be driven to completion by removal of H_2O .

Example




The rate of formation of an iminium ion is very, very fast when the reaction conditions are just mildly basic. Under strongly basic conditions, the step in which HO^- is lost to give the iminium ion is subject to rapid reversal back to the hemiaminal.

Like amines will do, cyanide (^-CN) will add to a ketone or aldehyde, giving (after protonation) a *cyanohydrin*, with the position of the equilibrium dependent on the electrophilicity of the carbonyl compound.



The conjugate bases of carbonyl compounds, *enolates*, react with ketones and aldehydes in the *aldol reaction*. The reaction is usually executed in two stages. First, the enolate is generated, usually by deprotonation of the carbonyl compound at low temperature with a strong base such as LDA, KHMDS, or LiHMDS. Then, the electrophilic carbonyl compound is added to the reaction mixture. Under these conditions, the reaction usually stops at the β -hydroxycarbonyl stage. The nucleophilic component may be any carbonyl compound or even a nitrile R_2CHCN , a sulfonyl compound R_2CHSO_2R , or a nitro compound R_2CHNO_2 . (One can describe nitriles, etc. as adopted members of the carbonyl family: they do not look like carbonyl compounds, but they behave like them.)


Example




It matters not one iota whether you draw the C^- or O^- resonance structure of the enolate. The two resonance structures describe the same compound.

Problem 2.3 Draw mechanisms for the following aldol reactions.


(a)




(b)




The enolate that is required for the aldol reaction can be generated in other ways, too. For example, trimethylsilyl enol ethers react with TBAF (tetrabutylammonium fluoride, $\text{Bu}_4\text{N}^+ \text{F}^-$) to give the corresponding enolates. Enolates may also be prepared by the dissolving metal reduction of α,β -unsaturated ketones (see Chap. 5).



When a carbonyl compound with two α -hydrogen atoms ($\text{R}^1\text{CH}_2\text{COX}$) undergoes an aldol reaction with an aldehyde R^2CHO , two new stereocenters are created, and hence two diastereomers can be formed. The stereochemistry of these aldol reactions has been extensively studied since the 1970s, and it is now fairly predictable. When $\text{R}^1\text{CH}_2\text{COX}$ is deprotonated with LDA, either the E or the Z diastereomer of the enolate $\text{R}^1\text{CH}=\text{C}(\text{OLi})\text{X}$ may in principle be generated, but the enolate in which R^1 and OLi are Z (called a Z enolate regardless of the nature of X) is lower in energy, so it usually predominates. The Z enolate then undergoes the aldol reaction with an aldehyde via a transition state that features a six-membered, Li-containing ring. A six-membered ring is usually lowest in energy when it is in the chair conformation, and the aldol TS is no exception. When the enolate is Z, the R^1 substituent must be placed in a pseudoaxial position because it must remain cis to the enolate O, but the aldehyde substituent (R^2) can be placed in a pseudoequatorial position. After C–C bond formation and workup, the syn aldol is obtained selectively. (Whether an aldol product is syn or anti is determined by drawing the main chain, including X and R^2 , in zigzag fashion in the plane of the paper; it is syn when R^1 and OH reside on the same side of the plane of the paper, and it is anti when they reside on opposite sides.) If the E enolate can be selectively generated, then both R^1 and R^2 can be placed in pseudoequatorial orientations in the aldol TS, and the anti aldol is obtained.




When the X group of the enolate also contains a stereocenter, two diastereomeric syn (or two anti) aldols can be formed. Depending on the nature of the X group, the diastereoselectivity may be very high. When an enantiopure, easily replaced X group is used to cause both new stereocenters in the aldol product to form with very high stereoselectivity, it is called a *chiral auxiliary*. The most widely used chiral auxiliaries are the oxazolidinones, which are derived from enantiopure α -amino acids such as (*S*)-valine. The aldol reaction of the enolate of an *N*-acyloxazolidinone (usually the *Z* enolate) again proceeds through a chairlike TS. Two chairlike TSs are possible; the lower energy one has the oxazolidinone *i*-Pr substituent pointing away from the aldehyde. After the aldol reaction, the oxazolidinone is hydrolyzed away and replaced with an OH group to give an enantiopure carboxylic acid.




There are many, many variations of the aldol reaction involving metals other than Li (e.g., B, Ti, Sn) and various chiral auxiliaries and other X groups. Almost all of them proceed through selective formation of a *Z* or *E* enolate followed by a chairlike TS for the aldol reaction.

The aldol reaction of two different enolizable carbonyl compounds is not usually carried out simply by mixing them and adding a base, because either carbonyl compound can act as a nucleophile or as an electrophile, and a mixture of all four possible products may be obtained. However, if one of the carbonyl compounds is nonenolizable and is more electrophilic than the other (e.g., one compound is a ketone and the other is $ArCHO$, $t-BuCHO$, or EtO_2CCHO), then the two components can be combined and allowed to undergo an aldol reaction in the presence of a relatively weak base like $NaOEt$, KOH , or $t-BuOK$. Only one of the compounds can be converted into a nucleophile, and it attacks only the other component (and not another equivalent of itself) to give only one product. Under these conditions, the initial aldol product usually undergoes $E1cB$ elimination to give an α,β -unsaturated carbonyl compound.

Example




In principle the protonation of O^- and subsequent deprotonation of C could be condensed into one intramolecular proton transfer step in which the O deprotonates C. However, such a transfer requires a very strained four-membered transition state. It is therefore considered the bad practice to draw an intramolecular proton transfer, especially when the solvent can serve as a proton “shuttle” instead.




In the *benzoin condensation*, CN^- catalyzes the dimerization of benzaldehyde to give benzoin, which has a new C–C bond. It is tempting to use CN^- to deprotonate one aldehyde, then have the resulting anion attack the other aldehyde, but two lines of argument tell you that this mechanism is almost certainly wrong. First, if CN^- is merely acting as a base, then any base would work in this reaction, but that is not the case. (Why would you use the very dangerous CN^- to catalyze a reaction when you could use a much more benign base instead?) Second, the carbonyl C atoms of aldehydes are not acidic.

Example




If CN^- is not acting as a base, it must be acting as a nucleophile. The only thing it can do as a nucleophile is to add to the aldehyde. The resulting alkoxide can deprotonate EtOH to give a neutral hydroxy nitrile. Because nitriles are

adopted members of the carbonyl family, they are acidic at the α -carbon, which, in this case, happens to be the former carbonyl C atom of the aldehyde. Therefore, deprotonation of the α -carbon of the nitrile is followed by addition of the resulting carbanion to a second equivalent of PhCHO to give an alkoxide. Proton transfer followed by elimination of ^-CN gives the product.




The reason ^-CN is able to act as a catalyst in the benzoin condensation is that it is a nucleophile that is an anion-stabilizing group after it makes its bond to the electrophile. Long ago, nature evolved a catalyst that is not ^-CN , but has the same properties that allow ^-CN to catalyze the benzoin condensation. This catalyst is *thiamine*, otherwise known as vitamin B₁. Thiamine contains a thiazolium ring, which happens to be quite acidic at C(2) due to the resonance and inductive effects of the N^+ and the special anion-stabilizing ability of S. The conjugate base has an $\text{N}=\text{C}^-$ zwitterionic resonance structure and a neutral carbene resonance structure. The latter resonance structure leads some to call thiamine an example of an *N-heterocyclic carbene*.




One of the steps in the biosynthesis of the amino acid valine is a thiamine-catalyzed reaction that is similar to the benzoin condensation. In this reaction, two equivalents of pyruvate combine with loss of CO_2 to make acetolactic acid, which has a new C–C bond. The mechanism of this reaction begins with deprotonation of thiamine by a base in the enzyme's active site. The resulting carbanion adds to the ketone group of pyruvate, which picks up the available H^+ from the first step to give an α -hydroxycarboxylate. Loss of CO_2 can now occur, with the electrons from the breaking C–C bond migrating to make a lone pair on the thiazolium N atom, giving an enamine. The enamine, of course, is nucleophilic at the β -carbon atom (formerly the pyruvate carbonyl C atom), so this C atom can add to the ketone group of another equivalent of pyruvate in what is formally an aldol

reaction. Proton transfer is then followed by elimination of the thiamine carbanion to give acetolactate and to regenerate the active catalyst. Overall, in this reaction, one of the equivalents of pyruvate is acting as an acetyl anion $^-\text{C}(=\text{O})\text{CH}_3$, with the electrons of the carbanion derived from cleavage of the C–C bond in the decarboxylation step. This reactivity would not be possible without the participation of the thiamine.

Example




Problem 2.4 Draw a mechanism for the following reaction catalyzed by an *N*-heterocyclic carbene. (Do not concern yourself with the stereochemistry.)




Aldol reactions are reversible, and you need to be able to recognize the reverse reaction, the *retro*-aldol reaction. Because a C–C σ bond is broken in the *retro*-aldol reaction, some driving force (e.g., relief of strain) is usually required for it to proceed to completion.

Example




The mechanism of this reaction cannot involve inversion by an S_N2 substitution reaction because (1) no HO^- is present, and (2) HO^- is an awful leaving group in S_N2 reactions, anyway. The nonnucleophilic base DBU can deprotonate the OH group to give an alkoxide, which can undergo a retro-aldol reaction to give an aldehyde and an ester enolate. The aldehyde can then rotate about the single C–C bond to present its other face to the enolate for attack. An aldol reaction then gives the isomerized product.




The *Knoevenagel reaction*, the condensation of 1,3-dicarbonyl compounds with aldehydes to give unsaturated compounds, is catalyzed by 2° amines. A perfectly reasonable mechanism involving deprotonation of the 1,3-dicarbonyl compound by base, aldol reaction with the ketone, and $E1c_b$ elimination of H_2O can be drawn. However, the Knoevenagel reaction does not proceed nearly so well using 3° amines, suggesting that the amine does not simply act as a base.


Example




If the amine does not act as a base, it must act as a nucleophile. After addition to the electrophilic ketone to give a hemiaminal, OH leaves, and an *iminium ion* is obtained. The iminium ion, the key intermediate, cannot be formed from a 3° amine.




The iminium ion is more electrophilic than the ketone from which it is derived; it reacts with the deprotonated 1,3-dicarbonyl compound.



To arrive at the product, the elements of the amine need to be eliminated. After the amine is protonated to make it a better leaving group, E1cb elimination gives the product and regenerates the catalyst.



Grignard reagents and organolithium reagents add to nitriles to give imines, which are rapidly hydrolyzed to ketones upon addition of water. Only one addition to the $C\equiv N$ triple bond takes place, because a second addition would produce a very high energy RN^{2-} species.




2.2.2 Conjugate Addition. The Michael Reaction

Alkenes and alkynes that are substituted with electron-withdrawing groups such as carbonyl, nitro, and sulfonyl groups are electrophilic. Many nucleophiles react with


these alkenes in *conjugate* or *1,4-addition* reactions to give addition products. For example, alcohols, thiols, amines, and other heteroatomic nucleophiles react with electrophilic alkenes by an unremarkable mechanism. The nucleophile adds to the C that is β to the electron-withdrawing group, and the electrons in the π bond move to the C adjacent to the electron-withdrawing group to give a carbanion. The carbanion is low in energy because its lone pair can be delocalized into the electron-withdrawing group.

Example




The most important kinds of conjugate addition reactions are *Michael reactions*, which involve the addition of C nucleophiles to C=C π bonds. The nucleophiles are often 1,3-dicarbonyl compounds such as malonates, cyanoacetates, β -ketoesters, and 1,3-diketones, but simple carbonyl compounds may also be used. The reaction usually requires only catalytic amounts of base.

Example




Often the Michael reaction is followed by an aldol reaction, a substitution, or another Michael reaction. For example, the Robinson annulation consists of a Michael reaction, an aldol reaction, and a dehydration (β -elimination).


Example




Numbering the atoms shows that bonds are made at C6–C13 and C8–C9, and the C6–O7 bond is broken.




By far the most acidic site in both starting materials is C8. Deprotonation of C8 turns it into a nucleophile, so it can add to C9 in a Michael reaction to give a C10 enolate. No more needs to be done with C10, so it is protonated.



The C6–C13 bond still needs to be formed. C13 is made nucleophilic by deprotonation, then it attacks C6. The alkoxide product is protonated to give an aldol.




In the last step, the C6–O7 bond is broken, and the elements of H₂O are lost. This β -elimination reaction proceeds by the E1cb mechanism because of the poor leaving group ability of ⁻OH and the acidity of C13.




Note that every proton transfer occurs in two steps by protonation with EtOH, then deprotonation by EtO⁻, not in one step by intramolecular proton transfer!

Problem 2.5 Each of the following reactions has a Michael reaction as a first step. Draw a reasonable mechanism for each reaction.


(a)



(b)



(c)




It is difficult to overemphasize the importance of the Michael reaction in synthesis. It is one of the mildest, most versatile, and most efficient methods for forming C–C bonds.

2.3 Substitution at C(sp²)-X σ Bonds

2.3.1 Substitution at Carbonyl C

Many carbonyl compounds, including esters, acyl chlorides, and acid anhydrides, have leaving groups attached to the carbonyl C, and many reactions proceed with substitution of this leaving group by a nucleophile. Substitutions at carbonyl C usually occur by an *addition–elimination* mechanism. The nucleophile Nu⁻ adds to


the electrophilic C of the carbonyl group to make a tetrahedral intermediate. The leaving group X^- then leaves to give a new carbonyl compound. Note that either X^- or Nu^- may be expelled from the tetrahedral intermediate. Which one is expelled depends on the nature of the two groups and the reaction conditions. Expulsion of Nu^- , though, gives back the starting material, which is not very productive!



Common error alert: $C(sp^2)$ electrophiles do not undergo substitution by the S_N2 mechanism. The two-step mechanism for substitution at carbonyl C is much more reasonable than a one-step, S_N2 mechanism for several reasons. The $C=O$ π bond is higher in energy than the $C(sp^2)-X$ bond, so it's easier to break. Moreover, addition of Nu^- to the $C=O$ π bond can occur along a trajectory that is out of the plane of the carbonyl group, whereas an S_N2 trajectory must be in the crowded plane of the carbonyl group. In addition to these theoretical considerations, plenty of experimental evidence suggests that the two-step mechanism is always operative. (See any physical organic chemistry textbook for details.)


Primary amines react with many esters just upon mixing to give amides. The amines are sufficiently nucleophilic to add to the ester carbonyl. After the nucleophilic N is deprotonated, the alkoxy group is a much better leaving group, so collapse of the tetrahedral intermediate occurs with expulsion of ^-OR to give the amide as the product.

Example



Transesterification of esters occurs by a mechanism very much like amide synthesis, but the reaction requires a catalytic amount of base (usually the Na salt of


the alcohol). The nucleophile is the alkoxide. The reaction is driven in the forward direction by the use of a large excess of the starting alcohol.



Problem 2.6 Why cannot carboxylic acids be esterified similarly?




Serine proteases, a large group of enzymes found in both eukaryotic and prokaryotic organisms, use a similar base-catalyzed reaction to promote the hydrolysis of the amide bonds of peptides and proteins. In the first part of the reaction, the basic imidazole group of a histidine residue in the protein active site deprotonates the OH group of a serine residue, and the nascent alkoxide adds to the carbonyl C of a peptide or protein amide that is also present in the active site to give the classical tetrahedral intermediate. The electrons on O then move to recreate the C=O π bond, expelling N, which simultaneously deprotonates the imidazolium N to give the neutral amine and an *O*-acylserine. In the second part of the reaction, a molecule of H₂O enters the active site, and, as the imidazole deprotonates it, the developing negative charge on the O adds to the carbonyl group of the *O*-acylserine to again give the classical tetrahedral intermediate. The electrons on O⁻ then move to recreate the C=O π bond, forming a carboxylic acid and expelling the O of serine, which simultaneously deprotonates the imidazolium N to bring the active site back to its original state. The overall rate of the protease-catalyzed amide hydrolysis is much faster than it would have been under physiological conditions without the enzyme.




In a nonenzymatic reaction, it is rare for three or more reactants to encounter one another in the proper trajectories and energies to react with one another concurrently, so it is generally unreasonable to draw three or more compounds taking part in a single mechanistic step. In

an enzymatic reaction, however, because the active site can hold several different reactants close to one another in a preferred spatial arrangement, it is often reasonable to draw three or more compounds reacting concurrently with one another. For example, in the NaOH-catalyzed (nonenzymatic) hydrolysis of an amide, it would not be very reasonable to show the base deprotonating H₂O at the same time that the H₂O attacked the carbonyl C, but in the serine protease-catalyzed hydrolysis of an amide, such a step is reasonable.

The reaction of alcohols with *enolizable acyl chlorides* or *anhydrides* may proceed by two different mechanisms. One is the addition–elimination mechanism that has already been discussed.




The other is a two-step, *elimination–addition* mechanism. In the elimination step, β-elimination occurs by an E2 mechanism to give a *ketene*, a very reactive compound that is not usually isolable. In the addition step, the alkoxide adds to the electrophilic carbonyl C of the ketene to give the enolate of an ester. Acyl chlorides lacking α-hydrogens (*t*-BuCOCl, ArCOCl), of course, can react only by the addition–elimination mechanism.




Often a nucleophilic catalyst such as DMAP (4-dimethylaminopyridine) is added to accelerate the acylation of alcohols R'OH with acyl chlorides and anhydrides. DMAP is a better nucleophile than ⁻OR', so it reacts more quickly with the acyl electrophile than ⁻OR' to give an acylpyridinium ion by addition–elimination. The acylpyridinium ion, though, is more reactive than an acyl electrophile, so ⁻OR' adds more quickly to it than to the acyl anhydride. The two addition–eliminations involving DMAP are together faster than the single one involving ⁻OR'. A rate acceleration is also observed with I⁻, another great nucleophile and great leaving group.

without catalysis:




with catalysis:



The *Claisen* and *Dieckmann condensations* are reactions in which an ester enolate acts as a nucleophile toward an ester. The Dieckmann condensation is simply the intramolecular variant of the Claisen condensation. In these reactions, the alkoxy part of the ester is substituted with an enolate to give a β -ketoester. A stoichiometric amount of base is required for this reaction, because the product is a very good acid, and it quenches the base catalyst. In fact, this quenching reaction is what drives the overall reaction to completion. The Claisen condensation is especially useful when one of the esters is nonenolizable (e.g., diethyl oxalate, ethyl formate, or diethyl carbonate).


Example




Ketones are acylated with esters in a similar manner. The product is a 1,3-diketone. Again, with intermolecular condensations, the reaction is especially important with nonenolizable esters such as diethyl carbonate, diethyl oxalate, and ethyl formate. And again, the reaction is driven to completion by deprotonation of the very acidic 1,3-dicarbonyl product.

Problem 2.7 Draw mechanisms for the following two acylation reactions.


(a)






Like aldol reactions, the addition of enolates to esters is reversible. 1,3-Dicarbonyl compounds that cannot be deprotonated cleave readily under basic conditions to give two simple carbonyl compounds. The cleavage occurs by addition–elimination, and an enolate acts as a leaving group.

Example



Grignard reagents, organolithium compounds, and complex metal hydrides react with esters to give alcohols. The nucleophiles first react by addition–elimination to give a transient ketone or aldehyde. The ketone or aldehyde is more reactive than the starting material toward the nucleophile, though, so another equivalent of nucleophile adds to it to give alcohol after workup.


Example



Nitriles are in the same oxidation state as esters, so you might expect the addition of Grignard reagents to nitriles to give primary amines, but, as noted earlier, addition to nitriles stops after a single addition because no leaving group can be expelled to give a newly electrophilic intermediate.


When Grignard reagents, organolithium compounds, or complex metal hydrides add to amides, the elimination step is slow at $-78\text{ }^{\circ}\text{C}$, especially when the amine component is $-\text{N}(\text{Me})\text{OMe}$ (*Weinreb amides*). When the tetrahedral intermediate is sufficiently long lived, quenching of the reaction mixture with water at $-78\text{ }^{\circ}\text{C}$ gives the ketone or aldehyde rather than the alcohol.

Example




The O atom of sulfoxides is weakly nucleophilic, and it reacts with acyl anhydrides or acyl chlorides. In the *Pummerer rearrangement*, a sulfoxide and an acyl anhydride are converted to a mixed O,S-acetal, which can be hydrolyzed to provide an aldehyde and a thiol. The mechanism of the reaction begins with the sulfoxide O atom attacking Ac_2O (or some other acyl anhydride) in an addition–elimination reaction to give an acetoxy-sulfonium ion. E2 elimination of AcOH from this compound then provides a new sulfonium ion with a $\text{C}=\text{S}^+$ π bond. The very electrophilic C atom is then attacked by acetate to give the O,S-acetal. Hydrolysis of the O,S-acetal proceeds by the usual addition–elimination mechanism. Later, we will see a reaction involving sulfoxides and an acyl chloride that begins the same way.

Example




2.3.2 Substitution at Alkenyl and Aryl C

α,β -Unsaturated carbonyl compounds with a leaving group in the β position are susceptible to addition–elimination reactions just like ordinary carbonyl compounds. The functional group $\text{X}-\text{C}=\text{C}-\text{C}=\text{O}$ is often described as a *vinyllogous* form of $\text{X}-\text{C}=\text{O}$. For example, 3-chloro-2-cyclohexen-1-one reacts with NaCN to give 3-cyano-2-cyclohexen-1-one by an addition–elimination mechanism. The electrophile is a vinyllogous acyl chloride, and its reactivity at the C attached to Cl is similar to the reactivity of an acyl chloride.




Aromatic compounds that are substituted with electron-withdrawing groups (usually nitro groups) undergo nucleophilic aromatic substitution reactions by this mechanism. Because addition of the nucleophile to the ring disrupts the aromaticity, at least one and preferably two electron-withdrawing groups are required to make the aromatic ring sufficiently electron-deficient that addition proceeds at a reasonable rate. Sanger's reagent, 2,4-dinitrofluorobenzene, reacts with amines in this fashion. Halopyridines undergo substitution reactions by an exactly analogous mechanism. Addition–elimination at aromatic rings is often called $\text{S}_{\text{N}}\text{Ar}$ for no particularly good reason, and the anionic intermediate is called a *Meisenheimer complex*.

Example




Problem 2.8 Draw mechanisms for the following two aromatic substitution reactions. *Note:* The second problem will be much easier to solve if you draw the coproduct.

(a)




(b)




Nucleophilic substitution can also occur at aryl rings that are not substituted with electron-withdrawing groups, although it is not seen as often. Two mechanisms are possible: $\text{S}_{\text{RN}}1$ and elimination–addition. The $\text{S}_{\text{RN}}1$ mechanism is a radical chain mechanism. (The R in $\text{S}_{\text{RN}}1$ stands for *radical*.) As such, it has three parts: initiation, propagation, and termination. Consider the following reaction.

Overall:




The reaction is *initiated* by electron transfer from the HOMO of the nucleophile (Nu^-) to the LUMO of the electrophile (R-X) to generate two radicals, $\text{Nu}\cdot$ and

$[\text{RX}]^{\pm}$ (a *radical anion*) (See Chap. 5 for a more complete discussion.) If the energies of the HOMO_{nucleophile} and the LUMO_{electrophile} are close enough, the transfer can occur spontaneously. In this particular example, light ($h\nu$) is used to promote an electron in the HOMO of the enolate nucleophile to its LUMO so that electron transfer can occur more readily. If the electron transfer is particularly slow, catalytic amounts of one-electron reducing agents (e.g., FeBr₂) can be added to initiate the chain reaction by electron transfer to the electrophile. When the electrophile is an aromatic compound, as it is in this example, it is most convenient to show the electron being transferred to the electrophilic C atom of the ring, and the π bond of the electrophilic C moving to form a lone pair and a formal negative charge on the adjacent atom.



A one-electron electron-flow arrow pointing from an atom *directly* to another atom is used to show an electron transfer, although this arrow is often omitted. A *two*-electron electron-flow arrow, however, does not indicate two-electron transfer, a process which is extremely unlikely; instead, it indicates that the electrons are forming a bond *between* the two atoms.


The *propagation* part of an S_{RN}1 mechanism consists of three steps. In the first step, the lone pair adjacent to the radical in $[\text{RX}]^{\pm}$ expels the leaving group and reestablishes the previously broken π bond to give X⁻ and R \cdot . In the second step, R \cdot combines with Nu⁻ to give a new radical anion, $[\text{RNu}]^{\pm}$. This step is just the reverse of the first step (with a different nucleophile, of course)! It is most convenient to draw this step as the addition of the nucleophile to the π bond of the electrophilic C atom, with the electrons of the π bond again moving to the adjacent atom to make a lone pair. In the third step, electron transfer from $[\text{RNu}]^{\pm}$ to the original starting material R-X occurs to give R-Nu (the substitution product) and to regenerate $[\text{RX}]^{\pm}$, the same radical as was generated in the initiation, completing the chain.



Note that the first two steps of the propagation part look a lot like the S_N1 substitution reaction (Chap. 3)—a leaving group leaves, then the nucleophile comes in—except that an alkyl radical is formed as a transient intermediate instead of a carbocation.

The best nucleophiles for the $S_{RN}1$ mechanism can make a relatively stable radical in the initiation part, either by resonance (enolates) or by placing the radical on a heavy element (second-row main-group or heavier nucleophiles). The best electrophiles are aryl bromides and iodides. If light is required for substitution to occur, the mechanism is almost certainly $S_{RN}1$. Substitution at alkenyl $C(sp^2)$ -X bonds can also occur by an $S_{RN}1$ mechanism.


Arenediazonium ions, ArN_2^+ or ArN_2^+ , which are usually prepared from $ArNH_2$ under acidic conditions (Chap. 3), bear one of the world's best leaving groups, and they undergo substitution reactions with many nucleophiles to which other $C(sp^2)$ electrophiles are resistant. For example, ArN_2^+ reacts with H_3PO_2 (hypophosphorous acid) to replace the N_2^+ group with H. This reaction probably proceeds by a variation on the $S_{RN}1$ mechanism. The reaction is initiated by electron transfer from H_3PO_2 to the terminal N of the N_2^+ group to give $Ar\ddot{N}=N\cdot$. The propagation part of the mechanism then begins with homolytic cleavage of the C-N bond of $Ar\ddot{N}=N\cdot$ to give $Ar\cdot$ and N_2 . Next, in a departure from the previously discussed $S_{RN}1$ mechanism, $Ar\cdot$ abstracts H \cdot from $H_2\overset{+}{P}(OH)O^-$ to give the product ArH and the new radical $H\overset{+}{P}(OH)O\cdot$. Finally, electron transfer from $H\overset{+}{P}(OH)O\cdot$ to ArN_2^+ completes the chain and generates the cation $H\overset{+}{P}(OH)=O$, which reacts with H_2O to give H_3PO_3 (phosphorous acid), the ultimate coproduct of the reaction.




Arenediazonium ions also react with KI and a variety of copper salts CuX to replace the N₂⁺ group with I, Br, Cl, OH, or CN. The reaction with KI proceeds by a conventional S_{RN}1 mechanism, but the other reactions proceed by more complex mechanisms involving multiple electron transfer steps, and we won't discuss them here.

Problem 2.9 Draw an S_{RN}1 mechanism for the reaction of PhN≡N⁺ with KI.


Simple aryl halides undergo substitution reactions with very strong bases such as ⁻NH₂. Neither the addition–elimination mechanism nor the S_{RN}1 mechanism seems very likely for this pair of substrates.



The generally accepted mechanism for this reaction is a two-step *elimination–addition* mechanism. In the β -elimination step, NH₂⁻ promotes the β -elimination of the elements of HI to give benzyne. In the addition step, NH₂⁻ adds to the very strained triple bond to give an aryl anion, which undergoes proton transfer. Workup gives the neutral product.



One piece of evidence for this mechanism is that the reaction of strong bases with *o*- and *m*-substituted aryl halides gives a mixture of products resulting from substitution *both* at the C bearing the leaving group *and* at its next-door neighbor. Neither the addition–elimination mechanism nor the S_{RN}1 mechanism can account for this observation.



Problem 2.10 Draw a mechanism explaining why two products are obtained from the reaction of *o*-iodoanisole and sodamide.

Problem 2.11 Alkenyl halides such as CH₃CBr=CHCH₃ do not undergo substitution upon treatment with a strongly basic nucleophile such as ⁻NH₂. What reaction occurs instead, and why does substitution not occur?


Aromatic substitution reactions that proceed by the elimination–addition mechanism are not widely used synthetically, as a very strong base ($\text{p}K_{\text{b}} \geq 35$) is required to generate the aryne intermediate by β -elimination of HX. In addition, there is regiochemical ambiguity for unsymmetrical aryl halides. Even benzyne itself is much more readily prepared by several other methods.

In summary, aryl halides can undergo substitution by addition–elimination, $\text{S}_{\text{RN}}1$, or elimination–addition mechanisms under basic conditions. The addition–elimination mechanism is most reasonable when the arene is electron-poor. When the arene is not electron-poor, the $\text{S}_{\text{RN}}1$ mechanism is most reasonable either when the nucleophile is a heavy atom or is delocalized, when light is required, or when a catalytic amount of a one-electron reducing agent is added. The elimination–addition mechanism is most reasonable when the arene is not electron-poor and when very strong base ($\text{p}K_{\text{b}} \geq 35$) is used. **Common error alert:** *The $\text{S}_{\text{N}}2$ mechanism is not an option for aryl halides.*


Problem 2.12 Hexachlorobenzene (C_6Cl_6) undergoes six substitutions with PhS^- to give $\text{C}_6(\text{SPh})_6$. Are the most reasonable mechanisms for the first and sixth substitutions the same or different? Draw mechanisms for these two substitutions.

2.3.3 Metal Insertion, Halogen–Metal Exchange

Aryl and alkenyl halides undergo reactions with metals such as Zn, Mg, and Li to give products where the C–X bond is replaced with a C–metal bond. The best-known metal insertion reaction is the Grignard reaction, which uses Mg. Lithiation requires two equivalents of Li, because each Li supplies only one electron, but the Grignard and zinc insertion reactions require only one equivalent of metal. The rate of insertion is strongly dependent on X, with $\text{I} > \text{Br} \gg \text{Cl}$, corresponding to the strength of the C–X bonds.




The mechanism of metal insertion is best understood as an electron-transfer process. One-electron transfer from Li to PhI gives a radical anion that is best drawn with the lone electron on the electrophilic C atom and a lone pair and negative charge on the adjacent C atom, as in the $\text{S}_{\text{RN}}1$ mechanism. The departure of I^- gives Ph^- , which combines with another equivalent of Li to give the carbanionic product.




When an aryl or alkenyl halide (RX) is treated with an alkyl lithium compound ($R'Li$), *halogen–metal exchange* can take place. The Li and X swap places to give RLi and $R'X$. The conversion of the $C(sp^3)-Li$ bond to the less basic $C(sp^2)-Li$ bond provides the driving force for the halogen–metal exchange. Three reasonable mechanisms can be drawn for this reaction: (1) an S_N2 substitution at the halogen atom, with the organic anion R^- acting as a leaving group; (2) an addition–elimination mechanism with a ten-electron Br intermediate; or, (3) an electron-transfer mechanism. The last mechanism, like the $S_{RN}1$ mechanism, features radical anion intermediates, but, in contrast to the $S_{RN}1$ mechanism, it is not a chain reaction. One of the steps of the electron-transfer mechanism involves a compound that is most conveniently depicted as a nine-electron Br intermediate. Heavy atoms can violate the octet rule without substantial energetic cost.


S_N2 mechanism for halogen–metal exchange




Addition–elimination mechanism for halogen–metal exchange



Electron-transfer mechanism for halogen–metal exchange



Halogen–metal exchanges are extremely fast reactions, occurring faster than mixing at $-78\text{ }^{\circ}\text{C}$! Both aryl and alkenyl bromides and iodides are substrates for halogen–metal exchange, but tosylates and other pseudohalides do not undergo halogen–metal exchange, and the exchange with chlorides is very slow. The organolithium compound may be CH_3Li , $n\text{-BuLi}$, $t\text{-BuLi}$, or $s\text{-BuLi}$. When $t\text{-BuLi}$ is used, *two* equivalents are required to drive the exchange to completion. The second equivalent of $t\text{-BuLi}$ acts as a base toward the coproduct $t\text{-BuX}$ to give isobutane, isobutylene, and LiX by a β -elimination reaction.



When CH_3Li or $n\text{-BuLi}$ is used in halogen–metal exchange, a rather electrophilic MeX or $n\text{-BuX}$ is obtained as a coproduct. This alkyl halide can undergo $\text{S}_{\text{N}}2$ substitution with the organolithium compound as nucleophile to give a product that looks like it has been formed by a nucleophilic aromatic substitution mechanism. However, $\text{S}_{\text{N}}2$ reactions of organolithium compounds with alkyl halides are rather slow at the low temperatures at which halogen–metal exchange is usually executed, so this side reaction is usually not a problem.

The aryl- or alkenyllithium compounds that are obtained from halogen–metal exchange are used as nucleophiles in subsequent reactions, usually toward π bond electrophiles such as carbonyl compounds.

2.4 Substitution and Elimination at $\text{C}(\text{sp}^3)\text{-X}$ σ Bonds, Part II


Substitution by the $\text{S}_{\text{N}}2$ mechanism and β -elimination by the $\text{E}2$ or $\text{E}1\text{cb}$ mechanism are not the only reactions that can occur at $\text{C}(\text{sp}^3)\text{-X}$. Substitution can also occur at $\text{C}(\text{sp}^3)\text{-X}$ by the $\text{S}_{\text{RN}}1$ mechanism, the *elimination–addition* mechanism, a *one-electron transfer mechanism*, and metal insertion and halogen–metal exchange reactions. An alkyl halide can also undergo α -elimination to give a carbene.

2.4.1 Substitution by the $\text{S}_{\text{RN}}1$ Mechanism

Tertiary alkyl halides *usually* undergo $\text{E}2$ elimination under basic conditions, but sometimes nucleophilic substitution occurs. In these cases, the mechanism *cannot* be $\text{S}_{\text{N}}2$ (unless the reaction is intramolecular). The $\text{S}_{\text{RN}}1$ mechanism can operate at $\text{C}(\text{sp}^3)$ under basic conditions. The $\text{S}_{\text{RN}}1$ mechanism for $\text{C}(\text{sp}^3)\text{-X}$ electrophiles is exactly the same as it is for $\text{C}(\text{sp}^2)\text{-X}$ electrophiles. Initiation occurs by electron transfer from the nucleophile to the electrophile to give a radical anion. Sometimes light is used to photoexcite the nucleophile to encourage it to transfer its electron,

and sometimes a one-electron reducing reagent (Chap. 5) is added to initiate the reaction instead. Propagation occurs by leaving-group dissociation to give the neutral radical, addition of the nucleophile to the radical to give a new radical anion, and electron transfer from the radical anion to another equivalent of starting electrophile.

Example




When the electrophile in an $S_{RN}1$ mechanism is $C(sp^3)-X$, it is not possible to draw the electron transfer step and the radical anion intermediates in the same way as they were drawn for $C(sp^2)-X$ electrophiles. Instead, it is usually best to transfer the lone electron to a π bond or heavy atom in the leaving group. In this particular example, the electron was transferred to the neutral O of the nitro group, moving the π bond electrons to form a lone pair on the N, so that it was easy to draw the cleavage of the C–N bond in the subsequent step to give a C radical. If the leaving group is a heavy atom such as Br or I, one can transfer the electron directly to the heavy atom to give a nine-electron intermediate.


The best nucleophiles for the $S_{RN}1$ mechanism can make a relatively stable radical in the initiation part, either by resonance (enolates) or by placing the radical on a heavy element (second-row or heavier nucleophiles). The best electrophiles for the $S_{RN}1$ mechanism are able to delocalize the odd electron in the radical anion (aromatic leaving groups, carbonyl compounds), can make a stable radical (3° alkyl halides), and have a weak R–X (Br, I) bond. Tosylates and other pseudohalides are very poor $S_{RN}1$ electrophiles. If light is required for substitution to occur, the mechanism is almost certainly $S_{RN}1$.

2.4.2 Substitution by the Elimination–Addition Mechanism


A third mechanism for substitution at $C(sp^3)\text{-X}$ bonds under basic conditions, *elimination–addition*, is occasionally seen. The stereochemical outcome of the substitution reaction in the figure tells us that a direct S_N2 substitution is not occurring. Two sequential S_N2 reactions would explain the retention of stereochemistry, but the problem with this explanation is that backside attack of MeO^- on the extremely hindered top face of the bromide is simply not reasonable. The $S_{RN}1$ mechanism can also be ruled out, as the first-row, localized nucleophile MeO^- and the 2° alkyl halide are unlikely substrates for such a mechanism.



An *elimination–addition* mechanism can be proposed. MeO^- is both a good nucleophile and a good base. It can induce β -elimination of HBr (probably by an $E1_{cb}$ mechanism because of the nonperiplanar relationship between the C-H and C-Br bonds) to give a compound that is now π -electrophilic at the C that was formerly σ -electrophilic. Another equivalent of MeO^- can now undergo *conjugate addition* to the electrophilic C ; the addition occurs from the bottom face for steric reasons. Proton transfer then gives the observed product.




Sometimes both the S_N2 and the elimination–addition mechanisms are reasonable. The substitution reaction shown below proceeds more quickly than one would expect from a 2° alkyl chloride, suggesting that the elimination–addition mechanism is operative, but an S_N2 mechanism for the reaction is not unreasonable. Experimental evidence is required to determine unambiguously which mechanism is actually occurring.




The elimination–addition mechanism for substitution is reasonable *only when elimination gives an alkene that is a π -bond electrophile at the C to which the leaving group was originally attached*. Most often the leaving group is β to a carbonyl, as in both preceding examples, but not always. If a substitution reaction gives a stereochemical result other than inversion or involves a very hindered substrate, then a simple S_N2 mechanism can be ruled out, and elimination–addition (and, of course, $S_{RN}1$) should be considered.

Problem 2.13 Is an elimination–addition mechanism reasonable for the following reactions? Draw the most reasonable mechanism for each one.

(a)




(b)



2.4.3 Substitution by the One-Electron Transfer Mechanism


One more mechanism for substitution at $C(sp^3)-X$ bonds, the *one-electron transfer mechanism*, should be discussed. This mechanism is related to the $S_{RN}1$ mechanism, but it is not a chain mechanism. Instead, after one-electron transfer from nucleophile to electrophile to give a radical anion (drawn as having a nine-electron halogen atom) and departure of the leaving group, radical–radical combination occurs to give the product.




It is not possible to distinguish the electron transfer mechanism from the S_N2 or $S_{RN}1$ mechanism by cursory examination of the reaction conditions and substrates, so it is rarely appropriate to propose this mechanism. However, you should be aware that some chemists believe that *all* substitution reactions are initiated by electron transfer.

2.4.4 Metal Insertion, Halogen–Metal Exchange


Alkyl chlorides, bromides, and iodides undergo metal insertion reactions with Li, Mg, and Zn, just as aryl and alkenyl halides do. The reaction is more facile for heavier halogens.




The *Reformatsky reaction*, in which an α -bromocarbonyl compound was treated with Zn to give an enolate, was for a very long time the only way of quantitatively making enolates of weakly acidic carbonyl compounds. Nowadays, it has been superseded by strong nonnucleophilic bases like LDA and KHMDS.




When metallation is carried out on an alkyl halide with a leaving group on the adjacent atom, β -elimination occurs very rapidly to give an alkene. Zinc is usually used to execute this reaction. The adjacent leaving group is a halide or pseudo-halide, a carboxylate, or even an alkoxy group. The reaction accomplishes the reverse of halogenation or cohalogenation of a double bond (Chap. 3). Dibromoethane is often used to initiate Grignard reactions because it reacts quickly with Mg to give the innocuous coproducts ethylene and MgBr₂.




Problem 2.14 Draw a mechanism involving a metal insertion for the following reaction.



Halogen–metal exchange is much less generally useful for C(sp³) halides than it is for C(sp²) halides. The exchange is thermodynamically driven, so it proceeds at reasonable rates only with 1° alkyl iodides (RCH₂I) and two equivalents of *t*-BuLi (not MeLi, *n*-BuLi, or *s*-BuLi).




However, bromo- and dibromocyclopropanes do undergo halogen–metal exchange at reasonable rates. The exocyclic bonds in cyclopropanes have a lot of *s* orbital character, so the cyclopropyl anion is much lower in energy than an ordinary C(sp³) anion. Organolithium reagents less reactive than *t*-BuLi (e.g., *n*-BuLi and MeLi) can undergo halogen–metal exchange with cyclopropyl halides. In the case of dibromocyclopropanes, the bromolithium compound can react with an electrophile without undergoing α-elimination (see discussion below) if it is maintained at sufficiently low temperature.




2.4.5 α-Elimination. Generation and Reactions of Carbenes

Consider an alkyl halide like CHCl₃ that has no β-hydrogen and so cannot undergo β-elimination. The inductive withdrawing effect of the Cl atoms renders the H atom acidic enough to be removed by *t*-BuOK. However, once the H atom is removed, there is a lot of repulsion between the lone pairs on the C atom and the Cl atoms, and the electropositive C atom is unhappy about having a negative charge, so a Cl atom can leave to give a *singlet carbene*, a neutral, divalent C with a lone pair and an empty orbital. The overall reaction is called α-elimination. It is convenient to depict a singlet carbene as a C atom with both a formal positive and a formal negative charge to emphasize the presence of both filled and empty orbitals, although of course the C atom has no formal charge at all.




The two unshared electrons in singlet carbenes have opposite spins. Carbenes generated by α -elimination are singlets because the two unshared electrons are derived from the same MO. *Triplet* carbenes, in which the two unshared electrons have parallel spins, are usually generated by photolysis of diazo compounds. Triplet carbenes are discussed in Chap. 5.


The most widely used substrates for α -elimination reactions are chloroform and bromoform, but other halides can also undergo α -elimination. For example, allyl chloride undergoes α -elimination when it is treated with a very strong base.




α -Elimination can also occur after halogen-metal exchange on a dibromocyclopropane.




α -Elimination can occur even at N. For example, *N*-tosylhydrazones are converted into diazoalkanes by α -elimination of TsH (toluenesulfonic acid).



Carbenoids are compounds that react like carbenes but are not true divalent C species. The *Simmons-Smith reagent* (ICH_2ZnI) is a widely used carbenoid. The reagent is derived by insertion of Zn into one of the C-I bonds of CH_2I_2 . (The rate of insertion of ordinary Zn dust into the C-I bond is very slow, so *zinc-copper couple*, or $\text{Zn}(\text{Cu})$, is used instead. The small amount of Cu on the Zn surface promotes the insertion reaction.) By examining the polarity of the C-I and C-Zn bonds, you can see how ICH_2ZnI might want to undergo α -elimination to give a carbene. In fact, it does not, but it does undergo typical carbene reactions.




Carbenes and carbenoids can also be generated from diazo compounds ($\text{R}_2\text{C}=\text{N}_2 \leftrightarrow \text{R}_2\text{C}=\overset{+}{\text{N}}=\overset{-}{\text{N}} \leftrightarrow \text{R}_2\text{C}^{\ominus}-\overset{+}{\text{N}}\equiv\text{N}$) by several nonbasic methods. We discuss them here because the reactivities of carbenes and carbenoids are the same no matter how they are generated. Diazo compounds are converted to singlet carbenes upon gentle warming and to carbenoids by treatment with a Rh(II) or Cu(II) salt such as $\text{Rh}_2(\text{OAc})_4$ or CuCl_2 . The transition-metal-derived carbenoids, which have a metal=C double bond, undergo the reactions typical of singlet carbenes. At this point, you can think of them as free singlet carbenes, even though they're not. Metal carbenoids are discussed in more detail in Chap. 6.





No matter how they are generated, carbenes and carbenoids undergo four typical reactions. The most widely used reaction is *cyclopropanation*, or *addition to a π bond*. The mechanism is a concerted [2 + 1] cycloaddition (see Chap. 4). The carbenes derived from chloroform and bromoform can be used to add CX_2 to a π bond to give a dihalocyclopropane, while the Simmons–Smith reagent adds CH_2 . Carbenoids generated from diazoalkanes with catalytic Rh(II) or Cu(II) also undergo cyclopropanations.

Example




Problem 2.15 Draw mechanisms for the following two cyclopropanation reactions.




The second typical reaction of carbenes is *insertion into a C–H bond*. This three-centered reaction is similar to cyclopropanation, except that the carbene latches onto a σ bond instead of a π bond. Again, both carbenes and carbenoids can undergo this reaction. It is most useful when it occurs in intramolecular fashion. If the C of the C–H bond is stereogenic, the reaction proceeds with retention of configuration.


Example




Base-promoted α -elimination of $\text{Ts}-\text{H}$ from the hydrazone gives a diazo compound.




Under the reaction conditions the diazo compound decomposes to give a carbene, which undergoes a C–H insertion reaction to give the highly strained product.




Problem 2.16 Draw a mechanism for the following C–H insertion reaction.



The third typical reaction of carbenes is *combination with a nucleophile*. Carbenes are electron-deficient species, so they combine with nucleophiles that have reactive lone pairs. Addition of a carbonyl O to a carbene gives a *carbonyl ylide*, a reactive compound useful for making furan rings by a 1,3-dipolar cycloaddition reaction (see Chap. 4).



The fourth typical reaction of carbenes is a *1,2-shift*. A group on the adjacent C migrates to the carbene C with its pair of electrons, giving an alkene. The 1,2-shift severely limits the usefulness of many substituted carbenes. For example, when cyclohexene is treated with Zn/Cu and CH₂I₂, a cyclopropane is obtained in over 50% yield; with CH₃CHI₂, the yield is only 5%. Most of the CH₃CH(I)ZnI is converted to CH₂=CH₂. The 1,2-shift can be made more useful, as in the Wolff rearrangement of α -diazoketones and Curtius rearrangement of acyl azides (see below), but these reactions generally do not proceed through free carbenes or nitrenes under thermal conditions.




2.5 Base-Promoted Rearrangements

A rearrangement is a reaction in which C–C σ bonds have both broken and formed in the course of a reaction involving just a single substrate. It is often more difficult to draw a reasonable mechanism for a rearrangement than for any other kind of reaction. When you draw a mechanism for a rearrangement reaction, it is especially important to determine exactly which bonds are being broken and which are formed. Do this by numbering the atoms in the starting materials, identifying the

atoms by the same numbers in the products, and making a list of bonds that are made and broken in the reaction.


Rearrangement reactions under basic conditions usually involve addition of a nucleophile to a carbonyl group followed by cleavage of one of the C–C σ bonds. The reaction is simply an addition–elimination reaction in which the leaving group is an alkyl group. The difference between this and most addition–elimination reactions of carbonyl compounds, of course, is that R^- is a horrid leaving group (unless of course it is somehow stabilized, e.g., as an enolate). Rearrangements occur when the atom α to the carbonyl C is electrophilic or when the nucleophile is also an electrophile. R^- can then act as a leaving group because it *migrates* to the electrophilic atom in a 1,2-shift instead of leaving the compound entirely. The electrophilic atom may be either a σ -bond electrophile or a π -bond electrophile, and it may be C or a heteroatom.



2.5.1 Migration from C to C


In the *benzylic acid rearrangement* of 1,2-diketones, HO^- adds to one ketone. The tetrahedral intermediate can collapse by expelling HO^- , giving back starting material, or it can expel Ph^- . The Ph^- group leaves because there is an adjacent electrophilic C to which it can migrate to give the product.

Example



The *Favorskii rearrangement* differs from the benzylic acid rearrangement in that the α -carbon is a σ -bond electrophile rather than a π -bond electrophile.


Example



The mechanism shown, the *semibenzilic mechanism*, operates only when the ketone cannot enolize on the side opposite the leaving group, as in aryl ketones. When the ketone *can* enolize, a different mechanism is operative. This mechanism is discussed in Chap. 4.

Diazomethane (CH_2N_2) reacts with ketones ($\text{R}_2\text{C}=\text{O}$) to insert a CH_2 unit between the carbonyl and α -carbon atoms. The diazo compound acts as a nucleophile toward the electrophilic carbonyl C, and migration of R to the diazo C then occurs with expulsion of the great leaving group N_2 . In principle the reaction can occur with other diazo compounds, but in practice other diazo compounds are rarely used for this purpose, as they are much more difficult to prepare than CH_2N_2 . If the migrating R group is a stereocenter, retention of configuration occurs.


Example



In the *Wolff rearrangement*, an α -diazoketone is heated to give a ketene. The mechanism of the Wolff rearrangement consists of one step: the carbonyl substituent migrates to the diazo C and expels N_2 . When the reaction is executed in

H₂O or an alcohol, the ketene reacts with solvent to give a carboxylic acid or an ester as the ultimate product. (The mechanism of this reaction was discussed previously.)


Example



Light can be used to promote the Wolff rearrangement, too, and in this case the reaction is called the photo-Wolff rearrangement. The photo-Wolff rearrangement is probably a non-concerted reaction. First, N₂ leaves to give a free carbene, then the 1,2-alkyl shift occurs to give the ketene.

α -Diazoketones are often prepared by adding CH₂N₂ to an acyl chloride in a conventional addition–elimination reaction. In this case, the entire sequence from acid to acyl chloride to α -diazo ketone to ketene to acid is called the *Arndt–Eistert homologation*. More complex α -diazocarbonyl compounds can be made by the reaction of unsubstituted or monosubstituted 1,3-dicarbonyl compounds with sulfonyl azides. If the nucleophilic carbon is monosubstituted, one of the carbonyl groups is lost.

Problem 2.17 Draw a reasonable mechanism for the diazo transfer reaction. Your task will be much easier if you draw the coproducts.




2.5.2 Migration from C to O

The *Baeyer–Villiger oxidation*, in which the terminal O of a peracid (RCO₃H) reacts with a ketone to give an ester, proceeds by a similar mechanism to the reaction of diazomethane with ketones. However, the Baeyer–Villiger reaction is

usually effected under mildly acidic conditions, so the discussion of its mechanism will be postponed to Chap. 3.


2.5.3 Migration from C to N

In the *Curtius rearrangement*, an acyl azide undergoes rearrangement to an isocyanate upon gentle heating. The mechanism is exactly analogous to the Wolff rearrangement. The acyl azide may be prepared under basic conditions by reaction of an acyl chloride with NaN_3 , or under acidic conditions by reaction of an acyl hydrazide (RCONHNH_2) with nitrous acid (HNO_2) (The latter reaction is discussed in Chap. 3.)




The *Hofmann rearrangement* can also be used to convert a carboxylic acid derivative to an isocyanate. A carboxamide is treated with Br_2 and aqueous base to give an isocyanate, which is usually hydrolyzed under the reaction conditions to give an amine with one fewer carbon atom than the starting material. The reaction proceeds by deprotonation of the amide and *N*-bromination, then a second deprotonation and rearrangement. The amide N is more reactive than the amide O in the bromination step because N is deprotonated under the reaction conditions.

Example




2.5.4 Migration from B to C or O

Migration of R to a neighboring atom occurs in situations besides when R is attached to a carbonyl C. Trialkylboranes also undergo migration reactions. For example, a trialkylborane (R_3B) will react with H_2O_2 under basic conditions to give a trialkyl borate $[(RO)_3B]$, which is hydrolyzed in situ to give ROH. In a trialkylborane, B is electron-deficient, so it wants an octet. Upon treatment with basic H_2O_2 , HOO^- adds to B to give an eight-electron complex. But B is electropositive, and it doesn't want a formal negative charge. So it throws off an alkyl group, which migrates to the adjacent O, displacing HO^- . But now B is electron-deficient again, and it wants an octet again, so the process repeats itself until all the B–C bonds have been replaced with C–O bonds. The trialkylborate that is ultimately obtained undergoes hydrolysis to give the alcohol.



Boron, the whiniest element in the periodic table, is never satisfied with its electron count. When it lacks its octet, it complains about being electron-deficient, but when a nucleophile comes along to give it its octet, it complains about its formal negative charge.

The alkyl groups in boranes can migrate to C, too. For example, addition of the carbenoid equivalent $LiCHCl_2$, obtained by deprotonation of CH_2Cl_2 with LDA at low temperatures, to an alkylboronate gives the one-carbon homologous product. Other carbenoid equivalents such as diazo compounds and CO can undergo similar reactions.




2.6 Two Multistep Reactions

A few well-known and widely used reactions use a cocktail of several different reagents and proceed by multistep mechanisms that are not easily discerned by the beginning student. Two of these reactions, the Swern oxidation and the Mitsunobu reaction, are discussed here. You will find that faculty members enjoy asking

graduate students to draw mechanisms for these particular reactions, so you should learn them well!


2.6.1 The Swern Oxidation

When an alcohol is treated with a reaction mixture derived from oxalyl chloride, DMSO, and Et_3N , it is oxidized to the aldehyde or ketone. The order of addition is important. First, oxalyl chloride is added to DMSO; then, Et_3N and the alcohol are added, and the reaction mixture is allowed to warm to room temperature. The coproducts are Me_2S (very smelly!), CO_2 , CO , and $\text{Et}_3\text{NH}^+ \text{Cl}^-$.




The overall transformation with respect to the alcohol is an *elimination* of the elements of H_2 . The problem is that H^- is not a leaving group. Either C or O of the alcohol must have an attached H replaced by a leaving group before an elimination reaction can take place. The O of the alcohol is nucleophilic under basic conditions, and therefore the elimination reaction may take place first by attachment of a leaving group to O of the alcohol, and then by an E_2 elimination. The role of the DMSO and the oxalyl chloride, then, is to produce an electrophile that becomes a leaving group after it is attached to the alcohol O.


DMSO is nucleophilic on O. It reacts with the electrophilic oxalyl chloride by addition–elimination.



S now has a good-leaving group attached. Cl^- can come back and attack S, displacing the oxalate, which decomposes to give CO_2 , CO , and Cl^- . The S–O bond is thereby cleaved.




At this point S is a good electrophile. Now, the alcohol and Et_3N are added. The alcohol is deprotonated and attacks S, displacing Cl^- .



It is reasonable to draw the alkoxide attacking the S-oxalate compound *directly*, rather than having Cl^- intervene.

There is a good leaving group attached to the O of the former alcohol now, so an E_2 elimination can ensue, giving the aldehyde and Me_2S .




Although this last step is reasonable, it is not the way that the elimination actually takes place. In the currently accepted mechanism, the CH_3 group is deprotonated to give a *sulfur ylide*, and a *retro hetero-ene* reaction ensues. Retro hetero-ene reactions are discussed in Chap. 4.

Many variations on the Swern oxidation exist, usually involving replacing $(\text{COCl})_2$ with another activating agent such as $(\text{CF}_3\text{CO})_2\text{O}$ (trifluoroacetic anhydride, TFAA) or DCC (*N,N'*-dicyclohexylcarbodiimide, $\text{C}_6\text{H}_{11}\text{N}=\text{C}=\text{NC}_6\text{H}_{11}$). Some of these reactions even have different names associated with them. In all of them, though, the O of DMSO is converted into a good leaving group, the alcohol O displaces the leaving group from S, and an elimination of H^+ and Me_2S ensues to give the aldehyde (or ketone).

2.6.2 The Mitsunobu Reaction

In the Mitsunobu reaction, a chiral 2° alcohol and a carboxylic acid are converted to an ester with clean inversion at the electrophilic C. The reaction requires Ph_3P and $\text{EtO}_2\text{C}-\text{N}=\text{N}-\text{CO}_2\text{Et}$ (DEAD, diethyl azodicarboxylate). It is usually carried out by adding DEAD slowly to a mixture of the alcohol, Ph_3P , and the carboxylic acid.




The reaction is clearly not a simple $\text{S}_{\text{N}}2$ displacement of OH^- from R by PhCO_2^- , because HO^- is a really awful leaving group in $\text{S}_{\text{N}}2$ reactions and will not leave under these mild conditions, and besides, Ph_3P and DEAD are required for the


reaction. But clearly, S_N2 displacement must happen at some point, or clean inversion at R could not occur.

Balancing the equation shows that H_2O has been lost. Whenever Ph_3P is used in a reaction, it is almost always converted to Ph_3PO . The other coproduct, then, must be $EtO_2CNHNHCO_2Et$. Because a single S_N2 displacement has occurred at the alcohol C, both O atoms in the product must come from benzoic acid, which means that the former alcohol O must end up attached to Ph_3P . Both the alcohol O and P are nucleophilic, so the role of the DEAD must be to convert one of them from a nucleophile into an electrophile. DEAD itself is a potent electrophile, with two electrophilic N atoms.

The first part of the mechanism of the Mitsunobu reaction involves addition of nucleophilic Ph_3P to the electrophilic N in DEAD. (One could have the alcohol add to DEAD instead, but P is far more nucleophilic.) The addition is preceded by protonation of DEAD by the carboxylic acid.




In the second part of the mechanism, the carboxylate displaces N from P in S_N2 fashion, giving an acyloxyphosphonium ion and a nitrogen anion. The latter then deprotonates the alcohol, generating an alkoxide, which displaces P from O to give an alkoxyphosphonium ion and to regenerate the carboxylate.



An alternative mechanism has the carboxylate deprotonate the alcohol, which then attacks the phosphoniumhydrazine to displace N from P. Although this scheme is more direct, it violates the pK_a rule (pK_a alcohol ≈ 17 , pK_b of carboxylate ≈ 5).

The nascent alkoxyphosphonium ion is a much better σ -bond electrophile than the alcohol, so in the last part of the reaction mechanism, the carboxylate O attacks the electrophilic C of the oxyphosphonium salt in S_N2 fashion, displacing Ph_3PO to give the product.



The mild conditions required for the Mitsunobu reaction make it one of the best methods for inverting the configuration of an alcohol or subjecting a 2° alcohol to nucleophilic substitution. Normally, E2 elimination competes with S_N2 substitution at 2° C(sp³), but little or no elimination occurs in the Mitsunobu reaction.

2.7 Summary

A saturated carbonyl compound is electrophilic at the carbonyl carbon. It is nucleophilic at the α-carbon (and on oxygen) *after it has been deprotonated* to make an enolate.

An α,β-unsaturated carbonyl compound is electrophilic at the β- and carbonyl carbons. It is nucleophilic at the α-carbon *after a nucleophile has added* to the β-carbon to make an enolate. It is *not* acidic at the α-carbon.

sp³-Hybridized atoms undergo substitution by:

1. S_N2 (by far the most common: 1° or 2° halide, 3° halide only if intramolecular); or
2. S_{RN}1 (3° halide, delocalized or heavy nucleophile, sometimes *hν* or a one-electron donor); or
3. elimination–addition (when β-elimination makes the carbon at which substitution occurs a π-bond electrophile); or
4. metal insertion (Mg, Li, Zn) and (occasionally) halogen–metal exchange (*t*-BuLi).

sp²-Hybridized atoms undergo substitution by:

1. addition–elimination (by far the most common: carbonyls, electrophilic alkenes, aromatic compounds with electron-withdrawing groups);
2. elimination–addition (acyl chlorides; aromatic compounds when a very strong base is used);
3. S_{RN}1 (delocalized or heavy atom nucleophile, sometimes *hν* or a one-electron donor); or
4. metal insertion (Mg, Li, Zn) and halogen–metal exchange (*n*-BuLi, *t*-BuLi, MeLi, *s*-BuLi).

Singlet carbenes undergo four typical reactions:

1. addition to a π bond (cyclopropanation);
2. insertion into a C–H bond;
3. addition to a lone pair nucleophile; or
4. 1,2-shift.

Table 2.2 Polar substitution mechanisms under basic conditions

Sequence	Nu ⁻ adds first	Nu ⁻ adds and X ⁻ leaves simultaneously	X ⁻ leaves first
Mechanism	addition–elimination	S _N 2	elimination–addition, S _{RN} 1

Table 2.3 Polar elimination mechanisms under basic conditions

Sequence	C–H breaks first	C–H breaks and X ⁻ leaves simultaneously	X ⁻ leaves first
Mechanism	E1cb	E2	none

Carbonyl compounds in which the α -carbon is electrophilic often undergo rearrangement reactions. Addition of a nucleophile to a carbonyl compound often prompts a rearrangement reaction.

We started this chapter with an introduction to nucleophilic substitution and elimination reactions. We previously mentioned that there are three sequences in which the bond-making and bond-breaking steps of nucleophilic substitution can take place, and we have now seen examples of all three sequences (Table 2.2). The steps of addition–elimination take place in the first sequence; the steps of S_N2 take place in the second sequence; and the steps of elimination–addition and S_{RN}1 take place in the third sequence. All of these mechanisms have limitations in their scope.

- Addition–elimination occurs at C only when C can temporarily shed a pair of electrons, e.g., when it is π -bound to O.
- Because the electrophilic C atom is pentacoordinate in the transition state for the S_N2 mechanism, reactions that proceed by this mechanism are highly susceptible to steric bulk around the electrophilic C atom.
- The third sequence, in which X⁻ leaves first, seems to require a carbocationic intermediate. Because carbocations cannot exist under basic conditions, the third sequence occurs under basic conditions only under special circumstances: *either* (1) when an electron is transferred to the electrophile so that a radical, not a carbocation, is obtained when X⁻ leaves (S_{RN}1), *or* (2) when a pair of electrons from an adjacent C–H bond can be used to satisfy the electron demand of the C atom at which substitution takes place (elimination–addition). (Under acidic conditions, where carbocations can exist, the mechanism whose steps occur in the third sequence is quite common: it is known as S_N1.)

We also previously mentioned that there are three sequences in which the two bond-breaking steps of elimination can take place (Table 2.3). The third sequence requires the formation of a carbocationic intermediate, and carbocations do not form spontaneously under basic conditions, so the bond-breaking steps of elimination mechanisms are thought not to proceed by the third sequence under

basic conditions. (Under acidic conditions, where carbocations can exist, the mechanism whose steps occur in the third sequence is quite common, and it is known as E1.) By contrast, we have seen examples of mechanisms that proceed by the first two of these sequences; we call such mechanisms E1cb and E2, respectively. The E1cb mechanism forms an anionic intermediate; for this intermediate to have any reasonable lifetime at all (which it must have if the E1cb mechanism is to be distinguished from the E2 mechanism), it must be stabilized, and the leaving group adjacent to it must be a poor one.

The final step in a reaction that occurs under basic conditions is often protonation of the conjugate base of the product. Sometimes the requisite proton comes from an aqueous workup, sometimes from solvent, sometimes from the conjugate acid of a basic catalyst, and sometimes from more starting material. How do you know whence comes the proton? The answer depends on the amount of base and on the basicity of the conjugate base of the product.


- When a substoichiometric (catalytic) amount of base is used, the base must be regenerated so that it can go back and deprotonate more starting material; therefore, the proton must come from within the reaction mixture and not from aqueous workup. If the catalytic base is relatively weak (e.g., EtO^- , Et_3N), the proton can come from its conjugate acid. (The conjugate acid is generated in the very first step of the mechanism, when the base deprotonates the starting material.) If the catalytic base is very strong (e.g., NaH , LDA), the proton cannot come from its conjugate acid, so it must come from more starting material.
- When a stoichiometric or excess amount of base is used, all of the acidic protons of the starting material are consumed at the beginning of the reaction, and it is not necessary to regenerate the base at the end of the reaction. The proton of the final neutralization step must come from an aqueous workup.

If the relative amount of base is not specified, you must use your judgment about $\text{p}K_{\text{b}}$ values to judge whence the proton comes. Some reactions generate very acidic products that must be deprotonated and remain so until aqueous workup (e.g., hydrolysis of esters to carboxylic acids, Claisen condensation to give 1,3-dicarbonyl compounds). On the other hand, some reactions generate the conjugate bases of only moderately acidic products (e.g., aldol condensation). These bases may acquire a proton from solvent or from the conjugate acid of the added base if the conjugate acid is not too weak. Alkoxide bases are commonly used in the corresponding alcohol solvents (e.g., NaOEt in EtOH), and in these reactions the solvent is often a proton source.


2.8 Problems

1. Indicate the product(s) of the following reactions and draw the mechanism. In some cases, no reaction occurs. Be sure to indicate the stereochemistry of the product where applicable.


(a)




(b)




(c)




(d)




(e)




(f)







(g)





(h)







2. Determine and draw the most reasonable mechanism (S_N2 , $S_{RN}1$, addition–elimination, or elimination–addition) of each of the following substitution reactions. Some reactions might reasonably proceed by more than one mechanism; in these cases, suggest an experiment that would allow you to determine the mechanism unambiguously.




(c)




(d)




(e)




(f)




(g)





(h) The product is a model for the antitumor agent, duocarmycin, a potent alkylator of DNA.




(i)









(l) Note the stereochemistry!










3. Draw reasonable mechanisms for the following reactions.






(e) The Darzens glycidic ester synthesis.









(l) Two mechanisms can be drawn for the *Bayliss–Hillman* reaction. Draw one.




(m) The rate of the *Bayliss–Hillman* reaction is dramatically reduced when the steric bulk of the tertiary amine catalyst is increased. Is your mechanism consistent with this information? If not, draw another mechanism.

(n) TMEDA = $\text{Me}_2\text{NCH}_2\text{CH}_2\text{NMe}_2$; the reaction takes a different course in its absence, but it's not needed for the mechanism.







(r) The Arbuzov reaction.




(s) No ^{18}O is incorporated into the product!




(t)




(u)




(v) This is a very difficult problem. Here's a tip: No reaction between *p*-toluenesulfonylmethyl isocyanide (TosMIC) and cyclopentanone occurs until base is added to the reaction mixture. Draw a deprotonation and then the first bond-forming step, and *then* number the atoms.




(w) The *Potier–Polonovski rearrangement*. pyr = pyridine.




(x) This is a hard one, but if you label all the atoms and concentrate on bonds made and bonds broken, you should be able to do it. One atom is already labelled to get you started.






(y) Pip = piperidine, a saturated six-membered ring with one NH group.






(z)







(dd) Under very similar conditions but using more NaOH, the Robinson annulation product is no longer the major one. *Numbering correctly is key to solving this problem!*




(gg) The first step is a Michael reaction. Use this information to number the atoms.



(hh)



4. *Catalytic antibodies* were first prepared in the mid-1980s. In one example, a rabbit or mouse was immunized with phosphonate ester **A**, and pure anti-**A** antibodies were isolated from this animal's spleen cells. Some of the anti-**A** antibodies were found to catalyze the hydrolysis of the ester functionality of **B** at rates significantly faster than the background.



- Draw the mechanism for the hydrolysis of the ester functionality of **B** under basic conditions. What is the rate-determining step?
- Considering the parameters on which the rate of any chemical reaction depends, explain why antibodies to **A** catalyze (increase the rate of) the hydrolysis of **B**. Use a reaction coordinate diagram to illustrate your explanation.


Polar Reactions Under Acidic Conditions

3

Most textbooks do not strongly differentiate polar mechanisms that occur under basic conditions from those that occur under acidic conditions, but the considerations that you need to bring to bear when drawing polar basic and polar acidic mechanisms are quite different. The typical reagents, the reactive intermediates, and the order of proton transfer steps all differ under acidic conditions from those seen under basic conditions. In this chapter, the mechanisms that occur under acidic conditions will be discussed. A lot of time will also be spent discussing carbocations, which are central in these mechanisms.

3.1 Carbocations

A carbocation is an organic compound with a trivalent, six-electron C atom. The C atom is sp^2 -hybridized, with an empty p orbital perpendicular to the plane of the three sp^2 orbitals. Carbocations are electron-deficient, and as such they are susceptible to attack by nucleophiles. Many (but not all) reactions of organic compounds that occur under acidic conditions involve carbocations or compounds for which important carbocationic resonance structures can be drawn.



Carbocations were originally called “carbonium ions” by Americans and “carbenium ions” by Europeans. After a while, the literature had become thoroughly confusing, so IUPAC stepped in and designated “carbonium ion” for pentavalent, positively charged C species

Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_3) contains supplementary material, which is available to authorized users.

such as CH_5^+ and “carbenium ion” for trivalent, positively charged C species such as CH_3^+ . Unfortunately, this move only added to the confusion, as some Americans started to use the IUPAC convention, and others continued to use the older one. The term *carbocation* is now preferred for CR_3^+ because it is unambiguous, and it provides a nice analogy to *carbanion*.

Common error alert: *When drawing reaction mechanisms involving carbocations, it is imperative that you obey Grossman’s rule. If you do not obey Grossman’s rule, you are guaranteed to lose track of which atoms have three groups attached and which have four.*


3.1.1 Carbocation Energy

Most carbocations are high in energy and very unstable and cannot be isolated except under very special circumstances. They exist only as transient, high-energy intermediates along a reaction coordinate. Because they are high in energy, the Hammond postulate (Chap. 1) suggests that carbocations should strongly resemble the transition states leading to them. As a result, the rates of reactions that have carbocations as intermediates are generally related to the energies of the carbocations themselves. **Common error alert:** *If you draw a reaction mechanism that involves a carbocation that is extremely high in energy, the mechanism is likely to be unreasonable; conversely, a reaction mechanism that proceeds via a low-energy carbocation is likely to be reasonable.*

Every time you draw a carbocationic intermediate, ask yourself: Is this a reasonably stable carbocation under these reaction conditions, or can a lower energy carbocation be drawn?

Most carbocations are high in energy, but some are higher in energy than others. There are four ways that carbocations can be lowered in energy: interaction of the empty $\text{C}(p)$ orbital with a nonbonding lone pair, interaction with a π bond, interaction with a σ bond (hyperconjugation), and by being part of an aromatic system. Hybridization also affects the energy of carbocations.

The common energy-lowering effects of lone pairs, π bonds, and σ bonds are all due to the fact that two overlapping orbitals produce a bonding MO and an antibonding MO. When a filled orbital such as a nonbonding orbital (n), a π bond, or a σ bond overlaps with an empty $\text{C}(p)$ orbital, a new bonding MO and a new antibonding MO are created. The two electrons from the filled orbital go into the bonding MO, producing a net decrease in energy. The order of energy-lowering ($n > \pi > \sigma$) is due to the fact that the interaction between the filled orbital and the empty $\text{C}(p)$ orbital is strongest when the two orbitals are close in energy. Because the nonbonding $\text{C}(p)$ orbital is higher in energy than either a bonding MO (σ or π) or a heteroatom-based nonbonding orbital, the higher the energy of the filled orbital, the stronger the energy-lowering effect.




- A nonbonding lone pair on a heteroatom lowers the energy of a carbocation more than any other interaction. One can draw a resonance structure for such a carbocation in which there is a π bond between the positively charged heteroatom and the adjacent cationic center. The heteroatom must be directly attached to the electron-deficient C for energy-lowering to occur; if not, energy-raising inductive effects take over. Even if the heteroatom is directly attached, if geometric constraints prevent overlap between the two orbitals, as in the bicyclic carbocation shown, then no energy-lowering occurs, and inductive effects take over. **Common error alert:** *Lone-pair-bearing heteroatoms are usually electronegative, too, but when there is a competition between an inductive destabilizing effect and a resonance stabilization effect, resonance always wins.*




The energy-lowering effect of a lone pair decreases as you go down the periodic table (e.g., O > S) and decreases as you go to the right (N > O > F), so N is the best resonance donor, with O a close second. Note that this pattern is not what you would expect from looking at trends in electronegativity. Heavier elements such as S and Cl are not nearly as good at lowering the energy of carbocations as are light elements, because their valence orbitals extend farther from the nucleus and do not overlap as well with the more compact C(p) orbital. F is a surprisingly good resonance donor, despite its electronegativity.

Common error alert: When a heteroatom lowers the energy of a carbocation by sharing its lone pair, it still has its octet and hence is neither electron-deficient nor electrophilic! (Remember that when an electronegative atom has a formal positive charge and its full octet, the atoms *adjacent* to it are electrophilic.) Electronegative atoms like N, O, and F are capable of lowering the energy of carbocations by resonance exactly because they do not surrender their octet when they participate in resonance.

- Resonance with a C=C π bond is the next best way to lower the energy of a carbocation. (The C=O and C=N π bonds *raise* the energy of carbocations by a strong inductive effect, although resonance attenuates this effect by a small amount.). The more π bonds that can resonate, the better. Aromatic rings are good at lowering the energy of carbocations. Again, geometric constraints that prevent overlap also prevent energy-lowering.




- The third way to lower the energy of a carbocation is by overlap with an *adjacent* σ bond, or *hyperconjugation*, a fancy name for an ordinary phenomenon. The more σ bonds, the greater the lowering of energy. The empty C(*p*) orbital in Me_3C^+ has nine C–H bonds with which it can overlap (three overlap completely and six overlap partially), whereas the empty C(*p*) orbital in Me_2CH^+ has only six, and in MeCH_2^+ it has only three, leading to the order of energies of substituted alkyl carbocations, $3^\circ > 2^\circ > 1^\circ$. **Common error alert:** If your mechanism has a 1° alkyl carbocation unstabilized by resonance as an intermediate, it is almost certainly incorrect.




Bonds from C to elements more electropositive than itself are even more energy-lowering than C–H and C–C bonds. Thus, C–Si and C–Sn σ bonds are often used to lower the energy of carbocations. Again, these bonds must be *adjacent*, not attached, to the carbocationic center to have any energy-lowering effect.

Common error alert: *Sigma bonds directly attached to a carbocationic center do not lower the energy of the carbocation because they do not overlap with the empty C(p) orbital.* The bonds must be adjacent to the cationic center to have an energy-lowering effect.


- Carbocations in which the empty C(p) orbital is part of an aromatic system (Chap. 1) are considerably lower in energy than what one would expect just from the energy-lowering effect of resonance alone. The most important aromatic carbocation is the tropylium (cycloheptatrienylium) ion, which is so low in energy that one can buy its salts from commercial suppliers. Conversely, those carbocations in which the empty C(p) orbital is part of an antiaromatic system (e.g., cyclopentadienylium) are substantially raised in energy.



- Alkenyl (vinyl), aryl, and alkynyl carbocations are particularly high in energy as compared to alkyl carbocations. Let us compare the isopropyl cation to the isopropenyl cation. In the latter the central C has two σ bonds, one π bond, and one empty orbital, so it is sp -hybridized (linear). The C(sp^3)–H σ bonds of the CH₃ group on the right lower the energy of both ions. In the isopropyl cation there are additional interactions with C(sp^3)–H σ bonds on the left, whereas in the isopropenyl cation there are additional interactions with C(sp^2)–H σ bonds on the left. Because C(sp^2) orbitals are lower in energy than C(sp^3) orbitals, the C(sp^2)–H σ bonds are lower in energy than the C(sp^3)–H σ bonds, so the C(sp^2)–H σ bonds are not as good at lowering the energy of the cationic center. In fact, 2° alkenyl carbocations (R₂C=CR) are only about the same energy as 1° alkyl carbocations, and 1° alkenyl carbocations (R₂C=CH) are only about the same energy as the CH₃⁺ carbocation.



Aryl and alkynyl carbocations are even higher in energy than 1° vinyl and methyl cations, because they cannot rehybridize to make an empty $C(p)$ orbital. In fact, both aryl and alkynyl carbocations can be generated only under very special circumstances and with the best of leaving groups, e.g., N_2 . **Common error alert:** *If your mechanism has an alkenyl, alkynyl, or aryl carbocation as an intermediate, it is almost certainly incorrect.*



*no stabilization of empty $C(sp^2)$ orbital
from neighboring $C(p)$ orbitals*

- Carbocations are *raised in energy* by inductively electron-withdrawing elements and groups. Carbocations α to a carbonyl group ($R_2\overset{+}{C}C=O$), β hydroxycarbocations ($HO\overset{+}{C}R_2$), and β -halocarbons are all particularly unhappy species.

Carbocations occupy a unique place in the world of electron-deficient cations. Electron-deficient nitrogen and oxygen compounds (nitrenium and oxenium ions, respectively) are extremely high in energy and are rarely or never seen. Electron-deficient boron and aluminum compounds are quite common, but these species are not cations. Silenium ions (R_3Si^+) are extremely unstable kinetically; still, it is useful to think of the R_3Si^+ group as a large, kinetically more stable H^+ .

Obey Meier's rule: When in doubt, draw resonance structures! Often, carbocations are drawn in just one of their resonance forms, and sometimes not even in the lowest energy form. It is up to you to see the different resonance forms and to see how they impinge on the energy and reactivity of the carbocation.


3.1.2 Carbocation Generation. The Role of Protonation

There are three methods for generating carbocations: ionization of a $C-X^+$ σ bond, reaction of a lone pair on the heteroatom in a $C=X$ bond with a Lewis acid, and reaction of a $C=C$ π bond with a Lewis acid such as H^+ or a carbocation.

Carbocations can also be generated by one-electron oxidation of $C=C$ π bonds. The carbocations generated by these methods are *radical cations*; they have an odd number of electrons. Reactions involving radical cations are discussed more thoroughly in Chap. 5.


- The R_3C-X^+ bond can ionize spontaneously to give R_3C^+ and $:X$. The likelihood of ionization depends on the energy of the carbocationic product R_3C^+ , the leaving group X , and the solvent. Loss of H_2O from $Me_3C-OH_2^+$ occurs readily at

room temperature, but ionization of $\text{RCH}_2\text{-OH}_2^+$ is very difficult because a very high energy carbocation would result. Note that X *usually* has a formal positive charge prior to ionization. The spontaneous departure of an anionic leaving group X^- is much less common, though it can happen in very polar (especially hydroxylic) solvents if the products are sufficiently stable. An anionic leaving group X^- is often converted into a neutral leaving group simply by protonating it; weak acids such as AcOH and $\text{pyrH}^+ \text{OTs}^-$ (PPTS) are sometimes all that is required. Sometimes strong Lewis acids such as BF_3 , AlCl_3 , FeCl_3 , ZnCl_2 , SnCl_4 , or TiCl_4 are used to promote ionization. Silver (I) salts (AgNO_3 , AgOTf , Ag_2O) can be used to promote the ionization of even relatively stable carbon-halogen bonds like C-Cl; the driving forces are the establishment of the strong Ag-X bond and precipitation of AgX.




• A heteroatom X in a $\text{C}=\text{X}$ bond can use its lone pair to react with a Lewis acid to give a product for which a carbocationic resonance structure can be drawn. Protonation of a carbonyl compound belongs in this category. One of the lone pairs on O coordinates to H^+ to give a compound with two major resonance structures, one of which is carbocationic. The carbocationic resonance structure is not the *best* structure, but it tells the most about the *reactivity* of the ion. If the carbonyl C has heteroatoms directly attached (e.g., esters, carboxylic acids, and amides), more resonance structures can be drawn. Reactions of imines (Schiff bases) often begin by protonation of N. **Common error alert:** *The reaction of esters, amides, and carboxylic acids with electrophiles occurs on the carbonyl O.*

Many more resonance structures can be drawn when the carbonyl O is protonated than when the noncarbonyl heteroatom is protonated.



• The π electrons in a $C=C$ π bond can react with a Lewis acidic electrophile to give a carbocation. The simplest example is the reaction of an alkene with H^+ . Note that one of the C atoms of the π bond uses the electrons of the π bond to form the σ bond to H^+ , while the other C becomes electron-deficient and gains a formal positive charge. Other cationic electrophiles (carbocations, acylium ions) can react with $C=C$ π bonds as well.




Both the first and second methods for generating a carbocation involve the reaction of a heteroatom with H^+ or another Lewis acid. The protonation of a heteroatom converts a π -bond electrophile into a more potent one, or it converts a mediocre leaving group into a better one. In Chap. 2, we saw that deprotonation of a substrate does not always occur at the most acidic site in polar basic mechanisms. Similarly, in polar acidic mechanisms, protonations do not always occur at the most basic site. To decide where to protonate a substrate, first determine which bonds need to be made and broken, then determine which of the atoms are nucleophilic and which are electrophilic. Then protonate a heteroatom, either to convert a leaving group into a better one or to convert an electrophile into a more potent one.


3.1.3 Typical Reactions of Carbocations. Rearrangements

Regardless of how they are generated, carbocations always undergo one of three reactions: *addition* of a nucleophile, *fragmentation* to give a compound containing a π bond and a stable cation (often H^+ , but not always), or *rearrangement*. These reactions compete with one another, and often slight differences in structure or reaction conditions tip the balance in favor of one reaction over another. For example, in the reactions of 3° alkyl carbocations, addition is favored when the nucleophile is a hydroxylic solvent (EtOH , H_2O , RCO_2H), while fragmentation is favored when R_3Si^+ can be cleaved or when the solvent is nonnucleophilic. It is difficult to predict when any of these reactions will occur, and you will usually be asked merely to rationalize the formation of the observed product.


- In an *addition* reaction, a nucleophile donates a pair of electrons to the carbocation's empty orbital to form a new σ bond. **Common error alert:** A lone-pair nucleophile bearing a proton (H_2O , ROH , RCO_2H , RNH_2 , etc.) is always deprotonated immediately after it adds to the carbocation. The two steps combined—addition, then deprotonation—are the microscopic reverse of the ionization of a carbon–heteroatom bond under acidic conditions. When the nucleophile is a carboxylic acid, the carbonyl O makes the new bond, not the acid O.



π -Bond and σ -bond nucleophiles can also add to carbocations. In the former case, a new carbocation is formed, as discussed above.




• Carbocations can undergo *fragmentation* to give a new electron-deficient cation and a species containing a π bond. In a fragmentation, the electrons in a bond adjacent to (but not attached to) the electron-deficient carbon atom move to form a π bond to the electron-deficient center ($^+C-X-Y \rightarrow C=X + Y^+$). The electron-deficient species Y^+ that is generated can be H^+ , a carbocation, or occasionally another species such as R_3Si^+ or R_3Sn^+ . The intermediate atom X may be C or another atom like N or O. Fragmentation is the opposite of addition of a π -bond nucleophile to a Lewis acid electrophile. Note that the electron-flow arrow showing the cleavage of the $X-Y$ bond shows the movement of the electrons in the $X-Y$ bond toward the cationic center. The group Y^+ is assumed to just float away upon loss of its bond to X . **Common error alert:** Do not use the arrow to show the Y^+ fragment flying off into the wilderness! If Y^+ floating away bothers you, show a weak base making a new bond to Y^+ at the same time as the $X-Y$ bond is cleaved. Usually the base is assumed to be present and is not shown.




• Carbocations can also *rearrange*, much more so than carbanions. The longer the lifetime of the carbocation (i.e., the more acidic the reaction conditions), the greater the propensity to rearrange. Usually, carbocations rearrange to give lower energy carbocations, but contrathermodynamic rearrangements can occur at high temperatures. Also, sometimes a higher energy carbocation in equilibrium with a lower energy one is carried on to product selectively for kinetic reasons.


The major mechanisms for carbocationic rearrangements are 1,2-hydride shifts and 1,2-alkyl shifts. Both occur in the rearrangement of the cyclohexylium ion (a 2° carbocation) to the 1-methylcyclopentylum ion (a 3° carbocation). A 1,2-alkyl shift of the C3–C2 bond of cyclohexylium from C2 to C1 gives a cyclopentylmethylium ion (a 1° carbocation). This reaction is uphill in energy. However, a 1,2-hydride shift of the C1–H bond from C1 to C2 gives a much lower energy product.




Example



Numbering: Only one CH_2 group, C8, is present in both starting material and product. Assume the C5–C6–C7–C8 ring in starting material and product does not change. C6 may still be attached to C3, C3 to C2 (or C4; they are equivalent, so it makes no difference), and that leaves C1 and C4; assume C4 is still attached to C5 to give the final numbering of the product. Make: C1–C7, C2–C4, C3–OAc. Break: C1–OMs, C2–C7, C3–C4.




The cation is generated at C1. Then C7–C2 migrates to C7–C1, and C4–C3 then migrates to C4–C2. Addition of AcOH to the C3 carbocation and H^+ loss gives the product.




Note how I kept the atoms in the same relative positions in the drawings as I moved the bonds around. In rearrangement reactions especially, draw all intermediates exactly as the starting material was drawn. Only when you have made and broken all bonds in your list should you try to redraw the structure.


Transannular 1,5-hydride shifts are often seen across medium-sized (eight-, nine-, and ten-membered) rings. The atoms directly across from each other in these rings are quite close together, so migration is facile. In general, though, most cationic rearrangements are best explained by a series of 1,2-shifts.




Often, a 1,2-shift is *concerted* with loss of the leaving group. For example, consider the two diazonium ions shown. Loss of N_2 from either diastereomer gives a common carbocationic intermediate, and this carbocation can undergo a 1,2-alkyl shift to give the aldehyde or a 1,2-hydride shift to give the ketone. If both diastereomers rearranged via the carbocation, then each diastereomer should give the same ratio of aldehyde to ketone. In fact, one diastereomer gives only the aldehyde, and the other gives only the ketone. This result suggests that there is no carbocationic intermediate, and that rearrangement is concerted with loss of the leaving group.



Why does the equatorial RN_2^+ ion give only the aldehyde, and the axial RN_2^+ ion only the ketone? When a 1,2-shift is concerted with loss of a leaving group, the migrating bond must be *antiperiplanar* to the C-X bond of the leaving group. (See Chap. 2 for a discussion of anti- and synperiplanar requirements in E2 elimination reactions.) In each diastereomeric diazonium ion in the example, the bond that is antiperiplanar to the C-N_2^+ bond migrates selectively. (Draw a Newman projection or make a model if you have trouble seeing this.) The same phenomenon is observed in the *Beckmann rearrangement*, in which an oxime is converted into an amide after a 1,2-alkyl shift and addition of H_2O . The group that is trans to the OH group (i.e., antiperiplanar) shifts selectively.




Problem 3.1 In the rearrangement reaction shown next, a 1,2-shift occurs with concerted loss of a leaving group. Draw a mechanism for this reaction. FeCl_3 is a Lewis acid. What by-products might be obtained if the migration were not concerted with loss of the leaving group?



The *pinacol rearrangement* represents another example of loss of $-\text{OH}$ under acidic conditions with concomitant migration. One could draw a mechanism with an intermediate carbocation, but this carbocation would be destabilized by the inductive effect of the neighboring OH group.

Example




How does one decide whether loss of a leaving group is concerted with a 1,2-shift or whether a carbocation is formed before the 1,2-shift occurs? Under strongly acidic conditions, when carbocations are particularly long-lived, nonconcerted mechanisms are usually drawn. By contrast, a concerted mechanism is usually drawn when

- loss of the leaving group would give a particularly high energy carbocation; or
- the carbocation that one obtains *after* the 1,2-shift is particularly low in energy; or
- a group that is antiperiplanar to the leaving group shifts selectively, while other groups do not.

Phenyl and other unsaturated groups undergo 1,2-shifts also, but they use a two-step, *addition-fragmentation* mechanism. A π bond from the phenyl group adds to the carbocation to give a three-membered ring intermediate called a *phenonium ion*. One of the bonds of the three-membered ring then fragments to give either the starting material or the product.


Example



The concerted shift of a Ph group has a higher activation energy than the two-step shift because the $C(sp^2)$ orbital on the migrating atom doesn't interact with the two other orbitals involved in the TS as strongly as a $C(sp^3)$ or $H(s)$ orbital would. The 1,2-shift of Ph groups is often faster than the 1,2-alkyl shift, even though it is nonconcerted and it involves a three-membered-ring intermediate. In the example, a lower energy carbocation would be obtained by a 1,2-methyl shift, but the phenyl group shifts more quickly.

It is sometimes difficult to discern that a mechanism involves a 1,2-alkyl shift. Look at your list of bonds broken and bonds made. If a group migrates from one atom to its next-door neighbor, you may have a 1,2-shift.

Problem 3.2 Draw a mechanism for the following rearrangement reaction. SnCl_4 is a Lewis acid. Treat the Me_3Si group as if it were a big proton.




Note how the group that migrates *retains* its stereochemistry! Retention of stereochemistry of the migrating group is a general feature of 1,2-shifts.

3.2 Substitution and β -Elimination Reactions at $C(sp^3)-X$


3.2.1 Substitution by the S_N1 and S_N2 Mechanisms

Nucleophilic substitutions at $C(sp^3)-X$ under acidic conditions usually occur by the S_N1 mechanism. The S_N1 mechanism consists of two steps, not counting protonations and deprotonations. In the rate-determining step, the leaving group leaves to give a carbocation. In a subsequent fast step, the nucleophile *adds to* the carbocation (one of the three typical reactions of carbocations) to afford the product. The nucleophile may be anionic (as long as it is a weak base, e.g., Br^- or I^-) or neutral. In addition to these two steps, there is sometimes a protonation of the leaving group *before it leaves*, and there is sometimes a deprotonation of the nucleophilic atom *after it adds*. Protonation of the leaving group transforms it into a much better leaving group, especially when it is $-OH$ or $-OR$. On the other hand, a neutral, protic nucleophile (e.g., H_2O , ROH , RCO_2H) always loses a proton to give a neutral species after it has added to the carbocation.




A carbocation is formed in the rate-limiting step of S_N1 substitution, so the rate of the reaction is directly related to the energy of the carbocation being formed. S_N1 substitution at $C(sp^3)-X$ occurs very readily at 3° centers, occasionally at 2° centers, especially when an energy-lowering group like a heteroatom or a π bond is directly attached, and at 1° alkyl centers only when a strongly energy-lowering group like O or N is attached. Substitutions in which the nucleophile is a π bond almost always proceed by the S_N1 mechanism, as π bonds are generally poor nucleophiles toward σ -bond electrophiles and rather good nucleophiles toward carbocations.

Example




It is not obvious at first sight whether the ring O atoms in the product come from the diol or the acetal. Draw the coproducts! You will see that two equivalents of MeOH are obtained. This information suggests that the Me-O bonds of the acetal do not break and therefore that the ring O atoms in the product come from the diol. (The preservation of the stereochemistry of the two C-O bonds in

the first reagent also provides a clue that this is the case.) The first two steps of the reaction must be protonation of a MeO group and loss of MeOH to give a very low energy carbocation.




Problem 3.3 Draw mechanisms for each of the following substitution reactions. Remember that in each case, loss of the leaving group is preceded by coordination of the leaving group to a Lewis acid such as H^+ .

(a)




(b)




Problem 3.4 Alkenyl and aryl halides do not undergo substitution reactions under acidic conditions. Why not?

Substitution at an electrophilic C atom can occur by the S_N2 mechanism under acidic conditions, but only under special circumstances. The electrophilic C must be a 1° C(sp^3)-X electrophile (or $\text{CH}_3\text{-X}$) so it is unable to stabilize a carbocation, the nucleophile must be a *very* good one like Br^- or I^- , and the conditions must be very

strongly acidic (e.g., refluxing 48% aq. HBr). One of the few examples of the S_N2 mechanism under acidic conditions is the conversion of 1° alcohols to halides with mineral acid. The strongly acidic conditions are required to convert the OH into a better leaving group that exists long enough to undergo an S_N2 reaction.




Problem 3.5 Draw a reasonable mechanism for the following substitution reaction. Which O is protonated first?




Common error alert: When reaction conditions are only weakly acidic, the S_N1 mechanism is almost always operative for substitutions at C.


Example



The mechanism one draws for this glycosylation reaction depends on whether the O in the product that is attached to the CH_3 group is identified as coming from CH_3OH or from the sugar. If it comes from the sugar, then substitution is occurring at the C of CH_3OH . There is no way a carbocation can form at this C, so an S_N2 mechanism must be operative.




If it comes from CH_3OH , then substitution is occurring at the anomeric C of the sugar. A very good carbocation (lowered in energy by O) can form at this C, so an S_N1 mechanism is likely.




Which mechanism is better? S_N2 mechanisms require harshly acidic conditions and very good nucleophiles such as Br^- or I^- , neither of which is the case here, so the S_N1 mechanism is much better than the S_N2 mechanism.

Substitutions at more electronegative elements like P and Br occur by the S_N2 mechanism under acidic conditions. These elements cannot form the stable cations required for an S_N1 mechanism.

Example




The elements of H_2O are removed from the amide with the help of POCl_3 . The amide O is nucleophilic, and P is electrophilic, so the first step is likely a simple S_N2 reaction at P with the amide O as nucleophile, with deprotonation of the nucleophile following. The C–O bond is cleaved next with assistance from the lone pair of N. Deprotonation of the nitrilium ion gives the isocyanide.




Substitution very rarely occurs by the $S_{RN}1$ mechanism under *acidic* conditions because radical anions are usually strongly basic. Substitution cannot occur by the S_N1 mechanism under *basic* conditions because the carbocationic intermediates are strongly Lewis acidic.

When S_N1 substitution occurs at a stereogenic center, loss of configurational purity is usually observed. The carbocationic intermediate is planar, and there is no bias for the approach of the nucleophile from one face or the other. Occasionally the loss of configurational purity is only partial for reasons that need not concern you here. However, sometimes an apparent S_N1 reaction proceeds stereospecifically. Such an outcome is usually the result of the participation of neighboring π bonds or lone pairs, as in the example shown. You can think of these reactions as two subsequent S_N2 reactions. Even if a true carbocationic intermediate is formed in these reactions, it exists for less time than it takes to rotate about a C–C σ bond.




3.2.2 β -Elimination by the E1 Mechanism

Elimination can also occur at $C(sp^3)-X$ centers under acidic conditions. The mechanism is called *E1*. The leaving group leaves, sometimes after protonation, to give a carbocation. The carbocation then *fragments* (one of the three reactions of carbocations) to give a compound containing a π bond and a new cation, usually H^+ . The specific bond that fragments is always *adjacent* to the electron-deficient C, *never attached to it*. The electrons in that bond migrate to form a π bond. A weak base (either the solvent or the conjugate base of the strong acid in the reaction mixture) is sometimes shown removing the H^+ . Other cationic groups besides H^+ , most commonly R_3Si^+ , R_3Sn^+ , or a stabilized carbocation, can be lost by fragmentation in this manner. In fact, given a choice between fragmenting to lose H^+ or R_3Si^+ , a carbocation will usually choose to lose the latter.




It is common practice not to show the weak base that removes H^+ , so that the carbocation seems to fragment spontaneously. **Common error alert:** *If you do not show the weak base that removes H^+ , be sure that your electron-flow arrow is drawn correctly.* The arrow shows how the *electrons* in the C–H bond move to form a π bond. It should not show H^+ flying off into the wilderness!




The elimination of small molecules like water and MeOH is often carried out under acidic conditions. The reaction is often driven to completion by azeotropic distillation with benzene or petroleum ether.


Example




The elements of H₂O are eliminated. Under acidic conditions, eliminations occur by an E1 mechanism. First, the leaving group is protonated to convert it into a better leaving group, and then it leaves to give a carbocation. Then fragmentation (one of the three typical reactions of carbocations) of a C–H bond occurs to give a diene.



Unfortunately, this diene is not the desired product. Compare the diene with the desired product. Which σ bonds differ between them? One C–H bond has to be made, and another has to be broken. Because the conditions are acidic, make a new C–H bond first by protonating a C=C π bond. Then fragment the resulting carbocation to give the desired product.



Problem 3.6 Draw a reasonable mechanism for the following transformation.




3.2.3 Predicting Substitution Versus Elimination


A carbocationic intermediate is formed in both the S_N1 and the $E1$ mechanisms. After the carbocation is formed, addition of a nucleophile leads to an overall substitution reaction, whereas fragmentation leads to an overall elimination reaction, so there is a competition between the two modes of reaction. It is possible to predict whether substitution or elimination dominates, just like it is possible to predict, whether S_N2 or $E2$ will predominate under basic conditions. Predicting which pathway dominates is easier under acidic conditions, though. *Addition is favored in hydroxylic (i.e., nucleophilic) solvents (RCO_2H , ROH , H_2O) and when the nucleophile is contained in the same molecule, whereas fragmentation is favored in aprotic solvents.* In other words, substitution occurs when the carbocation intermediate can be rapidly intercepted by a nucleophile, and elimination occurs when it cannot.

3.3 Electrophilic Addition to Nucleophilic $C=C$ π Bonds

Alkenes that are substituted with alkyl groups or heteroatoms are good nucleophiles toward Brønsted acids ($H-X$) and heteroatom–heteroatom σ -bond electrophiles (Br_2 , NBS, $PhSeCl$, RCO_3H). In an *electrophilic addition* reaction, the π bond acts as a nucleophile toward the electrophilic atom to give a carbocation, and then a nucleophile adds to the carbocation (one of the three reactions of carbocations) to give a product into which all the atoms of the starting materials are incorporated.




Alkenes that are directly attached to lone-pair-bearing heteroatoms, especially N and O, are particularly reactive toward electrophiles. One can draw a resonance structure that shows a formal negative charge on the β -carbon, and the intermediate carbocation is especially low in energy. Conversely, alkenes substituted with electron-withdrawing groups are less reactive toward electrophiles.




Mineral acids, carboxylic acids, alcohols, and H_2O all add across π bonds. Alcohols and H_2O are not sufficiently acidic to protonate the alkene in the first step, so a catalytic amount of a strong acid is used to promote the reaction.

Example




When the electrophilic atom is H^+ and the alkene is unsymmetrical, H^+ adds to the alkene so that the *lower energy carbocation*, almost always the more substituted one, forms. The nucleophile then adds to the carbocation to give the product. The observation that the nucleophile adds to the more substituted C of the double bond is known as *Markovnikov's rule*. Markovnikov's rule is simply an application of the Hammond postulate: the faster reaction is the one that leads to the intermediate lower in energy.

Problem 3.7 Dihydropyran (DHP) reacts with alcohols under acid catalysis to give tetrahydropyranyl (THP) ethers. The alcohols can be released again by treating the THP ether with MeOH and catalytic acid. Thus, the THP group acts as a *protecting group* for alcohols. Draw mechanisms for the formation and cleavage of the THP ether.




When a simple alkene reacts with an electrophilic, lone-pair-bearing heteroatom, a carbocation does *not* form. Instead, *both* C atoms of the π bond form new bonds to the electrophilic atom to give a product containing a three-membered ring. The four electrons required for the two new σ bonds come from the π bond and one lone pair of the heteroatom. The reaction is stereospecifically *syn* (i.e., the two new bonds form on the same side of the double bond). For example, epoxides are formed in the reaction of alkenes with peracids (RCO₃H) such as mCPBA. A *trans* alkene gives a *trans* epoxide, and a *cis* alkene gives a *cis* epoxide.




Some chemists omit the arrow from the O lone pair back to one of the C atoms of the alkene.

Alkenes also react with sources of electrophilic halogen such as Br₂, *N*-bromosuccinimide (NBS), and I₂ to give three-membered rings called *halonium* ions. Again, the four electrons required for the two new C–X bonds come from the alkene and a lone pair on the halogen. Halonium ions are in equilibrium with the open β -halocarbenium ions. For Br and I, the equilibrium favors the halonium ions greatly, but for Cl the equilibrium favors the β -halocarbenium ion due to the greater electronegativity of Cl (less willing to share a pair of electrons) and the shorter C–Cl bonds. The β -halocarbenium ion is also favored when strongly electron-donating groups such as –OR or –NR₂ are present to stabilize the carbocation.




Again, many chemists omit the arrow pointing from X back to one of the C atoms of the alkene.

Problem 3.8 Draw a mechanism for the following reaction. Will a halonium ion or a β -halocarbenium be an intermediate?




The halogen atom of a halonium ion has its octet and a formal positive charge, so the C atoms of the halonium ion are electrophilic and are susceptible to S_N2 nucleophilic attack. Because the S_N2 substitution reaction results in inversion at one

of the C atoms, the overall reaction—addition of the electrophilic halogen and nucleophile across the π bond—usually proceeds with anti stereochemistry.



Sometimes anti addition is not observed. Temporary participation of a neighboring group can give unusual stereochemical or regiochemical results.

Problem 3.9 Draw mechanisms that account for the formation of each product. The first step is the same in every mechanism. Be sure to think about stereochemistry!




3.4 Substitution at Nucleophilic C=C π Bonds


3.4.1 Electrophilic Aromatic Substitution

The π bonds in aromatic compounds are also reactive toward electrophiles, though not nearly so much as alkenes. The aromatic ring attacks an electrophile to give an intermediate carbocation. The carbocation then undergoes fragmentative loss of H^+ (sometimes another cation) *from the same C to which the electrophile added* to re-form the aromatic system and give an overall *substitution* reaction. In short, the predominant mechanism of substitution at aromatic rings under acidic conditions is electrophilic addition–elimination, sometimes referred to as $\text{S}_{\text{E}}\text{Ar}$. The reaction of toluene and nitric acid is indicative.


Example



Toluene is a nucleophile, so HNO_3 must be electrophilic. The N=O bond in nitric acid is analogous to the C=O bond in carbonic acid (HOCO_2H). The most commonly drawn mechanism is that HNO_3 undergoes H^+ -promoted loss of OH to give electrophilic $^+\text{NO}_2$, which then reacts with the aromatic compound by addition–elimination.



Unfortunately, this widely drawn mechanism has a serious flaw: the very first protonation of HNO_3 is unlikely to occur at OH to generate a 1,2-dication. Instead, it is much more likely that it will occur at the negatively charged O atom. From there, though, it is very difficult to draw a mechanism that leads to $^+\text{NO}_2$. Instead, it is now thought that the nitration reaction proceeds through the protonated form of nitric anhydride. The aromatic compound undergoes the usual addition–elimination mechanism for aromatic substitution, but the HNO_3 leaving group now attached to the nitro N does not leave until after the new C–N bond forms.




Arenes can only be induced to react with quite voracious electrophiles. For example, Br_2 reacts instantly with alkenes but is inert toward benzene. However, Br_2 reacts with benzene in the presence of the Lewis acid FeBr_3 , which coordinates to Br_2 and makes Br^- a better leaving group. (A β -halocarocation, not a bromonium ion, is an intermediate in the reaction of arenes with Br_2 .) Aromatic rings are *sulfonated* (substituted with $-\text{SO}_3\text{H}$) by treatment with SO_3 and H_2SO_4 , and *nitrated* (substituted with $-\text{NO}_2$) with HNO_3 .


New C–C bonds to arenes can be made by *Friedel–Crafts* reactions. Friedel–Crafts *alkylations* are traditionally executed with an alkyl chloride and catalytic AlCl_3 or an alkene and a strong Brønsted or Lewis acid; the key electrophilic species is a carbocation. In the *Bischler–Napieralski reaction*, intramolecular attack on a nitrilium ion ($\text{RC}\equiv\text{NR}$) occurs.

Problem 3.10 Draw mechanisms for the following electrophilic aromatic substitution reactions.


(a) A Friedel–Crafts alkylation.




(b) A Bischler–Napieralski reaction.



Friedel–Crafts *acylations* are usually executed with an acyl chloride or anhydride and an excess of AlCl_3 . Unfortunately, most textbooks depict the mechanism of the Friedel–Crafts acylation with acyl *chlorides* in a very troubling way. For example, consider the following reaction.




Most textbooks begin the mechanism of this reaction by having AlCl_3 coordinate to the acyl chloride Cl, followed by cleavage of the C–Cl bond to give an *acylium ion*.




However, there are two major problems with this proposal. First, Al is very oxophilic and not very chlorophilic, so it is unlikely that it would coordinate to Cl. (The low affinity of AlCl_3 for Cl is one reason why AlCl_3 is such a strong Lewis acid.) Second, carboxylic acid derivatives are always much more nucleophilic on the carbonyl O than they are on the X group attached to the carbonyl C. Considering the $\text{C}=\text{O}$ resonance structure of any carbonyl compound, it is easy to see that the Al would much rather coordinate to the carbonyl O than to the Cl of an acyl chloride.

One can draw a much better mechanism for the Friedel–Crafts acylation with acyl chlorides by having AlCl_3 make a bond to the *carbonyl O* of the acyl chloride. This step makes the carbonyl C atom much more electrophilic, so the aromatic ring can now attack the carbonyl C and undergo its regular addition–elimination mechanism for substitution of H with an electrophile. After aromaticity is reestablished, the C–Cl bond breaks, assisted by O, to give a complex of the ketone product with AlCl_3 . The Al–O bond does not break until aqueous workup, when H_2O attacks the Al and delivers the free ketone.




By contrast, the mechanism of the Friedel–Crafts acylation with acyl *anhydrides* can proceed through an acylium ion intermediate. After coordination of one of the carbonyl O atoms of the anhydride to AlCl_3 , the O atom *not* coordinated to Al can use its lone pair to expel the anhydride O and generate an acylium ion. Alternatively, the intermediate anhydride– AlCl_3 complex can react with an aromatic compound in exactly the same way as the acyl chloride does, with the acetate group *not* coordinated to Al playing the part of the Cl.




The electronic nature of the substituents on an aromatic ring has a profound effect on the regiochemistry of electrophilic aromatic substitutions. Electrophiles preferentially attack ortho or para to electron-donating substituents such as $\text{RO}-$, $\text{R}_2\text{N}-$, $\text{RCONH}-$, and halo substituents, whereas they attack meta to electron-withdrawing groups such as carbonyl, CN , NO_2 , and SO_3H groups. (Amino groups are protonated under the conditions of certain electrophilic aromatic substitution reactions, so they can be ortho–para or meta directors, depending on the reaction.) The directing ability of a group is directly related to its ability to stabilize or destabilize the intermediate carbocation in electrophilic aromatic substitutions.


Substitution para to an electron-donating group gives an intermediate with an excellent resonance structure...




... meta substitution does not!




Substitution para to an electron-withdrawing group gives an intermediate with a terrible resonance structure...



... meta substitution does not!




Charge-separated resonance structures for the starting materials also show that rings with electron-donating groups are most nucleophilic at the ortho and para positions, whereas rings with electron-withdrawing groups are least nucleophilic at these positions.




In most cases, the C of the arene that acts as a nucleophile has a H atom attached, so the fragmentation step of the substitution reaction gives H^+ . Other fragments can be lost, though. For example, the Me_3Si group is an *ipso* director: despite its apparent steric bulk, it directs electrophiles to add to the C to which it is attached. The C–Si bond then fragments to reestablish aromaticity. Attack on the ipso C occurs selectively because it moves the C–Si bond out of the plane of the ring where it can stabilize the carbocation, whereas attack on any other C moves a C–H bond out of the plane of the ring, and a C–Si bond is more carbocation-stabilizing than a C–H bond. Alkyl groups that can form reasonably stable carbocations (*t*-Bu, *i*-Pr) can act as ipso directors, too.

Example




Sometimes odd rearrangements in the course of aromatic substitution reactions can be explained by ipso substitution.


Example




The first product results from a simple aromatic substitution reaction. The second product is much more interesting than the first, because it seems like the Br atom has migrated from the bottom to the top of the aromatic ring. A three-atom migration of a C(sp^2)-Br bond is pretty unlikely, though, so perhaps something else is going on. Assuming that the C-Br bond does not break, careful numbering of the atoms reveals that the aryl C bound to the CH_2 group (C6) has undergone *ipso* substitution, and that the aryl- CH_2 bond has undergone a 1,2-shift from C6 to C5.




The OH group attacks triflic anhydride, displacing the fantastic leaving group TfO^- and converting the OH group into the same. Loss of TfOH from the substrate then gives an allylic cation.



The first product is formed by attack of C5 on C10 of the allylic cation, followed by loss of H^+ from C5 to reestablish aromaticity. The second product is formed by attack of C6 on C10 of the allylic cation. A 1,2-shift of C7 from C6 to C5 followed by loss of H^+ from C5 gives the product. In this particular reaction, instead of a 1,2-shift, a fragmentation (to give a stable $^+\text{CH}_2\text{OR}$ cation) followed by a second, conventional aromatic substitution is also reasonable.




Problem 3.11 Draw mechanisms explaining the formation of both electrophilic aromatic substitution products.



3.4.2 Diazonium Ions

When an amine RNH_2 is treated with sodium nitrite (NaNO_2) and acid, a diazonium ion ($\text{RN}\equiv\text{N}$) forms. The mechanism of the reaction begins with the formation of the electrophile $\text{N}\equiv\text{O}^+$ from HNO_2 . The amine attacks $\text{N}\equiv\text{O}^+$, and then elimination of H_2O occurs to give $\text{RN}\equiv\text{N}$.


Example




When an aromatic amine is used in this reaction, an arenediazonium ion ($\text{ArN}\equiv\text{N}$) is obtained. In this compound, one of the world's best leaving groups (N_2) is attached to an aromatic C atom, but it cannot just leave, because that would

give the very high energy Ar^+ ion. However, arenediazonium ions do undergo aromatic substitution reactions with several different nucleophiles, especially those that can engage in electron transfer reactions (Chap. 2). The terminal N of arenediazonium ions is also electrophilic, and electron-rich aromatic compounds such as phenols and anilines undergo electrophilic aromatic substitutions with the terminal N of $\text{ArN}^+\equiv\text{N}$ as the electrophile to give azo compounds ($\text{ArN}=\text{NAr}'$).


Problem 3.12 Draw a reasonable mechanism for the following reaction.



Aliphatic amines also react with HNO_2 . In the resulting alkyldiazonium ions, there is a much lower barrier to departure of N_2 , so they react quickly by standard $\text{S}_{\text{N}}1$, $\text{S}_{\text{N}}2$, or rearrangement reactions. For example, α -amino acids undergo substitution reactions with complete *retention* of configuration in the presence of HNO_2 (see Chap. 2). Likewise, acyl hydrazides react with HNO_2 to give acyl azides, key intermediates in the Curtius degradation.




Problem 3.13 In the *Stiles reaction*, highly reactive benzyne is obtained by treatment of anthranilic acid (2-aminobenzoic acid) with NaNO_2 and HCl . Draw a mechanism for this reaction.



3.4.3 Electrophilic Aliphatic Substitution

Alkenes undergo electrophilic substitution reactions by the same addition–fragmentation mechanism as do arenes. Alkenylsilanes and -stannanes are especially good substrates for electrophilic substitution reactions because the carbocation intermediate is strongly stabilized by the C–Si or C–Sn bond. Fragmentation of this bond then almost always occurs to give a desilylated or destannylated product. When the group that is lost is attached to the same C as the group that is added, the overall reaction is called α -substitution. (Arene electrophilic substitution reactions are always α -substitution reactions because of the need to reestablish aromaticity after the carbocation intermediate is formed.)


Problem 3.14 Draw a mechanism for the following electrophilic substitution reaction.



α -Substitution is not always observed when alkenes undergo electrophilic substitution. Sometimes the group that is lost to fragmentation is γ to the C where the new bond is formed. γ -Substitution is most commonly observed in the reactions of allylsilanes and -stannanes. The overall process is still a substitution with respect to the allylsilane, because a new σ bond is made at the expense of another σ bond, but the new bond is not made to the same atom as the old bond, and allylic transposition occurs.


Example

The *Sakurai reaction*.



TiCl_4 is a Lewis acid; it coordinates to the carbonyl O, making the carbonyl and β -carbon atoms into cations. The alkene then attacks the β -carbon in such a

way as to put the new carbocation on the C adjacent to the C–Si bond. Fragmentation of the C–Si bond gives a Ti enolate. Aqueous workup protonates the enolate to give the observed product.




3.5 Nucleophilic Addition to and Substitution at Electrophilic π Bonds

3.5.1 Heteroatom Nucleophiles

Two major resonance structures can be drawn for a protonated carbonyl compound (more if the carbonyl C is σ -bonded to heteroatoms). In the second-best resonance structure, O is neutral, and C is both formally positively charged and electron-deficient. As a result, carbonyl compounds undergo the same types of addition and substitution reactions under acidic conditions that they do under basic conditions.

Carboxylic acids, carbonates and their derivatives undergo acid-catalyzed hydrolysis and alcoholysis reactions, in which the OH or OR group σ -bonded to the carbonyl C is replaced with another OH or OR group. The mechanism of the reaction is simple. Protonation of the carbonyl O occurs to give a (resonance-stabilized) carbocation. Addition of the nucleophile to the carbocation occurs to give a tetrahedral intermediate. The nucleophile is deprotonated, the leaving group is protonated, and the leaving group leaves to give a new carbocation. Finally, the unsubstituted O is deprotonated to regenerate a carbonyl compound. All the steps are reversible, so the reaction can be driven in one direction or the other by executing the reaction in water or in alcohol.

Example




Don't lose the forest for the trees! The mechanism of substitution at the carbonyl group of esters or acids does not differ greatly depending on whether the conditions are acidic or basic. The mechanism always involves addition of a nucleophile to the carbonyl C followed by elimination of the leaving group. Under acidic conditions, there are a lot of proton transfer steps, but the fundamental nature of the mechanism is not different under acidic and basic conditions.


Amides and nitriles are hydrolyzed to carboxylic acids by a similar mechanism, the latter proceeding through an amide. These hydrolyses are irreversible under acidic conditions, though, because the coproduct amine is protonated under the reaction conditions and is made nonnucleophilic.

Problem 3.15 Draw mechanisms for the following carbonyl substitution reactions. In the second problem, think carefully about whence the O atoms in the product come.

(a)




(b)




Ketones and aldehydes can be interconverted with acetals. Acetalizations are usually thermodynamically uphill, so the reaction is usually driven to completion by the removal of H_2O from the reaction mixture by azeotropic distillation or by

addition of a dehydrating agent like 4 Å molecular sieves or triethyl orthoformate, $\text{HC}(\text{OEt})_3$. Hydrolyses of acetals are usually executed simply by dissolving the acetal in water and a cosolvent such as THF and adding a catalytic amount of acid.


Example



The first step in acetal formation is protonation of the carbonyl O to give a carbocation. An OH group in ethylene glycol adds to the carbocation and loses H^+ to give a tetrahedral intermediate called a *hemiacetal*. Protonation of $-\text{OH}$ and loss of H_2O gives a new carbocation. Addition of the other OH group to the carbocation and deprotonation gives the acetal.




Problem 3.16 Draw a mechanism for the following reaction. Free H_2O is *not* an intermediate in the reaction. What is the coproduct?




Ketones and aldehydes can also be converted to enol ethers if after the loss of H_2O the carbocation fragments with loss of H^+ to give the alkene. Because enol ethers are very reactive toward H^+ , they are usually isolated only when the double bond is conjugated to an electron-withdrawing group, as in the conversion of β -diketones to vinylogous esters.

Example




The diketone first tautomerizes to the β -hydroxy enone. Protonation of the ketone O gives a very low energy carbocation, to which EtOH adds. Deprotonation of the nucleophile, protonation of the OH leaving group, and loss of H_2O gives a new carbocation, which undergoes a fragmentation reaction with loss of H^+ to give the enol ether product.



Why must the diketone tautomerize to the keto–enol before the addition of EtOH can occur? By the principle of microscopic reversibility, both enol ether formation and enol ether hydrolysis must proceed by the same sequence of steps (only in reverse of one another). Protonation of the enol ether, the first step in its hydrolysis, would certainly occur on the carbonyl O, not on C, so enol ether formation must proceed through the same intermediate.


Ketones/aldehydes, enols, and hemiacetals are all rapidly interconvertible under *either acidic or basic* conditions, but acetals and enol ethers are rapidly interconvertible with any of these species only under *acidic* conditions (Table 3.1). It is important for you to be able to recognize that any one of these species is functionally equivalent to any of the others under acidic conditions, and you need to be able to draw the mechanisms of their interconversion.

The *trimethylsilyl* enol ether (enol ether, $\text{R}^3 = \text{Me}_3\text{Si}$) can be converted directly into an enolate by treatment with CH_3Li or $\text{Bu}_4\text{N}^+ \text{F}^-$. Conversely, enolates can be converted

Table 3.1 Interconversions of Ketones and Aldehydes and their Equivalents


directly into enol ethers when they are treated with certain particularly oxophilic electrophiles such as Me_3SiCl or even some acyl chlorides.

As it will under basic conditions, a ketone or aldehyde will react very rapidly with a 1° or 2° amine under mildly acidic conditions to give an iminium ion, which can then undergo a variety of reactions. The mechanism under acidic conditions is similar to the mechanism under basic conditions, differing only in the timing of the protonation and deprotonation steps. The rate of the formation of the iminium ion is very, very fast when the reaction conditions are just mildly acidic. Under strongly acidic conditions, the amine spends most of its time as an ammonium ion, rendering it nonnucleophilic.




An iminium ion is more electrophilic than the ketone or aldehyde from which it is made, so it is often made in situ in the presence of a nucleophile with which it can react. For example, in *reductive alkylation* or *reductive amination*, a 1° or 2° amine reacts with a ketone or aldehyde in the presence of an acid-stable reducing agent such as sodium triacetoxyborohydride ($\text{NaBH}(\text{OAc})_3$) to give a 2° or 3° amine. The key intermediate is an iminium ion. The borohydride's reactivity is tuned so that it can react much more quickly with the nascent iminium ions in the solution than

with the starting ketone or aldehyde. The nascent iminium ion can also be reduced by catalytic hydrogenation (Chap. 6), a reaction which is also selective for iminium ions over ketones and aldehydes. Iminium ions can be trapped by other nucleophiles, as well, although any nucleophile that is used must be sufficiently nonbasic to survive under the mildly acidic conditions of iminium ion formation.




Problem 3.17 Draw the mechanism of the following *Stetter reaction*. Hint: It involves an iminium ion. Why is it particularly important to keep the pH of the Stetter reaction from becoming too acidic?



In Chap. 2, we saw that certain nucleophiles that also had leaving groups attached, such as CH_2N_2 , would react with ketones to give products in which a group previously attached to the carbonyl C atom migrated to the nucleophilic atom with concomitant expulsion of the leaving group. Such reactions can also occur under acidic conditions if the nucleophile is sufficiently nonbasic. For example, ketones react with peracids (RCO_3H) to give esters in the *Baeyer–Villiger oxidation*. The peracid is often *m*-chloroperbenzoic acid (mCPBA); peracetic acid and trifluoroperacetic acid are also commonly used. Peracids have an O–OH group attached to the carbonyl C. They are only slightly more acidic than alcohols, because deprotonation of the terminal O does not give a stabilized anion, but they are usually contaminated with considerable amounts of the corresponding acid. For this reason, the Baeyer–Villiger reaction is usually conducted under mildly acidic conditions. As is the case when nucleophiles add to carbonyl compounds under acidic conditions, protonation of the carbonyl O occurs first to make the carbonyl C even more electrophilic than it normally is. The terminal O of the peracid then adds to the carbonyl C, followed by proton transfer from the positively charged O atom to the leaving group attached to it. The O–O bond is very weak, so one of the groups attached to the former carbonyl C migrates to O, displacing carboxylic acid. The product ester is obtained after final loss of H^+ from the carbonyl O.


Example



3.5.2 Carbon Nucleophiles

The carbocation that is formed upon protonation of a carbonyl compound can lose H^+ from the α -carbon to give an enol. Enols are good nucleophiles. Thus, under acidic conditions, carbonyl compounds are *electrophilic at the carbonyl C and nucleophilic at the α carbon and on oxygen*, just like they are under basic conditions. Resonance-stabilized carbonyl compounds such as esters and amides are much less prone to convert to their enol tautomers than less stable carbonyl compounds such as ketones, aldehydes, and acyl chlorides; for this reason, esters and amides rarely undergo reactions at the α -carbon under acidic conditions.


Problem 3.18 Draw a mechanism for the following *Hell-Vollhard-Zelinsky* reaction.




Enols are particularly reactive toward carbonyl compounds and toward electrophilic alkenes such as α,β -unsaturated carbonyl compounds. For example, the Robinson annulation proceeds under acidic conditions as well as under basic

conditions, as shown in the next example. Under acidic conditions, the electrophilic carbonyl compound is protonated on the carbonyl O to make a carbocation before it is attacked by the enol.


Example



The Robinson annulation consists of a Michael addition, an aldol reaction, and a dehydration. In the Michael addition, the nucleophilic ketone is converted into an enol by protonation and deprotonation. The enol then adds to the *protonated* Michael acceptor. Deprotonation of the positively charged O, protonation of C of the enol, and deprotonation of O then give the overall Michael addition product.




In the aldol reaction, the nucleophilic ketone is first converted into an enol by protonation and deprotonation. The enol then adds to the *protonated* ketone in an aldol reaction. Deprotonation of the positively charged O gives the aldol.




In the dehydration, the ketone is first converted into an enol by protonation and deprotonation. Protonation of the alcohol O is then followed by an E1

elimination reaction (loss of H_2O and then loss of H^+) to give the product. As in the formation of the enol ether discussed earlier, it follows from the principle of microscopic reversibility that the ketone must be converted into an enol before E1 elimination occurs.




The *Mannich reaction* is another version of an aldol reaction that takes place under mildly acidic conditions. There are several variants, but all of them involve the reaction of a nucleophilic ketone with a primary or secondary ammonium ion (RNH_3^+ or R_2NH_2^+) and an aldehyde, usually formaldehyde (CH_2O). The Mannich reaction proceeds via an iminium ion ($\text{RNH}=\text{CH}_2^+$ or $\text{R}_2\text{N}=\text{CH}_2^+$) that reacts with the enol form of the ketone to give a β -aminoketone. Sometimes E1 elimination of the amine (via the enol) follows to give an α, β -unsaturated ketone.


Example




One can envision several alternative mechanisms for the Mannich reaction. In one alternative mechanism, the ketone attacks the aldehyde directly in an aldol reaction, the aldol undergoes E1 elimination of H_2O (via the enol) to make an α,β -unsaturated ketone, and then the amine adds to the enone in a Michael fashion to give the product. Evidence against this mechanism: Ketones with only a single α H undergo the Mannich reaction, but such ketones cannot be converted into α,β -unsaturated ketones.



In another alternative mechanism, the ketone attacks the aldehyde directly in an aldol reaction, and then the β C of the aldol undergoes $\text{S}_{\text{N}}2$ substitution, with the amine acting as the nucleophile. Evidence against this mechanism: $\text{S}_{\text{N}}2$ substitution reactions under acidic conditions require strongly acidic conditions, but the Mannich reaction takes place under only weakly acidic conditions.



Another alternative mechanism has the amine reacting with the *nucleophilic* ketone (not just the electrophilic one) to form an iminium ion, which can lose H^+ from the α -carbon to give an *enamine*. The enamine, not the enol, is then the actual nucleophile that attacks the iminium ion. After the formation of the C–C bond, a new iminium ion is formed, which reacts with H_2O to return the ketone product. This alternative is perfectly reasonable, and it may in fact be a better mechanism than the one that used the enol as the nucleophile.




Finally, the example above uses formaldehyde as the electrophile, but formaldehyde is probably insufficiently basic ($\text{pK}_{\text{a}} \approx -5$) to be protonated by a simple ammonium salt ($\text{pK}_{\text{a}} = 10$), as shown in the very first step above. In the absence of a slight excess of free acid, the reaction of formaldehyde with an ammonium salt to give an iminium ion probably proceeds by the basic mechanism (Chapter 2), with solvent acting to deprotonate the ammonium ion initially.

Common error alert: Whenever you see a reaction that involves a ketone or aldehyde and a 1° or 2° amine, it is likely that an iminium ion is an intermediate.


Some carbonyl-based compounds (imines, carboxylic acids) are better electrophiles under acidic conditions than they are under basic conditions. Reactions using these compounds as electrophiles are usually executed under acidic conditions. On the other hand, enolates are always better nucleophiles than enols; when carbonyl compounds are required to react with electrophiles that are not particularly reactive, such as esters or alkyl bromides, basic conditions are usually used. Carbonyl compounds that are particularly low in energy (esters, amides) have such a small proportion of enol at equilibrium that they cannot act as nucleophiles under acidic conditions. Nevertheless, no matter whether acidic or basic conditions are used, carbonyl compounds are always nucleophilic at the α -carbon and electrophilic at the carbonyl carbon.

Trimethylsilyl enol ethers, which are usually prepared by reaction of an enolate with Me_3SiCl , can be used as substitutes for enols in the Lewis acid-catalyzed Mukaiyama aldol and Michael reactions. The mechanism of the Mukaiyama aldol or Michael reaction is very straightforward. After addition of the nucleophilic $\text{C}=\text{C}$ π bond to the electrophile (activated by the Lewis acid), fragmentation of the $\text{O}-\text{SiMe}_3$ bond occurs; workup then provides the aldol or Michael adduct. The Me_3Si group, then, is treated as if it were nothing more than a big proton. The principal advantage of the Mukaiyama aldol and Michael reactions over the conventional versions is that the Mukaiyama versions allow esters and amides to act as nucleophiles under acidic conditions.


Example



Retroaldol and retro-Michael reactions occur under acidic conditions. The mechanisms are the microscopic reverse of the aldol and Michael reactions, as you would expect. One of the most widely used acid-catalyzed “retroaldol” reactions is the decarboxylation of β -ketoacids, malonic acids, and the like. Protonation of a carbonyl group gives a carbocation that undergoes fragmentation to lose CO_2 and give the product. Decarboxylation does not proceed under basic conditions, because the carboxylate anion is much lower in energy than the enolate product.




A cyclic TS for decarboxylation is often drawn. Such a mechanism can be described as a *retroene* reaction (see Chap. 4).



3.6 Catalysis Involving Iminium Ions


We have already discussed the mechanisms of the acid- and base-catalyzed intramolecular aldol reactions. Primary and secondary amines also catalyze the intramolecular aldol reaction. For example, proline catalyzes an asymmetric intramolecular aldol reaction that gives rise, after dehydration, to the *Hajos–Parrish ketone*, a compound useful in the synthesis of steroids.

Example




One reasonable mechanism is to have the amine act simply as a base, but such a mechanism is ruled out by the fact that 3° amines do not catalyze the reaction

nearly as well. If 3° amines are poor catalysts, but 1° and 2° amines are good catalysts, then the mechanism must involve steps that a 3° amine cannot undergo. For this reason, the best mechanism begins by the formation of an iminium ion at the acyclic ketone of the substrate, which is then deprotonated to give an enamine, the actual nucleophilic species. After an intramolecular aldol reaction of the enamine with one of the two remaining ketone groups, the resulting iminium ion reacts with H₂O to afford the product and to regenerate the catalyst. (The reaction proceeds asymmetrically because the enamine reacts preferentially with one of the two enantiotopic ketone groups.)




When a 1° or 2° amine reacts with an α,β -unsaturated carbonyl compound, an α,β -unsaturated iminium ion is obtained that is even more electrophilic at the β -carbon than the original carbonyl compound. If a nucleophile adds to the β -carbon, a new iminium ion is obtained, and it can be hydrolyzed in situ to a carbonyl-containing product and the original amine, which is free to engage another equivalent of substrate. As a result, the reaction is catalytic in amine. When an appropriate chiral, enantiomerically enriched amine is used, this process can be rendered asymmetric.

Example




Because the amine is provided as a salt, the reaction conditions are mildly acidic. First, the 2° amine and the α,β -unsaturated aldehyde combine to form an α,β -unsaturated iminium ion by the mechanism that generally prevails under acidic conditions. Second, the indole nucleophile adds to the β -carbon of the α,β -unsaturated iminium ion, converting the iminium ion to an enamine. Next, fragmentation to reestablish the indole's aromaticity occurs, and the enamine reacts with a proton to again become an iminium ion. Finally, hydrolysis of the iminium ion back to the original amine gives the Friedel–Crafts product and regenerates the 2° amine.




It would be acceptable to combine into a single step the fragmentation of the C–H bond of the nucleophile and the reaction of the enamine with H^+ . It would even be acceptable to omit the electron-flow arrows in such a single step and instead write, “ $\sim\text{H}^+$ ”. However, it would not be acceptable to show the enamine making a bond to the H^+ of the breaking C–H bond, as such a step would require a four-membered ring transition state, which would undoubtedly be quite high in energy.


Iminium ions play a central role in biology. For example, 11-*cis*-retinal, the compound responsible for all animals' ability to perceive light, reacts with the NH₂ group of a lysine residue in one of a group of proteins called opsins to give an iminium ion. The iminium ion, not free retinal, is the compound that absorbs a photon and initiates a chain of events that eventually leads to a signal being sent to the brain.




The *class 1 aldolases* catalyze the aldol reaction between a ketone and an aldehyde by using the NH₂ group of a lysine residue to form an enamine of the ketone. For example, a class 1 aldolase catalyzes the aldol reaction of dihydroxyacetone phosphate with glyceraldehyde 3-phosphate to give fructose 1,6-bisphosphate. The mechanism begins with a combination of the lysine NH₂ group with the ketone of dihydroxyacetone phosphate to give an iminium ion. Deprotonation of the iminium ion gives an enamine, which attacks the aldehyde moiety of glyceraldehyde 3-phosphate to give a new iminium ion and the key C–C bond. Simultaneously, a tyrosine residue is available to donate a proton to the developing negative charge on the former aldehyde O atom. Finally, hydrolysis of the iminium ion and reprotonation of tyrosine frees the lysine residue and generates fructose 1,6-bisphosphate. The enzyme controls the configurations of the two new stereocenters by controlling the spatial arrangement of the substrates in the active site.

Example







Iminium ions also form the basis of the chemistry of *vitamin B₆*. The term “vitamin B₆” is used to refer to several interconverting compounds, the most important of which are *pyridoxamine phosphate* and *pyridoxal phosphate*. These compounds can promote reductive amination reactions as well as various reactions of amines and α -amino acids such as decarboxylations, alkylations, and nucleophilic substitutions.




For example, pyridoxamine phosphate reacts with pyruvic acid (as well as other α -keto acids) to give alanine and pyridoxal phosphate. This *transamination* reaction begins by the formation of an imine and protonation of the pyridine N. (The OH group on the pyridine ring undoubtedly plays a role in stabilizing the imine by an intramolecular hydrogen bond.) A base in the active site of the enzyme deprotonates the benzylic position of the pyridoxamine, and the electrons from the broken C–H bond migrate onto the N atom of the pyridinium ion to become a lone pair. The same pair of electrons can then migrate down to the C atom α to the carboxylic acid group, allowing it to pick up H^+ to give a new imine. Hydrolysis of this new imine then gives alanine and pyridoxal phosphate.



In a related process, pyridoxal phosphate catalyzes the decarboxylation of α -amino acids. Again, the reaction begins by formation of an imine and protonation of the pyridine N. A base in the active site of the enzyme deprotonates the CO₂H group, initiating C–C bond cleavage as the electrons from that bond migrate onto the N atom of the pyridinium ion to become a lone pair. The same pair of electrons can then migrate back to the C atom of the imine, allowing it to pick up H⁺ to give a new imine. (Unlike in the transamination reaction, the C=N bond of the new imine has the same location as in the original imine.) Hydrolysis of this new imine then gives the decarboxylated amine and regenerates pyridoxal phosphate.




In the decarboxylation reaction, the H^+ that reacts with the imine C can be replaced by other electrophiles. For example, pyridoxal phosphate catalyzes the condensation of serine and palmitoyl-CoA (a thioester) to give dehydrosphingosine, a compound that is subsequently transformed into lipids that are found in the cell membrane. Here, after the decarboxylation step, the pair of electrons on the pyridine N can then migrate back to the C atom of the imine, allowing it to react with the thioester by a standard addition–elimination mechanism to give a keto–imine. (There is probably a residue in the active site of the enzyme that stabilizes the O^- of the tetrahedral intermediate with a hydrogen bond or an electrostatic interaction.) Hydrolysis of this new imine then gives the free amino ketone and regenerates pyridoxal phosphate.




Pyridoxal phosphate also catalyzes β - and γ -nucleophilic substitution reactions. These substitution reactions proceed by an elimination–addition mechanism sandwiched between a lot of H^+ transfer steps.

Problem 3.19 Draw mechanisms for the following two pyridoxal phosphate-catalyzed nucleophilic substitution reactions.

(a)





3.7 Summary

There are generally three methods for generating carbocations:

1. ionization of a $C-X^+$ σ bond (usually preceded by protonation of the leaving group);
2. reaction of a lone pair on the heteroatom in a $C=X$ π bond with a Lewis acid (typically H^+); and
3. reaction of a $C=C$ π bond with a Lewis acid (typically H^+ or a carbocation).

Carbocations generally undergo three typical reactions:

1. addition of a nucleophile (usually a lone-pair or π -bond nucleophile);
2. fragmentation to give a π bond and a new cation (often a carbocation or H^+); and
3. rearrangement (typically a 1,2-hydride or -alkyl shift).

The addition of a protic nucleophile to a carbocation is always followed by deprotonation of the nucleophile.

Substitution at $C(sp^3)$ usually occurs by an S_N1 mechanism under acidic conditions; the S_N2 mechanism is operative at $C(sp^3)$ only when the $C(sp^3)$ is 1° , the nucleophile is very good, and the conditions are *very* strongly acidic. (However, substitution at heteroatoms such as S and P usually occurs by an S_N2 mechanism under acidic conditions.)

Substitution at $C(sp^2)$ normally occurs by an addition–elimination mechanism under acidic conditions. Electrophiles add to nucleophilic $C=C$ π bonds, including most arenes, and nucleophiles add to $C=N$, $C=O$, and electrophilic $C=C$ π bonds.


Under both acidic and basic conditions, a carbonyl compound is electrophilic at the carbonyl carbon and nucleophilic at the α -carbon. Similarly, under both acidic and basic conditions, an α , β -unsaturated carbonyl compound is electrophilic at the carbonyl and β -carbon atoms and nucleophilic at the α -carbon after a nucleophile has already added to the β -carbon. Carbonyl mechanisms differ under acidic and basic conditions only in the protonation and deprotonation steps: under acidic conditions, nucleophilic addition is always preceded by protonation of the electrophile and followed by deprotonation of the nucleophile (if it is protic).

A reaction that involves a ketone or aldehyde and a 1° or 2° amine probably proceeds through an iminium ion intermediate.


3.8 Problems

1. Rank each set of compounds by the ease with which they ionize under acidic conditions.


(a)




(b)




(c)




(d)




(e)



(f)




(g)




2. Indicate the major product of each reaction, and draw a reasonable mechanism for its formation.


(a)




(b)




(c)




(d)




(e)




(f)















(g)



(h)




3. When β -caryophyllene (**1**), is treated with sulfuric acid in ether, a large assortment of products is formed. Initially, after **1** is consumed, compounds **2** through **4** are the major hydrocarbon products. As time goes on, compounds **2** through **4** disappear, and compounds **5** through **9** appear in the reaction mixture. At longer times, compounds **5** through **9** disappear, and compounds **10** through **12** become the final hydrocarbon products. A large number of alcohols is also formed. Draw mechanisms explaining the formation of each of these products. *Your mechanism should also account for the sequence of their formation.*




4. Draw mechanisms for the following reactions.


(a) Li^+ in ether is a strong Lewis acid.




(b)




(c)




(d)








but




(e)




- (f) 
- (g) 
- (h) 
- (i) 
- (j) The product, one example of an azo dye, was used for a long time as the coloring agent in margarine until it was discovered that it was carcinogenic.
- 
- (k) When *p*-nitroaniline and salicylic acid are used as starting materials in the reaction in (j), Alizarin Yellow R, an azo compound used to dye wool, is obtained. What is the structure of Alizarin Yellow R?


- (l) The following reaction helps explain why piperidine is a federally controlled substance.




(m)




(n)




(o)



- (p) The following reaction is the key step in the biosynthesis of cholesterol. Compounds that inhibit the enzyme that catalyzes the reaction have been studied intensively because of their potential as anticholesterol drugs.




(q) The Wallach rearrangement.




The following pieces of information should help you. (1) When ^{18}O -labelled water is used as solvent, the product is labeled. (2) When one N in the starting material is selectively labeled with ^{15}N , the label is found to be randomly distributed in the product. (3) The key intermediate is dicationic.


- (r) Think of the Me_3Si^+ group as a big proton.




but






- (s) First draw a mechanism for formation of the five-membered ring. Then draw a mechanism by which the five-membered ring is converted into the six-membered ring simply by heating (no acid present).




- (t) The following two pieces of information should help you draw the mechanism. (1) The rate-determining step involves cleavage of the C–Cl bond. (2) The rate decreases *dramatically* as the number of C atoms between N and Cl increases.







(x) SnCl_2 is also a Lewis acid.




(y) *Note the stereochemistry of the product!* What does this tell you about the mechanism?




(z)




(aa)




(bb)



(cc)



5. A group of authors isolated from a plant a known compound, hyperbeanol B, and a new compound, which they named hypatulone A. After using various spectroscopic techniques to determine the structure of hypatulone A, they proposed the following biosynthetic pathway from hyperbeanol B to hypatulone A. See if you can find at least four features of the proposed biosynthetic pathway that make it highly implausible.



4.1 Introduction

A pericyclic reaction is a reaction in which bonds form or break at the termini of one or more conjugated π systems. The electrons move around in a circle, all bonds are made and broken *simultaneously*, and no intermediates intervene. The requirement of concertedness distinguishes pericyclic reactions from most polar or free-radical reactions, although for many pericyclic reactions, one can also draw reasonable alternative stepwise mechanisms.


For each class of pericyclic reactions two or more of the following characteristics will be discussed: the *typical reactions*, *regioselectivity*, *stereoselectivity*, and *stereospecificity*. The discussions of typical reactions and stereospecificity will help you recognize when pericyclic reactions are occurring in a particular chemical reaction. The discussions of regioselectivity, stereoselectivity, and stereospecificity will allow you to *predict* the structures and stereochemistry of the products obtained from pericyclic reactions.

4.1.1 Classes of Pericyclic Reactions

Before discussing specific ones, it is important to learn how to describe pericyclic reactions. There are four major classes of pericyclic reactions: *electrocyclic reactions* (ring openings or ring closings), *cycloadditions*, *sigmatropic rearrangements*, and *ene reactions*.

Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_4) contains supplementary material, which is available to authorized users.

In an *electrocyclic ring closing*, a σ bond forms between the termini of a conjugated π system. An *electrocyclic ring opening* is the reverse reaction, in which a C–C σ bond breaks to give a conjugated π system in which the termini used to be σ -bonded. Empty or filled p orbitals can participate in the π system. Electrocyclic reactions are further subclassified as 2π electrocyclic, 4π electrocyclic, etc., according to how many electrons are involved in the reaction. As in all pericyclic reactions, the electrons move around in a circle. Note how the π bonds shift upon formation or cleavage of the key σ bond.




You may have trouble seeing that the last example of an electrocyclic reaction is a two-electron and not a four-electron reaction. The new σ bond is formed between the termini of a three-atom π system. That three-atom system contains two electrons. The lone pairs of O are not part of the three-atom π system, so they are not included in the electron count of the electrocyclic reaction.


When σ bonds are formed between the ends of two π systems to give a cyclic product, the reaction is called a *cycloaddition*. The reverse reaction is called a *retrocycloaddition*. Cycloadditions are further classified as $[m + n]$ according to the number of *atoms* in each component.¹ Again, it is important to note not only the number of atoms but also the number of electrons involved in the process. You are already familiar with the six-electron $[4 + 2]$ cycloaddition, the *Diels–Alder reaction*. Four-electron $[2 + 2]$ cycloadditions are less common, for reasons that will be discussed, but ketenes undergo them readily. The $[3 + 2]$ cycloadditions (or 1,3-dipolar cycloadditions) are a very important class of six-electron cycloadditions that are used

¹Two conventions for naming cycloadditions are used in the literature. The older convention, and the one used in this textbook, is that m and n denote the number of *atoms* in each component. Woodward and Hoffmann altered the convention to make m and n denote the number of *electrons* in each component. The number of electrons and the number of atoms are the same for reactions involving neutral species such as the Diels–Alder reaction, but they are *not* the same for reactions involving charged or dipolar species. For example, the 1,3-dipolar cycloaddition is a $[3 + 2]$ cycloaddition according to the older convention and a $[4 + 2]$ cycloaddition according to the newer one. Always be careful to note which convention is being used.

to make a wide variety of five-membered heterocycles. Other cycloadditions, including [8 + 2], [4 + 3], and [6 + 4] cycloadditions, are also known.




Cheletropic reactions (e.g., [2 + 1] cycloadditions and [4 + 1] retrocycloadditions) are a special class of cycloadditions in which one of the components is a single atom. The one-atom component must have one full and one empty orbital; it may be a carbene ($\pm\text{CR}_2$), SO_2 ($\text{O}=\ddot{\text{S}}^+-\text{O}^- \leftrightarrow -\text{O}-\ddot{\text{S}}^{2+}-\text{O}^-$), or $\text{C}\equiv\text{O}$ ($^-\text{C}\equiv\text{O}^+ \leftrightarrow \pm\text{C}=\text{O}$). The [4 + 1] cycloadditions usually proceed in the retro direction with the expulsion of a stable small molecule such as CO or SO_2 .




Sigmatropic rearrangements involve the cleavage of a σ bond connecting the end of one fragment with the end of another, and concerted formation of another σ bond at the other ends of the fragments. The σ bond seems to migrate, hence the name of the reaction. Sigmatropic rearrangements are subclassified as $[n,m]$ sigmatropic rearrangements, where n and m are the number of *atoms* (not electrons) in each of the fragments. The very common [3,3] sigmatropic rearrangement is called


the *Cope rearrangement*. When one of the atoms in the π system is O, the [3,3] sigmatropic rearrangement is called the *Claisen rearrangement* (not to be confused with the Claisen condensation). (The initial product, a cyclohexadienone, isomerizes to a phenol, thus driving the reaction to the right.) The cationic [1,2] sigmatropic rearrangement (i.e., the 1,2-alkyl or hydride shift) has already been encountered. It is important to note the number of electrons involved in sigmatropic rearrangements, too. The [3,3] and [1,5] rearrangements are six-electron reactions, the cationic [1,2] rearrangement is a two-electron reaction, and the [1,3] rearrangement is a four-electron reaction.



Students seem to have more trouble recognizing and naming sigmatropic rearrangements than any other reaction. There is no net change in the number of σ or π bonds in a sigmatropic rearrangement. To name a sigmatropic rearrangement, draw a dotted line between the atoms where a bond forms, and draw short squiggles through the center of the bond that breaks and the dotted line. Put a heavy dot at each atom involved in σ bond formation or cleavage. Then count the number of atoms around the π system from one dot to another inclusive, being careful not to cross a squiggle.



The *ene* reaction is always a six-electron reaction. It shares some characteristics with the [4 + 2] cycloaddition and the [1,5] sigmatropic rearrangement. Like the [4 + 2] cycloaddition, a four-atom component reacts with a two-atom component, but in the *ene* reaction, the four-atom component consists of a π bond and an allylic σ bond (usually to a H atom), not two π bonds. Like a [1,5] sigmatropic rearrangement, a σ bond migrates, but the *ene* reaction also produces one σ bond at the expense of one π bond. When the reaction occurs between a C=C π bond and a C=C π bond with an allylic hydrogen, it is called the *Alder ene reaction*. The reaction may or may not be intramolecular. Retroene reactions are commonly seen, too, as in the thermal elimination of acetic acid from alkyl acetates. The *heteroene reaction* looks like a cross between a [3 + 2] cycloaddition and a [1,4] sigmatropic rearrangement. Retroheteroene reactions are used in some elimination procedures that are very important synthetically.




The key characteristics of the four major types of pericyclic reactions are summarized in Table 4.1.

Common error alert: *The pericyclic reactions are superficially similar to one another, and students sometimes have trouble distinguishing the different types from one another.* Archetypical, six-electron examples of each type of pericyclic

Table 4.1 Bond changes in pericyclic reactions


Reaction class	Changes in bond types
Electrocyclic reactions	One π bond \rightleftharpoons one σ bond
Cycloadditions	Two π bonds \rightleftharpoons two σ bonds
Cheletropic reactions	One π bond and $X^\pm \rightleftharpoons$ two σ bonds
Sigmatropic rearrangements	One σ bond \rightarrow new σ bond
Ene reactions	One π bond \rightleftharpoons one σ bond <i>and</i> one σ bond migrates

reaction are shown in the figure. (Note the *degeneracy* of the archetypical sigmatropic rearrangement.) Each archetypical reaction has three arrows moving in a circle, but each results in a different change in the patterns of bonding.




When drawing the change in bonding patterns in pericyclic reactions, it doesn't matter whether you draw the electrons moving clockwise or counterclockwise, because pericyclic reactions are *not* characterized by the movement of electron density from electron-rich to electron-poor or high-energy to low-energy sites. The electron-flow arrows are merely meant to show the change in bonding patterns as the reaction proceeds from starting material to product. However, when one component in the reaction has an atom with a formal negative charge, as in the [3 + 2] cycloaddition, the [2,3] sigmatropic rearrangement, or the retroheteroene reaction, it is important to begin your electron-pushing there.

Common error alert: *Students often draw fictional one-step pericyclic mechanisms for reactions that require more than one step.* A good guard against this sort of error is to be sure that you can name any pericyclic step in your mechanism. For example, for the following reaction, you may be tempted to draw a four-electron, one-step mechanism involving the C–C σ bond of the first starting material and the π bond of the second. Such a mechanism, however, cannot be classified in the scheme that has just been discussed, and therefore it is likely to be incorrect.



Stereospecificity, the property that the stereochemistry of the starting materials determines the stereochemistry of the product, is one of the hallmarks of pericyclic reactions. It is possible to draw two-step, nonconcerted, polar or free-radical mechanisms for many pericyclic reactions, but these two-step mechanisms fail to account for the stereospecificity of the reactions. For example, a two-step polar mechanism can be drawn for the Diels–Alder reaction between 2-methoxybutadiene (a nucleophile) and ethyl *cis*-crotonate (an electrophile). This mechanism proceeds through a dipolar intermediate in which one new σ bond has formed. In this intermediate, there is free rotation about the two C atoms of the dienophile, so the *cis* stereochemical relationship between the Me and CO₂Et groups is expected to be lost in the product. In fact, though, the product is exclusively *cis*. This finding does not completely rule out a polar mechanism—it is possible that the intermediate exists, but that ring closure occurs more quickly than rotation about the σ bond—but it does limit the lifetime of the dipolar intermediate to such an extent that one can say *practically* that it does not exist.



Many stereochemical results like these, and the consistent observation of non-thermodynamic products that would not be expected from two-step mechanisms, have accumulated to support the operation of the pericyclic mechanism in *most* cases. Recent advances in experimental and theoretical techniques have allowed chemists to probe the mechanisms of pericyclic reactions at time scales far shorter than the time required to rotate about a C–C σ bond, and these experiments have supported concerted mechanisms for some pericyclic reactions and nonconcerted mechanisms for others. In practical terms, though, if no experimental or theoretical evidence rules it out, Occam’s razor compels you to propose a concerted mechanism in favor of a nonconcerted one.


Pericyclic reactions can proceed under acidic or basic conditions. For example, the oxy-Cope rearrangement is greatly accelerated under basic conditions, while the Diels–Alder reaction is greatly accelerated by Lewis acids. Often a series of polar reactions is used to synthesize an unstable intermediate, which then undergoes a pericyclic reaction to reveal the product. In other words, a good command of polar mechanisms (Chaps. 2 and 3) is essential to understanding how to draw pericyclic mechanisms.

Like all reactions, pericyclic reactions are reversible in principle (even though they may be irreversible in practice). The forward and reverse reactions *always go through the same transition state*. As an analogy, if you wanted to travel from

Lexington, Kentucky, to Richmond, Virginia, you would choose the path that went through the lowest gap in the Appalachian mountains. If you wanted to go from Richmond back to Lexington, you would choose the same route, only in reverse. The path you chose would not depend on which direction you were traveling. Reactions obey the same principle.


4.1.2 Polyene MOs

You may think that there's not much to say about the "no-mechanism" pericyclic reactions, but there is. First, how they proceed stereochemically and even whether they proceed at all depends on whether the reaction is conducted *thermally* or *photochemically*. For example, many [2 + 2] cycloadditions proceed *only* photochemically, whereas all [4 + 2] cycloadditions proceed thermally. Second, all pericyclic reactions proceed stereospecifically, but the stereochemistry of the products sometimes depends on the reaction conditions. For example, 2,4,6-octatriene gives *cis*-5,6-dimethylcyclohexadiene upon heating and *trans*-5,6-dimethylcyclohexadiene upon photolysis. *These phenomena can be explained by examining the MOs of the reactants.* The rules governing whether pericyclic reactions proceed and the stereochemical courses when they do proceed are known as the *Woodward–Hoffmann rules*.



The Woodward–Hoffmann rules can be rationalized by examining the properties of the *frontier MOs* of the reactants, i.e., their HOMO (highest occupied molecular orbital) and LUMO (lowest unoccupied molecular orbital). In order to understand pericyclic reactions, then, you need to be able to construct the MOs of a polyene system from the constituent *p* orbitals.


Consider 1,3-butadiene. Four *p* orbitals interact, each with its neighbors, to produce four MOs. These four MOs are called ψ_0 , ψ_1 , ψ_2 , and ψ_3 . In the lowest energy MO, ψ_0 , every *p* orbital overlaps constructively with its neighbor to give an MO in which there are *no nodes*, or changes in sign between orbitals. In the highest energy MO, ψ_3 , every *p* orbital overlaps destructively with its neighbor to give an MO in which there are three nodes. In the intermediate-energy MOs, ψ_1 and ψ_2 , there are one and two nodes, respectively, and the MOs are constructed accordingly. Under thermal conditions, the four electrons derived from the four AOs occupy ψ_0 and ψ_1 ; ψ_1 is the HOMO and ψ_2 is the LUMO.



The signs of the AOs do not tell the whole story. In each MO, each AO has a coefficient associated with it that reflects the magnitude of its contribution to the MO. The coefficient can range from 0 to 1. The squares of the coefficients of one atom's AO in each MO add up to 1. The coefficients of the MOs can provide important information about reactivity.

Note that the signs of the terminal orbitals alternate from like, to opposite, to like, to opposite. A physical chemist would say that the symmetries of the MOs alternate between *symmetric* and *antisymmetric*. This property is universal among the MOs of polyenes. *You do not need to construct the complete MOs of any polyene to determine the signs of the termini of the HOMO and LUMO, on which the properties of pericyclic reactions largely depend.*

In 1,3,5-hexatriene, six AOs produce six MOs, the signs of whose termini alternate from like, to opposite, to like, etc. The number of nodes increases with each MO. In the ground state of 1,3,5-hexatriene, ψ_2 is the HOMO and ψ_3 is the LUMO. Note that in ψ_3 and ψ_4 , the *p* orbitals of the second and fifth C atoms of the chain have a coefficient of zero, indicating that the *p* orbitals from those C atoms do not contribute at all to ψ_3 and ψ_4 . Two of the nodes in both ψ_3 and ψ_4 pass through the centers of these two C atoms.



The symmetries of the MOs of conjugated π systems with odd numbers of atoms also alternate. The allyl system has three MOs: ψ_0 (symmetric), ψ_1 (antisymmetric), and ψ_2 (symmetric). In the allyl cation, ψ_0 is the HOMO and ψ_1 is the LUMO, whereas in the allyl anion, ψ_1 is the HOMO and ψ_2 is the LUMO. The pentadienyl system has five MOs. In the pentadienyl cation, ψ_1 (antisymmetric) is the HOMO and ψ_2 (symmetric) is the LUMO, whereas in the pentadienyl anion, ψ_2 (symmetric) is the HOMO and ψ_3 (antisymmetric) is the LUMO.

ψ_2	+	-	+		ψ_4	+	-	+	-	+
ψ_1	+	.	-	<i>MOs of the pentadienyl π system</i>	ψ_3	+	-	.	+	-
ψ_0	+	+	+		ψ_2	+	.	-	.	+
					ψ_1	+	+	.	-	-
					ψ_0	+	+	+	+	+


4.2 Electrocyclic Reactions

4.2.1 Typical Reactions


In an electrocyclic ring closing, a new σ bond forms between the termini of an acyclic conjugated π system to give a cyclic compound with one fewer π bond. In the reverse reaction, an electrocyclic ring opening, a ring σ bond that is allylic to both termini of a conjugated π system breaks to give an acyclic compound with one more π bond. Like all pericyclic reactions, electrocyclic reactions are reversible in principle. The ring-closed compound is *usually* lower in energy, because it has a σ bond in place of a π bond, but not always.

Cyclobutenes are in electrocyclic equilibrium with 1,3-butadienes. 1,3-Butadienes are lower in energy, because cyclobutenes are very strained, and it is therefore possible to convert a cyclobutene to a butadiene *thermally*. The reverse reaction, the conversion of a 1,3-butadiene to a cyclobutene, does not usually proceed under thermal conditions, as it involves an uphill climb in energy.


However, because they are more conjugated, 1,3-butadienes absorb light at longer wavelengths than cyclobutenes, so it is possible to convert a 1,3-butadiene to a cyclobutene *photochemically* by choosing a wavelength at which the butadiene absorbs and the cyclobutene does not.



The equilibrium between the cyclobutene and the 1,3-butadiene is shifted in favor of the cyclobutene in benzocyclobutenes. The electrocyclic ring opening of a benzocyclobutene, an aromatic compound, leads to an *o*-xylylene, a nonaromatic and reactive compound. *o*-Xylylenes are useful intermediates in Diels–Alder reactions.




1,3-Cyclohexadienes are in electrocyclic equilibrium with 1,3,5-hexatrienes. Neither compound is strained, and the cyclohexadiene has one more σ bond than the hexatriene, so the cyclohexadiene is lower in energy. The hexatriene is more conjugated than the cyclohexadiene, so it is more reactive photochemically. Under *both* thermal and photochemical conditions, then, the cyclohexadiene is favored over the hexatriene.



The equilibrium between the 1,3-cyclohexadiene and the 1,3,5-hexatriene is less lopsided when ring closure creates a strained ring. For example, the equilibrium constant for the interconversion of 1,3,5-cycloheptatriene and norcaradiene (bicyclo[4.1.0]hepta-2,4-diene) is close to 1, and the interconversion occurs rapidly at room temperature. The ring *opening* is facile because the strain of the three-membered ring is relieved, and the ring *closing* is facile because the ends of the π system are held close together and because a C–C σ bond is gained at the expense of a π bond.




Allyl and pentadienyl cations participate in electrocyclic ring openings and closings, too. (The corresponding anions undergo similar reactions, but they are less important synthetically.) Less highly conjugated cations are produced upon ring closure of these species, but the decrease in cation stabilization is compensated by the gain of a C–C σ bond. In the case of the allyl system, the increase in strain upon ring closing makes ring opening more favored.




In the *Nazarov cyclization*, a divinyl ketone undergoes electrocyclic ring closing upon treatment with a Lewis acid such as SnCl_4 to give a cyclopentenone. The allylic cation obtained upon electrocyclic ring closure can undergo fragmentation of either of two different σ bonds to give the product. The lower energy product is usually obtained, but the tendency of the C–SiMe₃ bond to fragment preferentially to the C–H bond can be used to put the double bond in the thermodynamically less favorable position.


Example




Problem 4.1 Draw a reasonable mechanism for the following preparation of pentamethylcyclopentadiene, a useful ligand for transition metals.




The electrocyclic equilibrium between cyclopropyl cations and allyl cations normally favors the allyl cation, because the cyclopropyl cation is both more strained and less conjugated than the starting allylic cation. For example, the cyclopropyl halide shown undergoes concerted loss of Br^- and electrocyclic ring opening to the allyl cation upon distillation. (In principle, a ring opening that is not concerted with loss of the leaving group could be drawn, but the cyclopropyl cation is very high in energy.) Addition of Br^- to the allylic cation then gives the product.




The carbene derived from halogen–metal exchange between RLi and a dibromocyclopropane can also undergo a four-electron electrocyclic ring opening to give an allene.



Cyclopropanones are in electrocyclic equilibrium with *oxyallyl cations*. The cyclopropanone is generally lower in energy, but the oxyallyl cation is not so much higher in energy that it is kinetically inaccessible. Oxyallyl cations can undergo cycloadditions, as will be discussed later.




α -Haloketones rearrange to carboxylic acids in the *Favorskii rearrangement*. When the ketone is cyclic, ring contraction results.




Two reasonable mechanisms can be drawn for the Favorskii rearrangement. In the first mechanism, the ketone acts as an *acid*. Deprotonation of the α -carbon that lacks the Cl atom gives an enolate. The enolate undergoes two-electron electrocyclic ring closing with expulsion of Cl^- to give a cyclopropane intermediate. Addition of HO^- to the carbonyl group of this very strained ketone is followed by strain-relieving elimination of an alkyl group to give a carbanion, which is probably quenched by solvent even as it forms.

Mechanism 1:




In the second mechanism, which was discussed in Chap. 2, the ketone acts as an *electrophile*. Addition of HO^- to the carbonyl group, then migration of C to its electrophilic neighbor with expulsion of Cl^- , provides the product.


Mechanism 2:



Mechanism 2 (the semibenzilic acid mechanism) looks better, but labeling studies show that the two C atoms α to the ketone become equivalent in the course of the reaction, which is consistent only with mechanism 1 (the electrocyclic mechanism). The rearrangement of α -chloro- α -phenylacetone to methyl hydrocinnamate is also consistent only with the electrocyclic mechanism; if the semibenzilic mechanism were operative, then methyl 2-phenylpropionate would be the product.




However, the rearrangement of α -chloroacetophenone to diphenylacetic acid *must* proceed by a semibenzilic acid mechanism, because a cyclopropane can't form.




To summarize, when H atoms are present on the α -carbon opposite the leaving group, the electrocyclic mechanism usually operates; when they are not, the semibenzilic mechanism operates. Why does the electrocyclic mechanism proceed more quickly than the “more reasonable” semibenzilic mechanism for enolizable α -haloketones? Deprotonation and electrocyclic ring closing are both very rapid reactions—the latter even when a strained ring is formed—and they must simply be faster than HO^- addition and migration, despite what our “chemical intuition” tells us.

Problem 4.2 Draw a reasonable mechanism for the following reaction. A Favorskii rearrangement is involved.




The electrocyclic ring closing of the allyl “cation” in the Favorskii rearrangement proceeds only because the cation in the product is quenched by O^- . Charge neutralization also provides the driving force for the electrocyclic ring closing of vinylcarbene to give cyclopropene. The ring closing can be drawn as either a two-electron- or a four-electron process, depending on whether the empty orbital or the filled orbital of the carbene is conjugated to the π bond.




The key to identifying an electrocyclic ring *closing* is to look for the formation of a new bond at the ends of a conjugated π system. The key to identifying an electrocyclic ring *opening* is to look for the cleavage of a σ bond joining the allylic positions of a conjugated π system. Three-membered rings are closed from or opened to allylic systems by electrocyclic reactions.

Example


The following rearrangement reaction was proposed to be the biosynthetic pathway to the natural product endiandric acid A.




If you number the atoms, you will see that you need to make bonds at C5–C12, C6–C11, C9–C17, and C10–C14.




Sometimes it helps to draw dashed lines where you need to make bonds.



The starting material contains a 1,3,5,7-tetraene group (C5 to C12), and one of the bonds you need to make, C5–C12, is between the termini of that system. An eight-electron electrocyclic ring closing forms that bond. The electrocyclic reaction also creates a new 1,3,5-triene group (C6–C11), and another bond you need to make, C6–C11, is at the termini of that system. A six-electron electrocyclic ring closing forms that bond.




The last two bonds are formed by a Diels–Alder reaction ([4 + 2] cycloaddition) between the C9=C10 π bond and the diene from C14 to C17.




You may have been tempted to form the C5–C12 and C6–C11 bonds *simultaneously* by a [2 + 2] cycloaddition. You will soon see, though, that [2 + 2] cycloadditions of simple C=C π bonds are forbidden to occur under thermal conditions by the Woodward–Hoffmann rules.

Problem 4.3 When phorone is treated with base, isophorone is obtained by an electrocyclic ring closing. Draw a reasonable mechanism.




Problem 4.4 4-Vinylcyclobutenones are very unstable compounds, isomerizing rapidly to phenols. Draw a reasonable mechanism involving electrocyclic reactions.




4.2.2 Stereospecificity

Of all the pericyclic reactions, the stereochemical course of electrocyclic reactions is easiest to understand, because electrocyclic reactions are unimolecular and involve only one array of orbitals. First, consider the electrocyclic ring closing of a butadiene, a four-electron reaction. The butadiene has four substituents at the termini. When the butadiene is in its reactive *s-cis* conformation, two of the groups can be described as *in* groups (because they are on the concave face of the arc defined by the four atoms of the butadiene group), and two as *out* groups (because they are on the convex face of the same arc). In the electrocyclic reaction, the termini of the butadiene must rotate in order for the *p* orbitals at the termini to overlap and form a bond. Two stereochemical results are possible. *The stereochemical result of the reaction depends on how the two termini rotate.* If the termini rotate in the same direction (conrotatory), then the two out groups become trans to each other, the two in groups become trans to each other, and any out group becomes cis to any in group.




On the other hand, if they rotate in opposite directions (*disrotatory*), then the two out groups become cis to each other, the two in groups become cis to each other, and any out group becomes trans to an in group.




It happens that under thermal conditions the electrocyclic ring closing of butadienes always proceeds by the conrotatory pathway. There are several ways to rationalize this observation; we use the frontier MO method here. Under thermal conditions, the HOMO of 1,3-butadiene is ψ_1 , and the LUMO is ψ_2 . The electrocyclic ring closing proceeds so that there is a constructive interaction where bond-making takes place as the HOMO goes through the TS. Because the HOMO ψ_1 has a bonding interaction between the termini of the π system in the conrotatory TS and an antibonding interaction between the termini of the π system in the disrotatory TS, the reaction proceeds in conrotatory fashion.

Under photochemical conditions, the electrocyclic ring closing of butadienes always proceeds by the disrotatory pathway, which is the opposite of the result under thermal conditions. The FMOs make the stereochemical result easy to understand. Under photochemical conditions, an electron is promoted from the HOMO ψ_1 to the LUMO ψ_2 , so ψ_2 becomes the HOMO. Molecular orbital ψ_2 has an antibonding interaction between the termini of the π system in the conrotatory TS but a bonding interaction between the termini of the π system in the disrotatory TS, so the reaction proceeds in disrotatory fashion.


It is easier to see the FMO interactions in electrocyclic ring closing reactions than in ring opening reactions. However, the TSs for ring closing and ring opening are the same, so the stereochemistry of cyclobutene ring opening is conrotatory under thermal conditions and disrotatory under photochemical conditions—the same as the stereochemistry of butadiene ring closing.



In summary, for butadienes and cyclobutenes: Four-electron, thermal, conrotatory; four-electron, photochemical, disrotatory. The easiest way to visualize the stereochemical result is to make a fist, use your thumbs to designate substituents at the termini of the π system, and rotate your fists to determine the stereochemical result upon dis- or conrotatory ring closure or opening.



The stereochemistry of electrocyclic ring closings of 1,3,5-hexatrienes is opposite to that observed in 1,3-butadienes: under thermal conditions, they proceed by the disrotatory pathway, whereas under photochemical conditions, they proceed by the conrotatory pathway. The disrotatory TS derived from the thermal HOMO (ψ_2 , symmetric) of 1,3,5-hexatriene and the conrotatory TS derived from the photochemical HOMO of 1,3,5-hexatriene (ψ_3 , antisymmetric) have bonding interactions at the termini. Again, the TS for six-electron ring opening is the same as the TS for six-electron ring closing, so ring openings of 1,3-cyclohexadienes are also disrotatory under thermal conditions and conrotatory under photochemical conditions.



You may begin to discern a pattern. The Woodward–Hoffmann rules for electrocyclic reactions are as follows (Table 4.2): Electrocyclic reactions involving an odd number of electron pairs proceed through a disrotatory TS under thermal conditions and a conrotatory TS under photochemical conditions. Electrocyclic reactions involving an even number of electron pairs proceed through a conrotatory TS under thermal conditions and a disrotatory TS under photochemical conditions. In practice, you need only remember “even-thermal-con” (or any other combination) to generate the entire table.

Problem 4.5 Cycloheptatriene undergoes rapid electrocyclic ring closure under thermal conditions. Determine the structure and stereochemistry of the product.

Problem 4.6 Confirm that the proposed mechanism of formation of endriandic acid A is consistent with the observed stereochemistry of the product.

Problem 4.7 Draw the HOMO for the pentadienyl cation $\text{H}_2\text{C}=\text{CH}-\text{CH}=\text{CH}-\text{CH}_2^+$, and determine whether it should undergo disrotatory or conrotatory ring closing under thermal conditions. Then do the same for the pentadienyl anion $\text{H}_2\text{C}=\text{CH}-\text{CH}=\text{CH}-\text{CH}_2^-$. Are the stereochemical courses of these reactions consistent with the Woodward–Hoffmann rules?

The Woodward–Hoffmann rules for electrocyclic reactions can also be formulated in terms of being *suprafacial* and *antarafacial* (Table 4.3). A π system is said to react *suprafacially* in a pericyclic reaction when the bonds being made to the two


Table 4.2 Woodward–Hoffmann rules for electrocyclic reactions

Number of electron pairs	Δ	$h\nu$
Odd	Disrotatory	Conrotatory
Even	Conrotatory	Disrotatory

Table 4.3 Woodward–Hoffmann rules for electrocyclic reactions

Number of electron pairs	Δ	$h\nu$
Odd	Suprafacial	Antarafacial
Even	Antarafacial	Suprafacial

termini of the π system are made to the same face of the π system. It reacts *antarafacially* when the bonds are made to opposite faces of the π system. In electrocyclic reactions, disrotatory reactions are suprafacial, and conrotatory reactions are antarafacial.




The value of the terms “suprafacial” and “antarafacial” is that, unlike “disrotatory” and “conrotatory”, they can also be used to describe the way that π systems react in cycloadditions and sigmatropic rearrangements. Most importantly, when a π system reacts suprafacially, its out groups become cis in the product; when it reacts antarafacially, they become trans. Note that in disrotatory electrocyclic reactions, the out groups become cis, and in conrotatory electrocyclic reactions, the out groups become trans.


The property that the stereochemical result of an electrocyclic reaction is absolutely predictable is called *stereospecificity*. A stereospecific reaction will give you one stereochemical result when a cis starting material is used, and the opposite result when a trans starting material is used. Other examples of stereospecific reactions include S_N2 substitutions, catalytic hydrogenation of alkynes or alkenes, and dihydroxylation and bromination of alkenes.

The Woodward–Hoffmann rules can be used to predict the stereochemical result of any electrocyclic ring opening or closing. There are a few conditions to the Woodward–Hoffmann rules of which you must be aware. First, the Woodward–Hoffmann rules apply only to concerted, pericyclic reactions. If an apparent electrocyclic reaction actually proceeds by a nonconcerted mechanism, the rules do not apply. Second, a reaction can be forced to proceed through the higher energy TS if the lower energy one is raised prohibitively high in energy by geometric

constraints. In these cases, the starting material is usually more stable than one would expect. For example, Dewar benzene is surprisingly stable, because for it to decompose to benzene, it must go through the “disallowed” disrotatory TS; the “allowed” conrotatory ring opening gives a *trans* double bond in the six-membered ring, which is prohibitively high in energy.




The biosynthesis of vitamin D₂ also illustrates the Woodward–Hoffmann rules. Mammals prepare precalciferol from ergosterol by a six-electron electrocyclic ring opening. The ring opening must proceed in conrotatory fashion (otherwise a *trans* double bond in a six-membered ring would be obtained), so it requires light. When sunlight never shines on one’s skin, vitamin D₂ synthesis is inhibited, and one may develop rickets.




Of course, too much sunlight is bad for you, too, due to another photochemical pericyclic reaction that will be discussed later.

Two-electron electrocyclic ring openings are also stereospecific. 1-Chloro-1,3-di-*t*-butylacetone, upon treatment with base, can undergo electrocyclic ring closing to give di-*t*-butylcyclopropanone. The intermediate dipole can exist in three different diastereomeric forms. The lowest energy one has the *t*-Bu groups pointing outward. This out,out diastereomer undergoes disrotatory electrocyclic ring closing under the thermal conditions to give only the higher energy *cis* product, which is in fact the product that is observed first. In time, more *trans* product is observed, as the *cis* product undergoes stereospecific electrocyclic ring opening to the lower energy out,out dipole, which can undergo unfavorable equilibration to the higher energy out,in dipole, which can close to the lower energy, *trans* product!




4.2.3 Stereoselectivity

Consider the electrocyclic ring opening of *trans*-3,4-dimethylcyclobutene. This compound opens in a conrotatory fashion under thermal conditions. Two products might be obtained from conrotatory ring openings allowed by the Woodward–Hoffman rules, but in fact only the *trans,trans* product is obtained, because there are severe steric interactions in the TS leading to the *cis,cis* product.




The phenomenon that one “allowed” TS is preferred over the other is called *torquoselectivity*, a special kind of stereoselectivity. The ring opening of *trans*-3,4-dimethylcyclobutene is *stereospecific* because the *cis,trans* isomer is never obtained, but it is *stereoselective* because the *trans,trans* isomer is selectively obtained over the *cis,cis* isomer.

Torquoselectivity is observed in a few other contexts. The ring opening of *cis*-bicyclo[4.2.0]octa-2,4-diene can occur in two disrotatory modes in principle. One of those modes, however, gives a product that has two *trans* double bonds in an eight-membered ring. This mode is disfavored with respect to the other disrotatory mode, which gives an all-*cis* product.




Halocyclopropanes undergo electrocyclic ring openings. Consider the two diastereomers of 1-bromo-*cis*-2,3-dimethylcyclopropane. If the Br^- left first to give a cyclopropyl cation, and then the ring opening occurred, then the *trans*- and *cis*-bromo compounds would give the same intermediate cyclopropyl cation; therefore, the allyl cation in which the two Me groups were “out” would be obtained from *either* diastereomer. Moreover, the *cis*-bromo compound would be expected to give the product more quickly because of steric encouragement of departure of the leaving group. In fact, though, the two isomers give isomeric allyl cations, and the *trans*-bromo compound reacts much more rapidly than the *cis* one. This result suggests that the two compounds do not proceed through a common intermediate produced by loss of Br^- , and therefore the loss of the leaving group and the ring opening must be concerted. Why does the *trans*-bromo compound react more quickly? The orbitals that constitute the breaking σ bond prefer to turn in the direction so that their large lobes overlap with the back lobe of the C–Br bond in the transition state (i.e., backside displacement of Br^-). In the *cis*-bromo compound, when the orbitals of the breaking σ bond turn in this way, the two Me groups bump into each other in the TS, so the reaction is much slower.



There are many cases where the torquoselectivity is not nearly so easy to explain or predict. For example, which diastereomer is predominantly obtained from the

electrocyclic ring opening of *cis*-3-chloro-4-methylcyclobutene? The answer is not obvious. Steric effects could easily be offset by electronic effects. Calculations of TS energies can sometimes give reasonably good predictions.




4.3 Cycloadditions

4.3.1 Typical Reactions


4.3.1.1 The Diels–Alder Reaction

The best-known cycloaddition is the *Diels–Alder reaction*, a six-electron, [4 + 2] cycloaddition. A 1,3-diene reacts with the π bond of a *dienophile* to give a six-membered ring with one π bond. Two new σ bonds are formed at the expense of two π bonds. The classic Diels–Alder reaction gives a carbocyclic ring, but hetero-Diels–Alder reactions, in which the new ring is heterocyclic, are widely used also.




The product of the Diels–Alder reaction is a cyclohexene that has two new bonds in a 1,3-relationship. Look for the presence of such a ring in the product to determine that a Diels–Alder reaction has occurred.

Example




Make: C1–C5, C4–C6. Break: C1–C4. The two new σ bonds have a 1,3-relationship in a new six-membered ring, suggesting that a Diels–Alder


reaction has taken place. Disconnect the C1–C5 and C4–C6 bonds of the product to see the immediate precursor to the product, an *o*-xylylene. The double-headed arrow (\Rightarrow), a *retrosynthetic arrow*, indicates that you are working backward from the product.



To get from the starting material to the *o*-xylylene, the C1–C4 bond needs to break. It can be broken by an electrocyclic ring opening of the cyclobutene. The entire mechanism in the forward direction, then, is as follows:




The Diels–Alder reaction requires that the diene be in the *s*-cis conformation, with the two double bonds of the diene coplanar and pointing in the same direction. Rotation about the σ bond between the internal C atoms of the diene interconverts the *s*-cis and *s*-trans conformations. In the *s*-trans conformation, there are fewer steric interactions between the *in* groups at the termini of the diene, so dienes normally reside predominantly in this lower energy (by about 4.0 kcal/mol) conformation. **Common error alert:** Do not confuse the *cis* or *trans* configurations of the double bonds of a 1,3-diene substituted at the terminal C atoms with the *s*-cis and *s*-trans conformations of the diene.




The barrier to converting the *s*-trans conformation to the *s*-cis conformation contributes to the overall activation barrier for Diels–Alder reactions. Structural factors that increase the proportion of diene in its *s*-cis conformation increase the rate of the Diels–Alder reaction, and factors that increase the proportion of diene in

its *s-trans* conformation decrease the rate of the reaction. Cyclopentadiene is one of the best dienes for the Diels–Alder reaction partly because it cannot rotate out of its *s-cis* conformation. In fact, cyclopentadiene undergoes [4 + 2] cycloaddition to itself so readily that it lasts only a few hours at 0 °C. *o*-Xylylenes are especially good dienes both because of their enforced *s-cis* geometry and because a nonaromatic starting material is transformed into an aromatic product. By contrast, dienes in which one of the double bonds is *cis* are poor substrates for Diels–Alder reactions because steric interactions between the *in* substituents in the *s-cis* conformation are particularly severe, and dienes whose *s-trans* conformation is enforced do not ever undergo the Diels–Alder reaction.




Similarly, acyclic 2,3-diazadienes (azines) have never been observed to undergo Diels–Alder reactions because the lone pairs on N repel one another, making the *s-cis* conformation about 16 kcal/mol higher in energy than the *s-trans* conformation. *Cyclic* azines, though, easily undergo Diels–Alder reactions.




Because two σ bonds are produced at the expense of two π bonds, the Diels–Alder reaction is normally exothermic in the forward direction, but the *retro*-Diels–Alder reaction is facile when one of the products is N_2 , CO_2 , or an aromatic ring.

Example




Make: none. Break: C1–C2, C3–C4, C5–C6. The C1–C2 and C5–C6 bonds are in a 1,3-relationship in a six-membered ring, and there is a C7=C8 π bond in

a 1,3-relationship to each of them in that ring. Therefore, the C1–C2 and C5–C6 bonds can be broken by a retro-Diels–Alder reaction to give the naphthalene and a cyclobutene. Cleavage of the C3–C4 bond then occurs by an electrocyclic reaction.




Most Diels–Alder reactions occur with what is called *normal electron demand*, in which an *electron-rich* (nucleophilic) *diene* reacts with an *electron-poor* (electrophilic) *dienophile*. The dienophile may be substituted with carbonyl, CN, sulfonyl, NO₂, or any other electron-withdrawing group. Dienophiles substituted with two electron-withdrawing groups (diethyl fumarate, maleic anhydride, benzoquinone) are particularly good substrates for the Diels–Alder reaction. Dienophiles that are not electron-poor undergo Diels–Alder reactions with electron-rich dienes under rather drastic conditions, if at all, although the rate of such a reaction can be increased by making it intramolecular. However, compounds with very strained double bonds (benzyne, norbornadiene) make good dienophiles even when they are not substituted with electron-withdrawing groups. Alkenes make better dienophiles than alkynes, all other things being equal.

Good Diels–Alder dienophiles




Dienes substituted with RO and R₂N groups (e.g., Danishefsky's diene, 1-methoxy-3-trimethylsilyloxy-1,3-butadiene) are particularly good substrates for Diels–Alder reactions, but alkyl-substituted dienes and even butadiene itself are common substrates. Benzene rings are very poor dienes in Diels–Alder reactions, because they lose aromaticity upon cycloaddition, but less aromatic compounds such as anthracene undergo Diels–Alder reactions more readily. Again, both cyclopentadiene and *o*-xylylenes are especially good dienes in Diels–Alder reactions.


Good Diels–Alder dienes




Frontier MO theory can be used to understand the dependence of the rate of the Diels–Alder reaction on the electronic nature of the substrates. Like any reaction, the rate of the Diels–Alder reaction is determined by the energy of its TS. In the TS of most Diels–Alder reactions, the *HOMO of the diene* interacts with the *LUMO of the dienophile*.



The energy of the Diels–Alder TS is directly related to the strength of the interaction between the MOs, which is in turn related to the difference in energy between the two MOs. The smaller the difference in energy between the two MOs, the stronger their interaction, the lower the energy of the TS, and the faster the reaction. The $\text{HOMO}_{\text{diene}}$, being a bonding orbital, is lower in energy than the $\text{LUMO}_{\text{dienophile}}$. Substitution of the diene with electron-donating groups raises the energy of the $\text{HOMO}_{\text{diene}}$, bringing it closer to the energy of the $\text{LUMO}_{\text{dienophile}}$, and substitution of the dienophile with electron-withdrawing groups lowers the energy of the $\text{LUMO}_{\text{dienophile}}$, bringing it closer to the energy of the $\text{HOMO}_{\text{diene}}$. Either of these substitutions brings the two orbitals closer in energy, increasing the rate of the reaction.



I mentioned earlier that alkynes are poorer dienophiles than the correspondingly substituted alkenes. The $\text{C}\equiv\text{C}$ bond in an alkyne is shorter than the $\text{C}=\text{C}$ bond in the corresponding alkene, so the $\text{C}(p)\text{--C}(p)$ overlap is better, and thus the alkyne's HOMO is lower in energy and its LUMO higher in energy than the alkene's. The LUMO of the alkyne interacts more poorly with the $\text{HOMO}_{\text{diene}}$ than the lower energy LUMO of the alkene, so the Diels–Alder reaction of the alkyne is slower.




C–C distance is shorter in alkynes than in alkenes, so C(p)–C(p) interaction is stronger...

... therefore alkyne has higher energy LUMO, interacts more weakly with HOMO of diene, and reacts more slowly in Diels–Alder reaction


The energy of the $LUMO_{\text{dienophile}}$ can also be lowered by the use of a Lewis acid catalyst. The Lewis acid coordinates to the O of a carbonyl group substituent on the dienophile, lowering the energy of the $LUMO_{\text{dienophile}}$ and leading to an increased reaction rate. The Lewis acid also increases the regioselectivity and the stereoselectivity of the reaction. Use of a chiral Lewis acid can lead to an enantioselective Diels–Alder reaction. The development of catalytic asymmetric Diels–Alder reactions is an active area of research. **Common error alert:** *It is easy to assume that a reaction mechanism is polar acidic when a Lewis acid is present, but Lewis acids are often used to promote cycloadditions, too.*

Note that the dependence of the rate of a Diels–Alder reaction on the electronic match between $HOMO_{\text{diene}}$ and $LUMO_{\text{dienophile}}$ is a kinetic effect, not a thermodynamic one. The reaction of an electron-rich diene with an electron-rich dienophile is just as thermodynamically favorable as its reaction with an electron-poor dienophile, but it does not proceed at a perceptible rate.

Very electron-poor dienes can undergo Diels–Alder reactions with electron-rich dienophiles in the *inverse electron-demand* Diels–Alder reaction. The dominant interaction in the TS of inverse electron-demand Diels–Alder reactions is between the $LUMO_{\text{diene}}$ and the $HOMO_{\text{dienophile}}$.




For example, the reaction of hexachlorocyclopentadiene with norbornadiene proceeds readily by an inverse electron-demand process to give Aldrin, an insecticide that has been banned because of its environmental persistence.




Dienes containing heteroatoms such as N and O undergo inverse electron-demand Diels–Alder reactions with electron-rich dienophiles such as enol ethers and enamines. The relatively low energy of the heteroatom p orbitals dramatically lowers the energy of both the $\text{HOMO}_{\text{diene}}$ and $\text{LUMO}_{\text{diene}}$.


Example



Make: C1–C5, C4–C6. Break: C1–N2, C4–N3, C6–OMe. The two new σ bonds have a 1,3-relationship in the six-membered ring, suggesting a Diels–Alder reaction as the first step. The Diels–Alder adduct can undergo a retro-Diels–Alder reaction to cleave the C–N bonds and give N_2 as a coproduct.




An elimination reaction (probably E1) then gives the observed product.




Lewis acid catalysis can lower the energy of $\text{LUMO}_{\text{diene}}$ in heterodienes even further, as in the cycloaddition of enol ethers to α,β -unsaturated carbonyl compounds. This reaction provides an important method for the synthesis of glucals,

dehydrated carbohydrates that are important building blocks in the synthesis of polysaccharides.




Heteroatomic dienophiles such as aldehydes and imines also participate in Diels–Alder reactions. Heteroatomic dienophiles have low-energy MOs, so they undergo normal electron-demand Diels–Alder reactions with electron-rich dienes. Singlet O₂ (¹O₂, O=O) also undergoes normal electron-demand Diels–Alder reactions. Atmospheric O₂ is a triplet, best described as a 1,2-diradical ($\cdot\text{O}-\text{O}\cdot$), whereas ¹O₂ has a normal O=O π bond and no unpaired electrons. Triplet O₂ is converted to the higher energy singlet form by *hν* in the presence of a sensitizer such as Rose Bengal.




4.3.1.2 Other Cycloadditions

1,3-Dipoles react with alkenes and alkynes (*dipolarophiles*) in 1,3-dipolar cycloadditions (a.k.a., [3 + 2] cycloadditions) to give five-membered heterocycles. Many agrochemicals and pharmaceuticals contain five-membered heterocycles, and the dipolar cycloaddition is an important synthetic route to these compounds.




The three-atom component of the cycloaddition, the 1,3-dipole, is a compound for which a relatively low energy resonance structure can be drawn in which one terminus has a formal positive charge (and is electron-deficient) and the other terminus has a formal negative charge. All the common 1,3-dipoles have a heteroatom (N or O) in the central position in order to stabilize the electron-deficient terminus.




The five-membered heterocyclic product is the key to identifying a 1,3-dipolar cycloaddition. Many 1,3-dipoles are not stable, so they are generated by a series of polar reactions and then react in situ without being isolated.

Example




The reaction produces a five-membered heterocycle, suggesting a 1,3-dipolar cycloaddition. What penultimate intermediate would undergo a 1,3-dipolar cycloaddition to give the observed product? The two-atom component of the dipolar cycloaddition is the C=C π bond, so the three-atom component must be C–N–O. The C is likely to be the (+) terminus and the O the (–) terminus of the dipole. The 1,3-dipole in this reaction is a *nitrile oxide*, an unstable functional group that must be generated in situ.




How is the nitrile oxide formed? The elements of water must be eliminated from the nitro compound, and an N–O bond must be cleaved. The O of the NO₂

group is not a leaving group, so the role of ArNCO must be to convert it into one. Nitro compounds are quite acidic ($pK_a = 9$), so deprotonation by Et_3N is the first step. Attack of O^- on the electrophilic C of the isocyanate, protonation of N, and then E2 elimination gives the nitrile oxide, which undergoes the [3 + 2] cycloaddition to give the product.



Note how this problem is most easily solved by working backwards one step from the product. This technique is very useful for solving pericyclic mechanism problems.


Problem 4.8 Draw a reasonable mechanism for the following reaction that involves a 1,3-dipolar cycloaddition. Hint: Work backwards one step from the product before working forward.



The selectivity of 1,3-dipoles for electron-rich or electron-poor dipolarophiles is complex. Very electron-poor dipoles such as ozone react most quickly with electron-rich and slowly with electron-poor dipolarophiles. Other dipoles, such as azides, react quickly with very electron-poor dipolarophiles, slowly with dipolarophiles of intermediate electronic character, and quickly with very electron-rich dipolarophiles. This “U-shaped reactivity” is due to a crossover in the nature of the reaction from $\text{LUMO}_{\text{dipole}}/\text{HOMO}_{\text{dipolarophile}}$ -controlled to $\text{HOMO}_{\text{dipole}}/\text{LUMO}_{\text{dipolarophile}}$ -controlled as the dipolarophile becomes more electron-poor. At intermediate electronic character, neither the $\text{HOMO}_{\text{dipole}}/\text{LUMO}_{\text{dipolarophile}}$ nor the $\text{LUMO}_{\text{dipole}}/\text{HOMO}_{\text{dipolarophile}}$ interaction is particularly strong, and the reaction proceeds slowly.

The reaction of ozone with alkenes is one of the most useful 1,3-dipolar cycloadditions. Ozone undergoes [3 + 2] cycloaddition to the alkene to give a

1,2,3-trioxolane, which immediately decomposes by a [3 + 2] retrocycloaddition to give a carbonyl oxide and an aldehyde. When the ozonolysis is carried out in the presence of an alcohol, the alcohol adds to the carbonyl oxide to give a hydroperoxide acetal. In the absence of alcohol, though, the carbonyl oxide undergoes another [3 + 2] cycloaddition with the aldehyde to give a 1,2,4-trioxolane.




1,2,4-Trioxolanes are isolable, but they can explode when heated gently. Neither 1,2,4-trioxolanes and hydroperoxide acetals are usually isolated, though. They are decomposed in situ in one of three ways: by gentle reduction (Me_2S , Ph_3P , H_2 over Pd, or Zn/HCl) to give two aldehydes, by a stronger reduction (NaBH_4 or LiAlH_4) to give two alcohols, or oxidatively (H_2O_2 and acid) to give two carboxylic acids. (Obviously, if the alkene is tri- or tetrasubstituted, ketones and not aldehydes are obtained.) Today the Me_2S reduction is the most widely used method, as it gives the most valuable products (aldehydes) in high yields, and the coproduct (DMSO) is easily removed.


Problem 4.9 Draw a mechanism for the reaction of Me_2S with a 1,2,4-trioxolane to give two aldehydes.

The [2 + 2] cycloadditions are widely used reactions. There are basically three situations in which [2 + 2] cycloadditions are seen: when the reaction is promoted by light, when one of the components is a ketene ($\text{R}_2\text{C}=\text{C}=\text{O}$) or another *cumulene* (e.g., $\text{RN}=\text{C}=\text{O}$), or when one of the components has a π bond between C and a second-row or heavier element (e.g., $\text{Ph}_3\text{P}=\text{CH}_2$ or $\text{Cp}_2\text{Ti}=\text{CH}_2$).


- The [2 + 2] photocycloaddition of two alkenes is widely used to form cyclobutanes. The reaction proceeds in the forward direction because the product cannot absorb light of the wavelengths that the starting material can absorb. In the Paterno-Büchi reaction, one of the two-atom components is a ketone or an aldehyde instead of an alkene. Why these [2 + 2] cycloadditions require light to proceed will be discussed later.




The light-induced [2 + 2] cycloaddition can occur *in vivo*. Two adjacent thymine residues in DNA can undergo a [2 + 2] cycloaddition to give a *thymine dimer*. DNA repair enzymes excise the dimer and usually repair it correctly, but occasionally they make a mistake, and a mutation occurs. The mutation can lead to skin cancer. Sunlight is essential for your health (for the ergosterol to precalciferol electrocyclic ring opening), but not too much sunlight!



Problem 4.10 The thymine dimer shown in the preceding example is produced by a [2 + 2] cycloaddition of two C=C bonds. A different, perhaps more mutagenic thymine dimer is produced by a different [2 + 2] cycloaddition. Draw a detailed mechanism for the formation of the second type of thymine dimer.




- The ketene–alkene cycloaddition gives cyclobutanones in a *thermal* reaction. Most ketenes are not kinetically stable, so they are usually generated *in situ*, either by E2 elimination of HCl from an acyl chloride or by a Wolff rearrangement of an α -diazoketone (see Chap. 2).




Other cumulenes such as isocyanates $\text{RN}=\text{C}=\text{O}$ can also undergo thermal [2 + 2] cycloadditions. The [2 + 2] cycloaddition of an isocyanate and an alkene is a useful


route to β -lactams, the key functional group in the penicillin and cephalosporin antibiotics, as is the [2 + 2] cycloaddition of a ketene and an imine.




Ketenes dimerize by a [2 + 2] cycloaddition in the absence of another substrate. The electron-rich C=C π bond combines with the electron-poor C=O π bond to give a β -lactone.




- The most important example of the third type of [2 + 2] cycloaddition is the Wittig reaction ($\text{Ph}_3\text{P}=\text{CH}_2 + \text{R}_2\text{C}=\text{O} \rightarrow \text{Ph}_3\text{P}=\text{O} + \text{R}_2\text{C}=\text{CH}_2$). The phosphorane adds to the ketone to give a phosphaoxetane, either by a concerted, [2 + 2] cycloaddition or by a two-step, polar process involving a *betaine* (pronounced BAY-tah-een) intermediate. The phosphaoxetane then undergoes [2 + 2] retrocycloaddition to give $\text{Ph}_3\text{P}=\text{O}$ and $\text{R}_2\text{C}=\text{CH}_2$.




There are other kinds of cycloadditions, too. The [4 + 1] cycloaddition, a cheletropic reaction, usually goes in the retro direction for entropic reasons. 3-Sulfolene (butadiene sulfone, 2,5-dihydrothiophene 1,1-dioxide) undergoes a [4 + 1] retrocycloaddition to generate SO_2 and 1,3-butadiene, which can undergo a Diels–Alder reaction with a dienophile. It is much more convenient to use 3-sulfolene instead of 1,3-butadiene itself, as the latter compound is a gas that is prone to polymerization.




Cyclopentadienones are very prone to do Diels–Alder reactions because of their enforced *s-cis* conformation and their antiaromaticity. The Diels–Alder reaction of a substituted cyclopentadienone and an alkyne is followed immediately by a [4 + 1] retrocycloaddition to generate CO and an aromatic compound.



Problem 4.11 A cyclopentadienone is the starting point for a cascade of cycloadditions and retrocycloadditions in the following reaction. Draw a reasonable mechanism. Hint: Number the atoms and draw the coproducts!



The [2 + 1] cycloaddition of carbenes and alkenes to give cyclopropanes was discussed in Chap. 2. Other cycloadditions are less common, although [4 + 3], [4 + 4], [6 + 4], [8 + 2] and many other cycloadditions are certainly known. The [4 + 3] cycloaddition in particular involves an allyl cation as the three-atom component and an electron-rich diene as the four-atom component.




The following are some key ways of identifying cycloaddition reactions:


- All cycloadditions (except chelotropic reactions) form two new σ bonds between the termini of two π systems.
- If you see a new six-membered ring containing two new bonds with a 1,3-relationship and a π bond, think Diels–Alder! A six-membered ring fused to a benzene ring is often made by the [4 + 2] cycloaddition of an *o*-xylylene and a dienophile or by a [4 + 2] cycloaddition of benzyne and a 1,3-diene.

- If you see a five-membered *heterocycle*, especially one containing N, think 1,3-dipolar cycloaddition! One of the ring heteroatoms is the central atom of the 1,3-dipole.
- If you see a four-membered ring, think [2 + 2] cycloaddition, especially if the ring is a cyclobutanone (ketene) or light is required (photochemically allowed). Ketenes and other cumulenes undergo [2 + 2] cycloadditions with special facility. An oxetane (four-membered ring with one O) is often obtained from the [2 + 2] photocycloaddition of a carbonyl compound and an alkene.


Example




A five-membered heterocycle is formed, suggesting a 1,3-dipolar cycloaddition. A 1,3-dipole almost always has a heteroatom in the 2 position, and the heterocycle here has only one heteroatom, so the 1,3-dipole must be the azomethine ylide.



The azomethine ylide must form from the amino acid and acetone. Briefly, the amine condenses with acetone to give an iminium ion, and decarboxylation produces the 1,3-dipole, which can undergo [3 + 2] cycloaddition to C₆₀ to give the observed product. By now you should be able to draw a mechanism for formation of the iminium ion.




Problem 4.12 The following reaction proceeds by a series of cycloadditions and retrocycloadditions. Draw a reasonable mechanism.




4.3.2 Regioselectivity

In the Diels–Alder reaction of *trans*-1-methoxybutadiene with ethyl acrylate, either the 1,2- or the 1,3-disubstituted product can be obtained in principle. The 1,3-disubstituted product is lower in energy (less steric hindrance), but the kinetic product is the 1,2-disubstituted compound. The easiest way to explain this phenomenon is to note that C4 of the diene is nucleophilic, and C2 of the dienophile is electrophilic. Combination of C4_{diene} with C2_{dienophile} gives the observed product.




The same explanation can be used to rationalize the outcome of the reaction of isoprene (2-methyl-1,3-butadiene) with acrolein (2-propenal). In this case, though, since the diene is 2-substituted, C1_{diene} is nucleophilic and combines with C2_{dienophile} to give the observed product.



In fact, since most Diels–Alder reactions proceed by the reaction of nucleophilic dienes with electrophilic dienophiles, the following rule can be formulated: Diels–Alder reactions proceed to put the most electron-donating substituent on the diene and the most electron-withdrawing substituent on the dienophile either “ortho” or “para” to one another. This “ortho–para rule” misuses the terms ortho and para, which really apply only to benzene rings, but it allows one to remember the regioselectivity of these reactions fairly easily.


The regioselectivity of an *intramolecular* cycloaddition depends more on geometric constraints within the substrate than electronic preferences.

Sometimes the ortho–para rule doesn't work well, especially when two substituents on the diene have competing directing abilities. For example, a PhS substituent at C1_{diene} is more strongly directing than a MeO substituent at C2_{diene}. By resonance arguments, the opposite should be the case, as MeO is a better resonance donor than PhS.



The only way the result can be explained is by looking at the coefficients of the orbitals of the HOMO of the diene and the LUMO of the dienophile. When the *p* orbitals of the diene combine in a bonding and antibonding way to make the HOMO and the LUMO, they do not contribute an equal weight to both MOs (unless the dienophile is symmetrical). (The situation is analogous to the one where C(*sp*³) and O(*sp*³) combine to form a σ bond: the O(*sp*³) orbital contributes more to the σ orbital, and the C(*sp*³) orbital contributes more to the σ^* .) *The Diels–Alder reaction proceeds so that the diene terminus with the largest coefficient in the diene HOMO interacts with the dienophile terminus with the largest coefficient in the dienophile LUMO.* It happens that the influence of substituents on C1 and C4 of the diene on the orbital coefficients is greater than that of substituents on C2 or C3. With simple dienes, the prediction from orbital coefficient arguments is usually the same as from the ortho–para rule—that the most electron-donating substituent on the diene and the most electron-withdrawing substituent on the dienophile are “ortho” or “para” in the product—but the orbital coefficient rule explains many cases that can't be explained simply by looking at resonance structures.


The regioselectivity of inverse electron-demand Diels–Alder reactions, 1,3-dipolar cycloadditions, and other cycloadditions can similarly be explained by resonance and orbital coefficient arguments. Determining which end of a 1,3-dipole is “nucleophilic” and which end is “electrophilic” can be dicey, though. In nitrones ($R_2C=NR-O^-$), the O is the nucleophilic end, so it reacts with the electrophilic end of a dipolarophile.




The problem with orbital coefficient arguments is that they require a calculation, whereas resonance arguments can be made using pen and paper. On the other hand, computers have made it possible for almost anyone to do a simple orbital coefficient calculation.

4.3.3 Stereospecificity

Some cycloadditions proceed thermally, whereas others require $h\nu$. The dependence of certain cycloadditions on the presence of light can be explained by examining interactions between the MOs of the two reacting components. Frontier MO theory suggests that the rate of cycloadditions is determined by the strength of the interaction of the HOMO of one component with the LUMO of the other. In normal electron-demand Diels–Alder reactions, $\text{HOMO}_{\text{diene}} (\psi_1)$ interacts with $\text{LUMO}_{\text{dienophile}} (\psi_1)$. Both of these orbitals are antisymmetric, so there is positive overlap between the orbitals where the two σ bonds form when both components of the reaction react from the same face of the π system (*suprafacially*).




Under inverse electron demand, the symmetric $\text{LUMO}_{\text{diene}} (\psi_2)$ interacts with the symmetric $\text{HOMO}_{\text{dienophile}} (\psi_0)$. Again, there is positive overlap between the orbitals at both termini of the two π systems when both components of the reaction react suprafacially.




By contrast, under photochemical conditions and normal electron demand, $\text{HOMO}_{\text{diene}}$ changes from the antisymmetric ψ_1 to the symmetric ψ_2 . In this case, positive overlap at both termini of the π systems can occur only if one of the π

components reacts *antarafacially*. This situation is very difficult to achieve geometrically, and hence six-electron cycloadditions do not proceed photochemically.




The stereochemical relationships among substituents in a suprafacial component of a cycloaddition are preserved in the cycloadduct. Groups that are *cis* (or *trans*) to one another in the dienophile become *cis* (or *trans*) to one another in the product. The two out groups in the diene become *cis* to one another in the product, as do the two in groups. Because one diastereomeric starting material gives one diastereomeric product, cycloadditions are said to be *stereospecific*.




Note that two stereoisomeric products that are consistent with the Woodward–Hoffmann rules can be obtained. The Woodward–Hoffmann rules allow you to predict the stereochemical relationship between substituents derived from the *same* component. They do not allow you to predict the relationship between substituents derived from *different* components. Guidelines for predicting the latter kind of relationship will be discussed shortly.

An analogous picture can be drawn for $[3 + 2]$ cycloadditions. These six-electron reactions can be either $\text{HOMO}_{\text{dipole}}/\text{LUMO}_{\text{dipolarophile}}$ -controlled or $\text{HOMO}_{\text{dipolarophile}}/\text{LUMO}_{\text{dipole}}$ -controlled. In either case, the maximum number of bonding interactions between the termini occurs when both components are suprafacial.



As in the Diels–Alder reaction, the stereochemistry of both starting materials is preserved in the products. The two out groups on the dipole become *cis* in the

product, as do the two in groups. The stereochemical relationships among the substituents of the dipolarophile are also preserved in the product.




Which groups on the termini are in or out is less clear for 1,3-dipoles than it is for 1,3-dienes. The three atoms of the dipole form a curve. The terminal substituents pointing to the concave side of the curve are the in groups, and the substituents pointing to the convex side are the out groups.


The suprafaciality of the 1,3-dipole component is important only when both ends of the dipole are C(sp^2) atoms (i.e., in azomethine ylides and carbonyl ylides). If either end of the dipole is N, O, or C(sp), the termini have no stereochemical relationship in either the dipole or the cycloadduct.

Example


Predict the stereochemistry of the product of the following reaction




The product is clearly derived from a [3 + 2] cycloaddition. Disconnection of the appropriate bonds leads back to an azomethine ylide intermediate, which can be formed from the aziridine by electrocyclic ring opening.




As for the stereochemistry, the electrocyclic ring opening of the aziridine is a four-electron process and is therefore conrotatory under thermal conditions. One CO_2Me group becomes an in group, and one an out group. The suprafacial nature of the [3 + 2] cycloaddition means that these two groups become trans in the product. The two ester groups on the dipolarophile, of course, retain their stereochemistry. The orientation of the esters in the product is “up, down, down, down” (or vice versa).




Under thermal conditions, the TS of the [2 + 2] cycloaddition is made up of the antisymmetric ψ_1 (the LUMO) of one component and the symmetric ψ_0 (the HOMO) of the other. Positive overlap between the orbitals at both termini of the π systems can be obtained only if one of the components reacts antarafacially. This orientation is very difficult to achieve geometrically, and hence [2 + 2] cycloadditions do not normally proceed under thermal conditions. However, under photochemical conditions, one of the components has an electron promoted from ψ_0 to ψ_1 . Now the HOMO–LUMO interaction is between ψ_1 of the photoexcited component and ψ_1 of the unexcited component, and thus *both* components can be suprafacial in the TS. The [2 + 2] cycloaddition of most alkenes and carbonyl compounds do in fact proceed *only* upon irradiation with light.




Three classes of [2 + 2] cycloadditions do proceed under thermal conditions. Ketenes ($R_2C=C=O$) undergo concerted cycloadditions to alkenes under thermal conditions because the ketene can react *antarafacially* with an alkene that reacts *suprafacially*. The two termini of the $C=C$ π bond of the ketene react from *opposite* faces of the π bond, creating positive overlap between the orbitals at both termini of the two π systems. The antarafacial nature of the ketene does not have any stereochemical consequences, as there is no *cis*–*trans* relationship in the ketene to preserve in the product. The alkene component of the [2 + 2] cycloaddition with ketenes, however, reacts suprafacially, and its stereochemistry is *preserved* in the product.



Why is it that ketenes are able to react antarafacially, and alkenes are not? After all, the π orbital of the ketene that reacts antarafacially is also present in an alkene. In ketenes, one of the C atoms has only the sterically undemanding O atom attached to it. Common alkenes have sterically demanding substituents on *both* ends of the antarafacial component. The substituents at one end of the antarafacial alkene jut directly into the path of the other alkene in the TS, sterically inhibiting the reaction.



The second kind of thermally allowed $[2 + 2]$ cycloaddition occurs when one of the atoms involved is a second-row or heavier element, as in the Wittig reaction. Whether the first step of the Wittig reaction actually proceeds in a concerted fashion is a matter of debate, but the point here is that a concerted mechanism is a reasonable possibility. Moreover, there is no controversy over whether the second step of the mechanism is a concerted $[2 + 2]$ retrocycloaddition.




Why aren't the $[2 + 2]$ cycloaddition and retrocycloaddition of the Wittig reaction disallowed? The Woodward–Hoffmann rules state that when the symmetries of the MOs of the reactants are mismatched in ways that we have discussed, the TS for the reaction is raised very high in energy, and the reaction is therefore “disallowed”. In principle, even a disallowed reaction can proceed at sufficiently high temperatures; the reason this approach usually doesn't work is that other reactions usually take place at temperatures far below those required for the disallowed process. (However, even a symmetry-disallowed reaction involving only C=C π bonds can proceed at reasonable temperatures if it is particularly favorable, as in the electrocyclic ring opening of Dewar benzene to benzene.) Now, the Wittig reaction proceeds at ordinary temperatures because when π bonds to elements heavier than C, N, or O are involved in pericyclic reactions, factors other than mismatches in MO symmetries become much more important to the energy of the TS. In other words, the concerted mechanism for the Wittig reaction *is* disallowed by the Woodward–Hoffmann symmetry rules, but it is not *as* disallowed as the $[2 + 2]$ cycloadditions of C=C or C=O π bonds. Other factors, including the poor

overlap of the orbitals comprising the C=P π bond, the very high energy of that bond, and the very low energy of the P–O σ bond, lower the energy of the TS of the Wittig reaction enough that it proceeds at ordinary temperatures.

Metal alkylidenes ($M=CR_2$) undergo thermally allowed [2 + 2] cycloadditions with alkenes during *olefin metathesis* (see Chap. 6) and other reactions for similar reasons.


In the third class of thermally allowed [2 + 2] cycloadditions, a very electron-rich alkene is allowed to react with a very electron-poor alkene. These reactions almost certainly proceed stepwise through a zwitterionic or diradical intermediate, so they are not pericyclic reactions, and no violation of the Woodward–Hoffmann rules occurs. [2 + 2] Cycloadditions that proceed by a stepwise mechanism are nonstereospecific.



To summarize, most [2 + 2] cycloadditions are light-promoted. The only concerted thermal [2 + 2] cycloadditions involve a ketene or other cumulene or a compound in which a heavy atom such as P or a metal is doubly bound to another element. **Common error alert:** *If neither component of a thermal [2 + 2] cycloaddition is a member of these classes, the cycloaddition must proceed by a stepwise mechanism.*

Example

Provide *two* reasons why the following mechanism for the formation of endiandric acid A is unreasonable.




Reason 1: [2 + 2] Cycloadditions do not occur under thermal conditions unless one of the components is a ketene or has a heavy atom. No light is specified in this reaction, and ambient light is not sufficient to promote a [2 + 2] cycloaddition. Reason 2: Both π bonds that participate in the purported [2 + 2] cycloaddition have trans H substituents. In the bicyclic product, though, the two

bottom H atoms of the cyclobutane are *cis*. Therefore, one of the π bonds would have to be reacting *antarafacially*, which is geometrically impossible.


The Woodward–Hoffmann rules for cycloadditions (Table 4.4) are as follows. Both components of a cycloaddition involving an odd number of electron pairs are *suprafacial* under thermal conditions; under photochemical conditions, one component must be *antarafacial*. Both components of a cycloaddition involving an even number of electron pairs are *suprafacial* under photochemical conditions; under thermal conditions, one component must be *antarafacial*.

Photochemical *suprafacial–antarafacial* reactions are very rare because the geometrically simpler thermal reaction is likely to occur instead.

Problem 4.13 What do the Woodward–Hoffmann rules suggest about the facial reactivity of the components of the following thermal [6 + 4] cycloaddition and thermal [4 + 3] cationic cycloaddition?



The application of the Woodward–Hoffmann rules to cheletropic reactions is not straightforward. In the [2 + 1] cycloaddition of singlet carbenes to alkenes, the stereochemistry of the alkene is preserved in the product, so the alkene must react *suprafacially*. The Woodward–Hoffmann rules suggest that the carbene component of this thermal, four-electron reaction must react *antarafacially*. However, what this means for a species lacking a π system is difficult to interpret.




The [4 + 1] retrocycloaddition proceeds *suprafacially* with respect to the four-atom unit, with *cis* substituents on the terminal carbons of the four-atom unit


Table 4.4 Woodward–Hoffmann rules for cycloadditions

Number of electron pairs	Δ	$h\nu$
Odd	Suprafacial–suprafacial	Suprafacial–antarafacial
Even	Suprafacial–antarafacial	Suprafacial–suprafacial

becoming *out* in the product. The one-atom component must react suprafacially, but again, what this means for a species lacking a π system is difficult to interpret.




Not all chelotropic reactions proceed suprafacially with respect to the larger component. In the following $[6 + 1]$ retrocycloaddition, the Me groups are *cis* in the starting material, but one becomes *out* in the product, and the other becomes *in*. Results such as these are difficult to rationalize or predict a priori.



4.3.4 Stereoselectivity


Consider the Diels–Alder reaction between 1-methoxybutadiene and ethyl acrylate. The major product has the MeO and CO₂Et groups on adjacent C atoms. A reaction that is stereospecific with respect to each component could give either the *cis* or the *trans* product. The TS leading to the product in which the substituents are *trans* is clearly less sterically encumbered than the other TS, and so one would predict that the *trans* product is predominantly obtained. However, the major product is the one in which the groups are *cis*.




Diels–Alder reactions generally proceed selectively via the TS in which the most powerful electron-withdrawing group on the dienophile is *endo*, i.e., sitting

underneath the diene, as opposed to pointing away from it. This phenomenon is known as the *endo* rule.

The Diels–Alder reactions of dienophiles with cyclopentadiene to give norbornenes were among the earliest studied. The fact that the *endo* norbornene (the one in which the electron-withdrawing group derived from the dienophile was *cis* to the two-carbon bridge) was always obtained was called the *endo* rule. The rule was later extended to Diels–Alder reactions not involving cyclopentadiene, and the terms *exo* and *endo* then changed their meaning.




The *out–endo*→*cis* mnemonic device allows you to draw the products of Diels–Alder reactions with stereochemistry consistent with the *endo* rule. The first word of the mnemonic refers to the orientation of a group on a terminus of the diene. The second word refers to a substituent on the dienophile (usually the most electron-withdrawing one). The third word gives the stereochemical relationship of these two groups in the product. Thus, the *out* group on the diene and the *endo* group on the dienophile are *cis* in the product. Either of the first two words can be toggled to its opposite, as long as the third word is toggled, too: *out–exo*→*trans*, *in–endo*→*trans*, and *in–exo*→*cis*. To apply the *out–endo*→*cis* mnemonic, you must determine which group on the dienophile is the *endo* group. Application of the *out–endo*→*cis* mnemonic then gives the stereochemistry of the major product.




Example

Predict the stereochemistry of the major product of the following Diels–Alder reaction.




First redraw the starting material and product so that they are in the proper conformation (*s-cis* for the diene) and mutual orientation. Orient the two so that

the strongest electron-donating group on the diene is in a 1,2- or 1,4-relationship with the strongest electron-withdrawing group on the dienophile. Then draw the product with no stereochemistry indicated.




Stereochemistry: The most electron-withdrawing group on the dienophile is *endo*, and the *out-endo*→*cis* mnemonic tells you that the OAc and CN groups are *cis* in the product. The *suprafacial-suprafacial* nature of the Diels-Alder reaction tells you that the two *out* groups on the diene become *cis*, and that the stereochemistry of the dienophile is preserved in the product, so the OAc group (*out*) and the Me group opposite it (*in*) are *trans* in the product, and the CN group and the Me group next to it are also *trans* in the product. Draw the OAc up (or down, it doesn't matter), and the rest of the stereochemistry follows.



Common error alert: *Be certain to preserve the stereochemistry about all three π bonds.* When a diene is drawn in its *s-trans* conformation, as in the preceding example, students often inadvertently isomerize the π bonds when they try to redraw it in its *s-cis* conformation. A correct application of the *out-endo*→*cis* mnemonic then leads to an incorrect answer. Following Grossman's rule can help prevent this common error.


The *endo* rule applies equally to inverse electron-demand Diels-Alder reactions. In these reactions, the most electron-donating group on the dienophile is preferentially *endo*. The *out-endo*→*cis* rule applies, too.




The *endo/exo* ratio in any particular reaction can vary a lot depending on reaction conditions and the substrates. The ratio increases in favor of the *endo* product when Lewis acids are used to accelerate the Diels-Alder reaction. Increased

steric interactions can turn the tide in favor of the exo product. In intramolecular Diels–Alder reactions, the ratio depends more on conformational preferences than anything else, and either exo or endo products may be obtained predominantly, depending on the reaction conditions and the particular substrate.


Why is the endo TS lower in energy than the exo TS? The most widely accepted explanation cites *secondary orbital interactions*. In the more crowded approach, the orbitals of the carbonyl group of the dienophile can interact with the orbital on C2 of the diene. The secondary orbital interactions in the endo TS are energetically favorable, so the kinetic product is the more crowded, less thermodynamically stable endo product.



The preference for the endo TS can also be rationalized by invoking effects other than secondary orbital interactions. For example, the dipoles associated with the in C–H bond of the diene and the electron-withdrawing group of the dienophile interact most favorably when the electron-withdrawing group is endo. Lewis acids increase the endo selectivity by polarizing the electron-withdrawing group and thus increasing the magnitude of the dipole. The endo selectivities of Diels–Alder reactions of certain substrates can also be explained by steric and solvent effects.




endo TS: dipoles aligned favorably




exo TS: dipoles aligned unfavorably


Endo selectivity is a kinetic phenomenon. If an equilibrium is established between the higher energy endo and lower energy exo products, then predominantly exo products will be seen. The cycloaddition of maleic anhydride and furan proceeds very rapidly, even at very low temperatures, to give only the exo product. The unusually low energy of furan (an aromatic compound) allows the retro-Diels–Alder reaction of the endo product to proceed at a reasonable rate. Even though the rate of formation of the endo product is faster than the rate of formation of the exo product, establishment of an equilibrium between starting materials and products leads to a thermodynamic ratio that favors the exo product.




1,3-Dipolar cycloadditions give predominantly *endo* products, too. The out-*endo*→*cis* mnemonic applies.




[2 + 2] Photocycloadditions also proceed to give predominantly *endo* products. For example, the light-induced dimerization of thymidine occurs with *endo* selectivity. The carbonyl group of one ring positions itself over the other ring, and the more sterically crowded stereoisomer is obtained.



In the [2 + 2] cycloaddition of monosubstituted ketenes to cycloalkenes, two products can also be obtained. The thermodynamic product, where the R group is on the convex face of the bicyclic system, is *not* obtained predominantly. In fact, the reaction is “masochistic”: the larger the R group, the greater the proportion of the higher energy product.



Because the ketene must react antarafacially, the alkene approaches the ketene with the two π bonds nearly perpendicular to each other. The smaller portion of the ketene, the C=O group, sits under the ring of the alkene, while the larger portion, the CHR group, resides farther away. The H and R groups may be oriented with respect to the alkene in two ways. In the lower energy orientation, the H substituent on the ketene points up toward the alkene, while the larger R group points down. The antarafacial reactivity of the ketene causes this lower energy orientation to lead to the higher energy product, in which the R group is on the *concave* face of the bicyclic system. The larger the R group, the lower the relative energy of the TS that has the R group pointing away from the cycloalkene, and the greater the proportion of higher energy product.




4.4 Sigmatropic Rearrangements


4.4.1 Typical Reactions

A sigmatropic rearrangement produces a new σ bond at the expense of a σ bond, so this reaction is the most inherently reversible of all pericyclic reactions. The position of the equilibrium depends on the relative thermodynamic and kinetic stabilities of the starting material and products. Most synthetically useful sigmatropic rearrangements are two- or six-electron processes.


The [3,3] sigmatropic rearrangements (Cope and Claisen rearrangements) are the most widely used sigmatropic rearrangements and are probably the most widely used pericyclic reactions after the Diels–Alder and 1,3-dipolar cycloadditions. In the Cope rearrangement, a 1,5-diene isomerizes to another 1,5-diene. In the Claisen rearrangement, an allyl vinyl ether (a 1,5-diene in which the third or fourth C atom is replaced with O) isomerizes to a γ,δ -unsaturated carbonyl compound (another 1,5-diene in which the first or sixth C atom is replaced with O). Both the Cope and Claisen rearrangements normally require temperatures of 150 °C or greater to proceed, although certain types of substitution can lower the activation barrier.




The Cope rearrangement of the simplest 1,5-diene, 1,5-hexadiene, is degenerate: the starting material is identical with the product, and the equilibrium constant for the rearrangement is 1. Substituents may shift the equilibrium to one side or the other. For example, the equilibrium between 3,4-dimethyl-1,5-hexadiene and 2,6-octadiene lies on the side of the more substituted π bonds.




The position of the equilibrium of the Cope rearrangement is pushed even further toward one side when cleavage of the σ bond relieves ring strain. The relief of ring strain also lowers the activation barrier for the rearrangement. Thus, *cis*-1,2-divinylcyclopropane is stable only at very low temperatures.




The position of the Cope equilibrium can also be altered by removing the product 1,5-diene from the reaction mixture. In the *oxy-Cope rearrangement*, a 3-hydroxy-1,5-diene undergoes the Cope rearrangement to give an enol, which isomerizes quickly to a δ,ϵ -unsaturated carbonyl compound. The latter compound is a 1,6-diene, not a 1,5-diene, so it is incapable of undergoing the Cope rearrangement in the retro direction. The reverse isomerization of the δ,ϵ -unsaturated carbonyl compound to the enol does not occur quickly enough for the retro-Cope rearrangement to proceed.



Oxy-Cope rearrangements proceed at especially low temperatures when the alcohol is deprotonated. The *anionic oxy-Cope rearrangement* is accelerated compared with the neutral reaction because the negative charge is more delocalized in the TS than in the starting material. The driving force for the anionic oxy-Cope rearrangement is no longer removal of the product diene from the equilibrium but simply delocalization of the negative charge. The starting alcohol is usually deprotonated by KH because the O–K bond is much weaker than the O–Na or O–Li bond; the crown ether 18-crown-6 is often added to isolate the K^+ counterion from the alkoxide even further.




In general, Claisen rearrangements are driven in the forward direction by the formation of a C=O π bond at the expense of a C=C π bond, but there are exceptions to this general rule. For example, the first Claisen rearrangement to be discovered was the isomerization of an *O*-allylphenol to a 2-allylphenol. One might expect that in this particular case, the equilibrium would lie on the side of the aromatic compound, not the 2,4-cyclohexadienone. However, the cyclohexadienone quickly tautomerizes (by a nonconcerted mechanism!) to the aromatic 2-allylphenol, which cannot undergo the reaction in the reverse direction.




The key to identifying Cope and Claisen rearrangements is the 1,5-diene in the starting material or in the product. A γ,δ -unsaturated carbonyl compound (a 1,5-heterodiene) can be made by a Claisen rearrangement, and a δ,ϵ -unsaturated carbonyl compound can be made by an oxy-Cope rearrangement.

Example


The orthoester Claisen rearrangement.




Label the atoms and draw the coproducts.




Make: C1–C5, O4–C6. Break: C3–O4, C6–O8, C6–O9. The product has a 1,5-disposition of two π bonds, C2=C3 and O4=C6. Working retrosynthetically, the C1–C5 bond can be made and the C3–O4 bond broken by a [3,3] sigmatropic (Claisen) rearrangement of a 1,5-diene precursor.




The immediate precursor to the product can be made from the alcohol and the orthoester by S_N1 substitution followed by E1 elimination.



[3,3] Sigmatropic rearrangements are rather rare in biology, but one notable example is the Claisen rearrangement of chorismate to prephenate, a key step in the biosynthesis of aromatic amino acids such as tyrosine. The enzyme chorismate mutase catalyzes this reaction by inducing chorismate to assume the conformation that is most favorable for the rearrangement to occur.




The [1,5] sigmatropic rearrangement of H atoms around a cyclopentadienyl group is an extremely facile process because the ends of the pentadienyl system are held closely to one another. The different isomers of a substituted cyclopentadiene are in rapid equilibrium (on the laboratory time scale) above 0°C . A synthesis of prostaglandins was developed in the late 1960s in which the first two steps were (1) alkylation of cyclopentadiene with benzyloxymethyl bromide to give a 5-substituted cyclopentadiene, and (2) a Diels–Alder reaction. A dienophile that would react with the cyclopentadiene below -20°C was sought, because at higher temperature the cyclopentadiene isomerized into its more stable 1- and 2-substituted isomers.




The [1,5] *alkyl* shift is also seen in cyclopentadienes, but much higher temperatures (usually $>200\text{ }^{\circ}\text{C}$) are required. The $\text{C}(sp^3)$ orbital is much more directional than the $\text{H}(s)$ orbital, so the simultaneous overlap with two orbitals that is required in the TS is not as facile as it is with H.


Problem 4.14 The following reaction involves [1,5] sigmatropic rearrangements. Draw a reasonable mechanism. Remember to obey Grossman's rule!




The [2,3] sigmatropic rearrangement involves the rearrangement of a 1,2-dipole to a neutral compound. An allyl group migrates from the positive end to the negative end of the dipole to neutralize the charges.




Amine oxides, sulfoxides, and selenoxides all undergo the [2,3] sigmatropic rearrangement. The equilibrium between allyl sulfoxides and allyl sulfenates lies on the side of the sulfoxide, but the equilibrium can be pushed toward the sulfenate by reduction of its O–S bond.




Allylsulfonium ylides (allyl $\text{SR}^+ - \text{CR}_2^-$) and allylammonium ylides (allyl $\text{NR}_2^+ - \text{CR}_2^-$) are also substrates for the [2,3] sigmatropic rearrangement. Both ylides are usually generated in situ by deprotonation of the sulfonium or ammonium salt.




Problem 4.15 Draw a mechanism for the following [2,3] sigmatropic rearrangement. Why does this particular reaction proceed under such mildly basic conditions?



The [2,3] sigmatropic rearrangement of allyloxycarbanions is known as the *Wittig rearrangement* (not to be confused with the Wittig reaction). The requisite carbanions can be prepared by transmetalation of a stannane (tin compound). Stannanes, unlike organolithium compounds, are stable, isolable, chromatographable compounds, but they are easily converted to the organolithium compound with BuLi.




Allyl propargyl ethers also are good substrates for the Wittig rearrangement. Deprotonation of the propargyl position is relatively facile.



The key to identifying a [2,3] sigmatropic rearrangement is that an allylic group migrates from a heteroatom to an adjacent atom (which may be C or another heteroatom).


Problem 4.16 Upon mixing an *N*-chloroaniline and an α -mercaptoester, a nucleophilic substitution occurs, followed by a [2,3] sigmatropic rearrangement. An ortho-alkylated aniline is ultimately obtained. Draw the mechanism for this reaction.



Four-electron, [1,3] sigmatropic rearrangements are very rare. Occasionally an alkyl group can undergo a concerted 1,3-shift, but H atoms *never* undergo concerted [1,3] sigmatropic rearrangements. **Common error alert:** *The tautomerization of an enol to a carbonyl compound appears to be a [1,3] sigmatropic rearrangement at first glance, but the reaction is catalyzed by base or acid and never proceeds by a concerted pericyclic mechanism.* These observations will be rationalized in the next section.



The [1,7] sigmatropic rearrangement, an eight-electron process, is also quite rare. A 1,3,5-hexatriene can undergo a six-electron electrocyclic ring closure more rapidly and with greater release of energy than it can a [1,7] sigmatropic rearrangement. However, a very important [1,7] sigmatropic rearrangement occurs in the human body. Precalciferol (provitamin D_2) (which you may remember is made by a conrotatory electrocyclic ring opening of ergosterol) is converted to ergocalciferol (vitamin D_2) by a [1,7] sigmatropic H shift.




All the sigmatropic rearrangements discussed so far occur under thermal conditions. Photochemical sigmatropic rearrangements are extremely rare.


4.4.2 Stereospecificity

In a sigmatropic rearrangement, bonds are made and broken at the ends of two conjugated systems. The Woodward–Hoffmann rules for sigmatropic rearrangements must take both components into account.

The most common sigmatropic rearrangements are [1,2] cationic, [1,5], and [3,3] rearrangements. These rearrangements proceed readily under thermal conditions. In the cationic [1,2] hydride shift, a thermal reaction, the MOs of two components must be examined. The one-atom component, the H atom, has one orbital, the $1s$ orbital. The two-atom component has two orbitals, ψ_0 and ψ_1 . Two electrons must be distributed among these three orbitals. It is clear that the $H(1s)$ orbital is lower in energy than the antibonding orbital ψ_1 , but it is not clear whether $H(1s)$ or ψ_1 is lower in energy. If $H(1s)$ is lower in energy, the two electrons will both go in $H(1s)$; if ψ_0 is lower in energy, they will both go in ψ_0 ; and if the two MOs are equal in energy, one electron may go in each. Nevertheless, no matter how the two electrons are distributed among the two components, *the dominant HOMO-LUMO interaction in the TS is between the symmetric $1s$ orbital of the one-atom component and the symmetric ψ_0 of the two-atom component*. The H atom is always classified as a suprafacial component, as the $1s$ orbital is monophasic, so positive overlap in the TS between orbitals where bond-making and bond-breaking take place is produced when the two-atom component is suprafacial as well.




Likewise, in the cationic [1,2] alkyl shift, both components must be suprafacial for there to be positive overlap in the TS between orbitals where bond-making and bond-breaking take place. The migrating group retains its configuration because of the requirement for suprafaciality.




The dominant FMO interaction in the TS of the [1,5] sigmatropic rearrangement, a six-electron reaction, is between the $H(1s)$ orbital and the symmetric ψ_2 of the five-atom component, no matter how the six electrons are divided among the two


components. (An interaction between two half-filled orbitals is shown.) Again, positive overlap in the TS between orbitals where bond-making and bond-breaking take place is obtained when the five-atom component reacts suprafacially.




The [3,3] sigmatropic rearrangement is a six-electron reaction. No matter how the six electrons are distributed among the two three-atom components, the dominant FMO interaction in the TS is between the antisymmetric ψ_1 of one component and the antisymmetric ψ_1 of the other component. The reaction proceeds suprafacially with respect to both components.




Likewise, the dominant FMO interaction in the TS of the [2,3] sigmatropic rearrangement is between the antisymmetric ψ_1 orbitals of both components. The reaction proceeds suprafacially with respect to both components.




By contrast, in the [1,2] anionic H shift, the dominant FMO interaction is between the symmetric $1s$ orbital of the one-atom component and the antisymmetric ψ_1 of the two-atom component. For there to be a positive overlap between orbitals where bond-making and bond-breaking take place, the two-atom component must react antarafacially. Thus, for this shift to be a thermally allowed process, the H atom must have partial bonds to the top and bottom faces of the C_2 unit simultaneously. Because this arrangement is geometrically impossible, [1,2] anionic H shifts are thermally disallowed reactions.




A thermally allowed anionic [1,2] shift can occur if the one-atom component reacts antarafacially. In the case of the alkyl shift, the $C(p)$ orbital of the migrating R group can react antarafacially, with the configuration inverting upon migration. In practice, the geometric requirements for anionic [1,2] alkyl shifts are so stringent that the reactions are extremely rare.



Thermal [1,3] H shifts such as the *concerted* rearrangement of enols to carbonyl compounds are disallowed. The allylic C–C–O unit itself can only react suprafacially, as it is geometrically impossible for the $H(1s)$ orbital to bond simultaneously to a top lobe on one terminus and a bottom lobe at the other terminus, and the H atom itself must also react suprafacially, as the $H(1s)$ orbital has only one lobe. The Woodward–Hoffmann rules, though, say that one of the two components of this four-electron rearrangement must react antarafacially for it to be allowed. Therefore, this rearrangement reaction always proceeds through a nonconcerted mechanism and requires acidic or basic catalysis. **Common error alert:** A mechanism involving a concerted [1,3] sigmatropic rearrangement of H is almost always incorrect.




On the other hand, a thermal [1,3] alkyl shift is allowed because the alkyl group can adopt an antarafacial orientation in the TS. The two lobes of the $C(p)$ orbital of the migrating atom bond to opposite ends of the allylic system in the TS, and the configuration of the migrating group inverts.




Because the [1,3] sigmatropic rearrangement of alkyl groups has such stringent geometric requirements, it is quite rare. Only a handful of examples of [1,3] sigmatropic rearrangements are known. In one such example, the configuration of the migrating C inverts, demonstrating its antarafacial reactivity in the rearrangement.


Common error alert: A mechanism involving a [1,3] sigmatropic rearrangement of an alkyl group, though not impossible, should be viewed with suspicion.



A thermal [1,3] sigmatropic rearrangement is allowed only if one component is antarafacial, but a photochemical [1,3] sigmatropic rearrangement is expected to be allowed when it proceeds suprafacially with respect to both components. The stereochemical requirement changes because under photochemical conditions, the HOMO of the three-atom component is ψ_2 (symmetric), not ψ_1 (antisymmetric).




Photochemical sigmatropic rearrangements are rare, but in one example, a photochemical [1,3] sigmatropic rearrangement proceeds suprafacially with respect to both components, resulting in retention of configuration about the migrating one-atom component, a stereogenic alkyl group. The reaction fails to proceed at all under thermal conditions.



A thermal, concerted [1,7] H shift is sometimes observed in acyclic systems, because the 1,3,5-triene system is floppy enough to allow the H to migrate from the top face to the bottom face (making the triene the antarafacial component). The

precalciferol–calciferol rearrangement is thermally allowed for this reason. (However, because precalciferol is formed in its excited state, it is quite possible that it undergoes a *photochemical* [1,7] sigmatropic rearrangement that is suprafacial with respect to both components.) In cyclic compounds like cycloheptatriene, though, geometric constraints prevent the H from migrating from the top to the bottom face of the C_7 π system, and the shift does not occur.



In summary, the Woodward–Hoffmann rules for sigmatropic rearrangements (Table 4.5) are as follows. Both components of a sigmatropic rearrangement involving an odd number of electron pairs are suprafacial under thermal conditions; under photochemical conditions, one component must be antarafacial. Both components of a sigmatropic rearrangement involving an even number of electron pairs are suprafacial under photochemical conditions; under thermal conditions, one component must be antarafacial.

The stereochemical consequences of facial selectivity are manifested most clearly in [3,3] sigmatropic rearrangements. Consider the orthoester Claisen rearrangement, in which an allylic alcohol is converted into a γ,δ -unsaturated ester. The intermediate ketene acetal undergoes a [3,3] sigmatropic rearrangement that is suprafacial with respect to both three-atom components, so the new bond between C1 and C6 and the old bond between C3 and C4 must both be to the same face of the C4–C5–C6 component. In practice, this means that because the C3–C4 bond in the starting material comes out of the plane of the paper or screen, the C1–C6 bond in the product also comes out of the plane of the paper or screen. The same argument holds for [2,3] sigmatropic rearrangements.





Table 4.5 Woodward–Hoffmann rules for sigmatropic rearrangements

Number of electron pairs	Δ	$h\nu$
Odd	Suprafacial–suprafacial	Suprafacial–antarafacial
Even	Suprafacial–antarafacial	Suprafacial–suprafacial


Problem 4.17 A small amount of 4-allylphenol is often obtained from the Claisen rearrangement of allyl phenyl ether. Draw a concerted mechanism for this reaction, name the mechanism, and determine whether the suprafacial–suprafacial rearrangement is thermally allowed or disallowed by the Woodward–Hoffmann rules. If it is not allowed, draw a multistep mechanism for the reaction.

Problem 4.18 Examples of the Stevens rearrangement and the nonallylic Wittig rearrangement are shown. What do the Woodward–Hoffmann rules say about the nature of these reactions? Offer two *explanations* (not necessarily mechanisms) of why these reactions proceed. (*Hint*: Think of the conditions on the applicability of the Woodward–Hoffmann rules.)




4.4.3 Stereoselectivity

Cope rearrangements must be suprafacial with respect to both components, but multiple stereochemical results are still possible. Cope rearrangements have a six-membered ring in the TS. The ring can be in any of four conformations (two chair and two boat). These different conformers can lead to different stereoisomeric products. Consider the following possible conformations of the disubstituted compound. Cope rearrangement via one chair conformation leads to a product in which the Ph-substituted π bond is *cis* and the CH_3 -substituted π bond is *trans*. Rearrangement via the other chair conformation leads to a product in which the CH_3 -substituted π bond is *cis* and the Ph-substituted π bond is *trans*. Rearrangement of the *same* compound via one boat conformation leads to a product in which both π bonds are *trans*. Rearrangement via the other boat conformation leads to a product in which both π bonds are *cis*. In other words, all four stereochemistries about the $\text{C}=\text{C}$ bonds can be obtained from a single diastereomeric starting material. I must emphasize that all four possible stereochemistries are consistent with a suprafacial arrangement of both components in the TS.




Of course, one of the four possible TSs is usually quite a bit lower in energy than the others, and this leads to *stereoselectivity* in the Cope rearrangement. The chair TSs are preferred to the boat TSs, just as they are in cyclohexanes, and chair TS 2, in which the large Ph group is pseudoequatorial and the smaller Me is pseudoaxial, is lower in energy than chair TS 1, in which Ph is pseudoaxial and Me is pseudoequatorial. However, certain substitution patterns can cause one of the boat TSs to be lower in energy. For example, if the Me and Ph groups were replaced with *t*-Bu groups, which are much too large ever to be pseudoaxial, then boat TS 1 would be preferred.

Most Cope rearrangements, especially those of simple 1,5-dienes, proceed through a chair TS, and the stereochemical consequences are easily analyzed. For example, the following (*S,E*) allylic alcohol undergoes an orthoester Claisen rearrangement to give mostly the (*R,E*) product; the alternative chair TS, which leads to the (*R,Z*) product, has a pseudoaxial BnOCH_2 group and so is higher in energy.




Example

Draw the product of the following oxy-Cope rearrangement (an aldehyde) with the correct stereochemistry.



The first step is to draw the starting material in the proper conformation for the rearrangement, *without altering its stereochemistry*. The starting material is drawn in the figure such that the C2–C3 and C4–C5 bonds are in the *s-trans* conformation (antiperiplanar). Redraw the compound so that these two bonds are *s-cis* (eclipsed). After the rotation, the Ph group, formerly up, will now be down. Then rotate about the C2–C3 and C4–C5 bonds so that C1 and C6 are near one another, being careful to preserve the double bond geometries. Finally, rotate the entire structure so that the C3–C4 bond is vertical. You now have a *top view* of your starting material.




Now you need to draw the compound in its chair conformation. Draw a chair with only five sides, and then draw the two double bonds at the ends of the chain.

The easiest way to draw a five-sided chair is as follows. Draw a shallow V, draw an upside-down V of the same size below and to the left of the first V, and connect the ends of the two Vs on one side.




Although the termini of the 1,5-diene are sp^2 -hybridized, their two substituents occupy pseudoaxial and pseudoequatorial positions. Draw the substituents of the double bonds in your chair, again being careful to preserve the double bond geometry. Note that the upper double bond in your *top view* drawing is now in the back of the chair, and the lower double bond is now in the front. Finally, draw the four bonds (two axial and two equatorial) to the C(sp^3)




centers of your chair, and then fill in the substituents, being careful that the “down” substituents point down and the “up” substituents point up. You have now drawn your compound in a correct chair conformation.

OOPS! The chair conformation you have drawn has the largest $C(sp^3)$ substituent, the Ph group, in an axial orientation! This means that you have not drawn the lowest energy chair conformation. The easiest solution to this problem is to switch the configurations of both $C(sp^3)$ centers so that you have the wrong enantiomer (but still the right diastereomer), draw the rearrangement reaction, and then switch the configurations of both $C(sp^3)$ centers in the product back to the correct enantiomeric series to give you the product.




A more rigorous way of dealing with the problem is to flip the chair. When you flip the chair, all the axial substituents at $C(sp^3)$ centers become equatorial, and vice versa. Be careful to preserve the stereochemistry about the double bonds: the pseudoaxial and pseudoequatorial substituents of the double bonds retain their orientation in the flipped chair!




Of course, if your original chair has the largest $C(sp^3)$ substituent in the correct, equatorial position, you don't need to worry about switching configurations or flipping the chair.

Problem 4.19 A mechanism involving a [3,3] sigmatropic rearrangement (an aza-Cope rearrangement) followed by a Mannich reaction can be drawn for the following reaction. Draw the mechanism. Then predict the stereochemistry of the product obtained when the aza-Cope rearrangement proceeds through a chair conformation.




Not every Cope or Claisen rearrangement can proceed through a chair TS. Sometimes the chair TS is raised prohibitively high in energy compared with the boat TS. For example, *cis*-1,2-divinylcyclopropane undergoes a Cope rearrangement to give 1,4-cycloheptadiene. If the starting material underwent rearrangement through the chair TS, one of the π bonds in the seven-membered ring in the product would be *trans*, so the reaction proceeds through the boat TS.




For any 1,5-diene other than a simple, acyclic one, molecular models are usually necessary to determine whether the Cope or Claisen rearrangement will proceed through a chair or a boat TS.

Cope and Claisen rearrangements are not the only sigmatropic rearrangements that show stereoselectivity. For example, consider the [1,5] sigmatropic rearrangement of the following diene. It has the *S* configuration about the stereocenter and the *E* configuration about the double bond distal to the stereocenter. Because the reaction is suprafacial with respect to the five-atom component, the H can move from the top face at one terminus to the top face at the other, or it can move from the bottom face at one terminus to the bottom face at the other. In the first case, the (*E*, *S*) product is obtained; in the second case, the (*Z*, *R*) product is obtained. The (*E*, *S*) product would probably be obtained selectively, as it has the large Ph group in the thermodynamically preferred position. Neither the (*E*, *R*) product nor the (*Z*, *S*) product is obtained because of the stereospecific nature of the rearrangement.




A similar argument can be made for the [1,7] sigmatropic rearrangement. The (*S*, *E*) starting material rearranges antarafacially with respect to the seven-atom component. The H can move from the bottom face at one terminus to the top face at the other, or it can move from the top face at one terminus to the bottom face at the

other. Either the (*E,R*) or the (*Z,S*) product, but neither the (*E,S*) nor the (*Z,R*) product, is obtained.




4.5 Ene Reactions


The ene reaction shares some characteristics with both the Diels–Alder reaction and the [1,5] sigmatropic rearrangement. The ene reaction is always a six-electron reaction. Like the Diels–Alder reaction, it has one four-electron component, the *ene*, and one two-electron component, the *enophile*. The two-electron component is a π bond. The four-electron component consists of a π bond and an allylic σ bond. The atom at the terminus of the σ bond is usually H; the other five atoms involved in the ene reaction may be C or heteroatoms. Because the ene reaction involves six electrons, it is suprafacial with respect to all components.




The suprafacial reactivity of the enophile means that the two new bonds to the enophile form to the same face. When the enophile is an alkyne, the two new σ bonds in the product are *cis* to one another.




Ene reactions involving five C atoms and one H usually require very high temperatures ($>200\text{ }^\circ\text{C}$) to proceed. The reaction occurs at much lower temperature if the H atom is replaced with a metal atom in the *metallaene* reaction. The metal may be Mg, Pd, or another metal.




Note how the *cis* product is obtained in the metallaene reaction. This stereochemical result reflects the preference of this particular substrate for an *endo* transition state, just as in cycloadditions. In cycloadditions, though, the *endo* substituent of the dienophile is usually an electron-withdrawing substituent, whereas in this ene reaction the *endo* substituent of the enophile is simply the alkyl chain joining it to the ene.




The ene reaction also occurs when heteroatoms replace C in either the ene or the enophile. The following heteroene reaction requires a much lower activation energy than normal because of the driving force of formation of the aromatic indole ring and because of the instability of ethyl glyoxylate, which has adjacent carbonyl groups.




Ene reactions with enols as the ene component are driven in the forward direction by the favorable energy derived from the regeneration of the carbonyl group, just like in the oxy-Cope rearrangement. Very high temperatures may be required to generate a sufficiently high concentration of enol to make the reaction proceed.




Selenium dioxide (SeO_2) is often used to hydroxylate alkenes in the allylic position. The mechanism of this transformation involves two sequential pericyclic reactions. The first reaction, an ene reaction, gives a selenenic acid. Then a [2,3] sigmatropic rearrangement occurs, and the intermediate loses SeO to give the observed product. Note how two allylic transpositions result in no allylic transposition at all!



A number of synthetically useful elimination reactions proceed thermally, with no base or acid required. These elimination reactions proceed through a concerted *retroene* mechanism. (The mechanism is sometimes called E_i .) The thermal elimination of acetic acid from alkyl acetates and the elimination of RSCOSH from alkyl xanthates (the *Chugaev reaction*) are retroene reactions.




Retroene reactions are partly driven by the gain in entropy. (Entropic contributions to ΔG° are much more important at the high temperatures required for ene reactions.) The formation of the $\text{C}=\text{O}$ π bond at the expense of the $\text{C}=\text{S}$ π bond provides an additional driving force for the Chugaev reaction. Acetic acid elimination is enthalpically unfavorable, and it requires much higher temperatures so that the entropic contribution becomes dominant. The formation of the $\text{C}=\text{O}$ π bond and entropic gains also provide the driving force for the elimination of methyl formate from the following allylic MOM (methoxymethyl) ether.




Selenoxide elimination, a *retroheteroene* reaction, is widely used for the oxidation of carbonyl compounds to the α,β -unsaturated analogs. An α -selenocarbonyl compound is oxidized to the selenoxide with one of a variety of oxidizing agents (H_2O_2 , mCPBA, NaIO_4 , O_3 , etc.). The retroheteroene reaction of the selenoxide is so facile that it occurs at room temperature within minutes. Amine oxides (*Cope elimination*, not to be confused with the Cope rearrangement) and sulfoxides also undergo the retroheteroene reaction, but they require higher temperatures. Retroheteroene

reactions are driven by entropy, by charge neutralization, and sometimes by cleavage of a weak σ bond (e.g., C–Se) in favor of a C=C π bond. All retroheteroene reactions involve a 1,2-dipole, usually $\bar{E}-\bar{O}$, where E is a heteroatom.




The factors that make ene and retroene reactions proceed are nicely illustrated by a synthesis of enantiopure, isotopically labeled acetic acid $\text{CH}(\text{D})(\text{T})\text{CO}_2\text{H}$, a very useful compound for studying the mechanisms of enzyme-catalyzed reactions. One ene and one retroene reaction occur in this synthesis. The ene reaction is driven by formation of a new σ bond at the expense of a $\text{C}\equiv\text{C}$ π bond; the retroene reaction is driven by the formation of a $\text{C}=\text{O}$ π bond in an ester. Note that both pericyclic reactions proceed stereospecifically, even at the very high temperatures required for them to proceed!



Ene reactions make one new σ bond at the expense of one π bond, like electrocyclic reactions, but they are fairly easy to distinguish from electrocyclic reactions otherwise. Look for allylic transposition of a double bond and transfer of an allylic H atom. In a retroene reaction, a nonallylic H is transferred to an allylic position.

Problem 4.20 The final step of the Swern oxidation involves elimination of Me_2S and H^+ from a sulfonio ether. An E2 mechanism for this elimination is reasonable, but a retroheteroene mechanism is actually operative. Draw the retroheteroene mechanism.



4.6 Summary

The Woodward–Hoffmann rules for all pericyclic reactions (Table 4.6) are as follows. A pericyclic reaction involving an odd number of electron pairs must have an even number of antarafacial components under thermal conditions and an odd number of antarafacial components under photochemical conditions. A pericyclic reaction involving an even number of electron pairs must have an odd number of antarafacial components under thermal conditions and an even number of antarafacial components under photochemical conditions. In practice, of course, “even number of antarafacial components” means “none”, and “odd number of antarafacial components” means “one”.

Pericyclic mechanisms are undoubtedly the hardest for students to draw. The superficial similarity of the mechanistic types, the way in which seemingly reasonable steps are disallowed by theoretical considerations, the simultaneous formation of many bonds, the lack of a clearly reactive center—all these features of pericyclic reactions combine to make them anathema to many students. You can learn some useful techniques to help you work through pericyclic mechanism problems. Some of these techniques have already been mentioned in the course of the discussion, but they are reiterated here for emphasis.

General considerations when drawing pericyclic mechanisms:

- Draw dashed lines between the atoms where you are forming new bonds, and draw squiggles across bonds that break. Sometimes this procedure will help you identify the pericyclic reaction you need to draw.
- In many problems, a series of polar reactions proceeds to give a reactive intermediate that then undergoes a pericyclic reaction to give the product. Look at the product, and determine what pericyclic reaction could generate it. Then draw the immediate precursor to the final product. Don't be shy about drawing electron-flow arrows on the product to help you draw the precursor with all its bonds in the correct positions. This procedure often simplifies the problem considerably.
- **Common error alert:** *Students often draw fictional pericyclic steps such as $A-B + C=D \rightarrow A-C-D-B$.* A good preventive is to be sure that you can name any reactions that occur. If you cannot name it, it ain't a reaction!
- As always, draw your coproducts, label your atoms, make a list of bonds to make and break, and obey Grossman's rule!

Table 4.6 Woodward–Hoffmann rules for all pericyclic reactions

Number of electron pairs	Number of antarafacial components	
	Δ	$h\nu$
Odd	Even	Odd
Even	Odd	Even

Whether working forward or backward, look for some key substructures.


- The presence of a 1,3-butadiene or a cyclobutene in the starting material or the product may indicate a four-electron electrocyclic reaction.
- The presence of a 1,3-cyclohexadiene or a 1,3,5-hexatriene in the starting material or the product may indicate a six-electron electrocyclic reaction.
- Cyclopropyl cations and allylic cations can open and close, respectively, by two-electron electrocyclic reactions, as can the corresponding halides.
- A six-membered ring with two new σ bonds in a 1,3-relationship may indicate a [4 + 2] cycloaddition (Diels–Alder or hetero-Diels–Alder reaction). When the new ring is fused to an aromatic one, benzyne or an *o*-xylylene may have been a reactive intermediate.
- The formation of a five-membered heterocycle with two new σ bonds almost always indicates a [3 + 2] cycloaddition.
- The formation of a cyclobutanone almost always indicates a ketene–alkene [2 + 2] cycloaddition.
- Light and a cyclobutane often indicate a [2 + 2] cycloaddition. **Common error alert:** *A cyclobutane that lacks a ketone and that is produced in the absence of light is likely not formed by a [2 + 2] cycloaddition.*
- Loss of CO₂, N₂, CO, or SO₂ by cleavage of two σ bonds often indicates a retro [4 + 2] or [4 + 1] cycloaddition.
- A 1,5-diene, including a γ,δ -unsaturated carbonyl compound, often indicates a [3,3] sigmatropic rearrangement, i.e., a Cope or Claisen rearrangement.
- A δ,ε -unsaturated carbonyl compound is often the product of an oxy-Cope rearrangement. Oxy-Cope rearrangements are accelerated under strongly basic conditions (KH with or without 18-crown-6).
- The H atoms of cyclopentadienes undergo [1,5] sigmatropic rearrangements with great facility.
- Migration of an allylic group from a heteroatom to its next-door neighbor often indicates a [2,3] sigmatropic rearrangement.
- The formation of a new σ bond at the ends of two π bonds and the simultaneous migration of a H atom may indicate an ene reaction.
- The elimination of an acid such as AcOH or PhSeOH may indicate a retroene or retroheteroene reaction.
- A requirement of light (*h* ν) suggests that either an electrocyclic reaction (usually a ring closing), an even-electron-pair cycloaddition (e.g., a [2 + 2] cycloaddition), or a free-radical reaction has occurred.

Good luck!


4.7 Problems

1. Determine the number of electrons involved in each of the following reactions, name the reaction's mechanism as specifically as possible, and predict whether the reaction proceeds thermally or photochemically.


(a)




(b)




(c)




(d)




(e)




(f)




(g)




(h)




(i)




(j)









(k)






2. Predict the major product (regio- and stereoisomer) of each of the following cycloadditions. All reactions but (h) are [4 + 2] or [3 + 2] cycloadditions.










(h) The dots mark the locations where the polyene reacts.




- 1,3,5,7-Cyclononatetraene can theoretically undergo four different electrocyclic ring closures. Draw the product of each of these reactions, determine the stereochemistry of each when it is obtained under thermal conditions, and order the products by thermodynamic stability.
- Draw the product of each of the following [3,3] sigmatropic rearrangements, including its stereochemistry. In some cases, you may find it necessary to build molecular models in order to see the stereochemical result.




(e)





(f)



(g)




(h)




5. When ketenes react with 1,3-dienes, bicyclic cyclobutanones are obtained. The mechanism of this reaction is usually described as a one-step [2 + 2] cycloaddition reaction, but the following two-step mechanism has been proposed.

- Name the two steps of the proposed mechanism.
- Explain why the C=O and not the C=C bond of the ketene reacts with the 1,3-diene in the first step of the proposed mechanism.
- When an unsymmetrically substituted ketene $[(R_L)(R_S)C=C=O]$ is used in this reaction, the larger group (R_L) is found in the more sterically hindered endo position in the *ultimate* product (“chemical masochism”), as shown here. Use the proposed mechanism to explain (in words *and* pictures) this phenomenon. You will need to look at the stereochemical result of *both* steps of the mechanism.




6. Draw mechanisms for the following reactions.


(a)




(b)




(c)




(d)




(e)




(f)




(g)




(h)




(i)




(j) Make an analogy between acyl chlorides and sulfonyl chlorides to solve this problem.




(k) NPhth = phthalimidoyl, an analog of succinimidoyl (as in NBS).




(l)




(m) Draw separate mechanisms for both reactions. The mechanism of the first reaction will be simpler to draw if you number the atoms in the very first intermediate, rather than the starting material. *Hint:* The carbon-containing coproduct of the second reaction is HCO_2^- .




(n)




(o)




- (p) What reaction could the second equivalent of the very strong, nonnucleophilic base LDA induce?




- (q) The *Fischer indole synthesis*. Note the coproduct!




- (r) Two equivalents of sodiomalonate are required for the following reaction to occur. *Hint*: What is the role of the second equivalent of malonate?




- (s)




- (t) The following problem is tough but doable. Number all your atoms and draw in the H atoms. Then ask, what is the role of the Rh?




(u)




(v) The reaction is thermally allowed, but light is required to supply enough activation energy.




(w)




(x)




(y)




(z)




- (aa) Be sure to account for the observed regio- and stereochemistry. *Hints:* (1) The C–O bond is already present in **A**. (2) Na₂S is an excellent nucleophile.




(bb)




(cc)




(dd)




(ee)




(ff)




- (gg) Here's a clue to rule out one of the possible mechanisms: Irradiation of benzene under the same conditions does *not* give benzocyclooctatetraene, the product of the following reaction.




- (hh) Atomic C has the reactivity of $\pm C\pm$, a double carbene.



- (ii) The key to this very difficult problem is to number the N atoms in the product correctly. Draw the azido groups in their $R\overset{-}{N}-\overset{+}{N}_2$ resonance structure, draw the coproducts, and *then* number the atoms. Then, for the first step, think of a thermal rearrangement of organic azides that we have already learned.



- (jj) No reaction occurs (starting material is recovered) in the absence of $\text{KO-}t\text{-Bu}$. What does that tell you about the mechanism of this reaction?



5.1 Free Radicals


A free radical is a species containing one or more unpaired electrons. Free radicals are electron-deficient species, but they are usually uncharged, so their chemistry is very different from the chemistry of even-electron electron-deficient species such as carbocations and carbenes.

The word *radical* comes from the Latin word for “root” (as in radish). The term *radical* was originally used to denote a fragment of a molecule that remained unchanged throughout a series of reactions. The term *free radical* was later coined to refer to a fragment of a molecule that wasn’t bonded to anything. Today, *radical* and *free radical* are used interchangeably, although *radical* still retains its original meaning in certain contexts (e.g., in the use of R in organic structures).

5.1.1 Stability

Most of the chemistry that is discussed in this chapter involves alkyl radicals ($\cdot\text{CR}_3$). The alkyl radical is a seven-electron, electron-deficient species. The geometry of the alkyl radical is a shallow pyramid, somewhere between sp^2 and sp^3 hybridization, and the energy required to invert the pyramid is very small. In practice, one can usually think of alkyl radicals as if they were sp^2 -hybridized.


Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_5) contains supplementary material, which is available to authorized users.




Both alkyl radicals and carbocations are electron-deficient species, and the structural features that lower the energy of carbocations also lower the energy of radicals. Alkyl radicals are lowered in energy by adjacent lone-pair-bearing heteroatoms and π bonds, just as carbocations are, and the order of energy of alkyl radicals is $3^\circ > 2^\circ > 1^\circ$. However, there are two major differences between the energy trends in carbocations and alkyl radicals.

- A C atom surrounded by seven electrons is not as electron-deficient as a C atom surrounded by six electrons, so alkyl radicals are generally not as high in energy as the corresponding carbocations. For example, the very unstable aryl and 1° alkyl carbocations are almost never seen, whereas aryl and 1° alkyl radicals are reasonably common.
- The amount of extra stabilization that adjacent lone pairs, π bonds, and σ bonds provide to radicals is not as great as that which they provide to carbocations. The reason is that the interaction of a filled AO or MO with an empty AO (as in carbocations) puts two electrons in an MO of reduced energy, whereas the interaction of a filled AO or MO with a half-filled AO (free radicals) puts two electrons in an MO of reduced energy and one electron in an MO of increased energy.

Orbital interaction diagram for radicals




Orbital interaction diagram for carbocations




Even though adjacent lone pairs, π bonds, and σ bonds do not stabilize radicals as much as they stabilize carbocations, the cumulative stabilizing effect of several such groups on a radical can be considerable. Benzylic radicals are particularly low in energy, as the radical center is stabilized by three π bonds. The triphenylmethyl (trityl) radical, a triply benzylic radical, was the first free radical to be recognized as such. This remarkably low energy radical is in equilibrium with the dimer that

results from combination of the methyl carbon of one radical with a para carbon on another radical. (The structure of the dimer was originally misidentified as hexaphenylethane.)




Neutral free radicals are electron-deficient, so radicals centered on less electronegative elements are lower in energy than radicals centered on more electronegative elements. As a result, the order of stability for first-row radicals is alkyl ($\cdot\text{CR}_3$) > aminyl ($\cdot\text{NR}_2$) > alkoxy ($\text{RO}\cdot$), and for halogens it is $\text{I}\cdot > \text{Br}\cdot > \text{Cl}\cdot > \text{F}\cdot$. **Common error alert:** The hydroxyl radical ($\cdot\text{OH}$) is very high in energy. Although it is involved in certain very important reactions in biological systems and in atmospheric chemistry, its intermediacy in a synthetic reaction should be viewed with skepticism. **Common error alert:** The $\text{H}\cdot$ radical is also very high in energy and is hardly ever seen.

Unlike carbocations, free radicals are lowered in energy both by electron-rich π bonds, like $\text{C}=\text{C}$ π bonds, and by electron-poor π bonds, like $\text{C}=\text{O}$ π bonds. The additional resonance provided by the $\text{C}=\text{O}$ group offsets the increase in energy from partly localizing a radical on O and making O electron-deficient. However, an electron-rich π bond is more energy-lowering than one that is electron-poor. When a radical is substituted by both an electron-donating and an electron-withdrawing group, the total decrease in energy is greater than the sum of the parts, in a phenomenon called the *captodative effect*.




The *aminoxyls* (a.k.a. *nitroxyl radicals* or *nitroxides*) are remarkably stable free radicals. Aminoxyls have two major resonance structures, one N-centered and one O-centered; the lone electron may also be considered to be in the π^* orbital of an $\text{N}=\text{O}$ π bond. Aminoxyls are stable because dimerization would give a very weak N–N, N–O, or O–O bond. TEMPO (2,2,6,6-tetramethylpiperidin-1-oxyl), a commercially available aminoxyl, is further stabilized by steric shielding. Other low-energy free radicals include the small molecules O_2 (a 1,2-diradical, best represented as $\cdot\text{O}-\text{O}\cdot$) and nitric oxide ($\cdot\text{N}=\text{O}$), a “messenger molecule” in mammals that mediates smooth muscle contraction.



Tables of homolytic bond strengths (bond dissociation energies, BDEs) offer a good guide to the relative energies of radicals. Such tables can be found in most organic chemistry textbooks. Compare the BDEs of the two bonds $\text{H}_3\text{C-H}$ and $\text{Me}_3\text{C-H}$. The BDE for the former is 104 kcal/mol, whereas the BDE for the latter is 91 kcal/mol. The smaller the BDE, the weaker the bond, and the lower energy the radical, so the $\text{Me}_3\text{C}\cdot$ radical is lower in energy than the $\text{H}_3\text{C}\cdot$ radical. If you compare the $\text{H}_3\text{C-Br}$ bond (70 kcal/mol) with the $\text{Me}_3\text{C-Br}$ bond (63 kcal/mol), you will see a similar trend. You should note, however, that the difference between the BDEs for $\text{H}_3\text{C-H}$ and $\text{Me}_3\text{C-H}$ (13 kcal/mol) is not the same as the difference between the BDEs for $\text{H}_3\text{C-Br}$ and $\text{Me}_3\text{C-Br}$ (7 kcal/mol). The difference between the ΔBDEs reflects the fact that the $\text{H}\cdot$ free radical is very high in energy. One must use BDEs with care!

Free radicals can also be stabilized kinetically by steric shielding of the radical centers. Such free radicals are called *persistent*. Examples of persistent free radicals include perchlorotriptyl, galvinoxyl, and the radical derived from BHT (butylated hydroxytoluene, 2,6-di-*tert*-butyl-4-methylphenol), an antioxidant that is used as a food preservative.




5.1.2 Generation from Closed-Shell Species


Most free radicals are not kinetically stable—they tend to react with one another to give electron-sufficient species—so free radicals that are to be used in reactions must usually be generated from closed-shell species in situ. (One very notable exception: O_2 , which is best described as a 1,2-diradical, $\cdot\text{O}-\text{O}\cdot$.) Free radicals can be generated from closed-shell species in four ways: σ -bond homolysis, photochemical excitation of a π bond, one-electron reduction or oxidation, and cycloaromatization.

- Sigma-bond homolysis is a very common way to generate free radicals. The σ bond is usually a heteroatom–heteroatom bond such as N-O or Br-Br , but even σ bonds such as C-C or C-N can homolyze if a very low energy fragment is formed or if the bond is very strained. Light is sometimes used to induce σ -bond homolysis

by promoting one of the electrons in the σ bonding orbital to the σ^* antibonding orbital, but if the σ bond is sufficiently weak and the product radicals are sufficiently low in energy, heat may suffice to break it.




Benzoyl peroxide and AIBN are two of the compounds most widely used to generate free radicals in a reaction mixture. The O–O bond in benzoyl peroxide and the C–N bonds in AIBN homolyze under thermal *or* photochemical conditions.




We use *single-headed* or *fishhook* electron-flow arrows to show the movement of unpaired electrons in free-radical reactions.

The likelihood of bond homolysis is directly related to the BDE for that bond. The BDE for the H–H bond is 104 kcal/mol, whereas the BDE for the Br–Br bond is 46 kcal/mol, so the likelihood of H–H homolysis is much smaller than the likelihood of Br–Br homolysis. Sigma bonds that are particularly prone to homolysis include N–O and O–O bonds, bonds between C and very heavy atoms like Pb and I, halogen–halogen bonds, and very strained bonds.

Upon photolysis of a diazo compound, the C–N bond cleaves in heterolytic fashion, N_2 is lost, and a *carbene* forms, usually in the *triplet* form. Triplet carbenes have one electron in each of two orbitals and may be thought of as 1,1-diradicals. Organic azides also undergo loss of N_2 upon photolysis. The products are highly reactive *nitrenes*, the N analogs of carbenes.




• When light of the appropriate wavelength is allowed to shine on a compound containing a π bond, an electron from the π bonding orbital is promoted to the π^* antibonding orbital. The product can be considered to be a 1,2-diradical, and it undergoes reactions typical of free radicals. The C=O, C=S, and C=C π bonds can all be photoexcited in this manner. The weaker the π bond, the easier it is to photoexcite.




An asterisk (*) is often used to denote a compound in a photoexcited state, but this notation does not convey the reactivity of the compound. The 1,2-diradical structure is a more useful depiction.

In photoexcited alkenes, there is no π bond between the two radical centers, so free rotation about the C–C bond can occur. *cis* Alkenes can be isomerized to *trans* alkenes photolytically. The reaction does not usually proceed in the reverse direction, because the photoexcited *cis* alkene and the photoexcited *trans* alkene are in equilibrium, and the equilibrium favors the less sterically encumbered *trans* isomer.




The eyes of arthropods, mollusks, and vertebrates use the *cis*–*trans* isomerization reaction to detect light. The eye contains an iminium ion derived from 11-*cis*-retinal and opsin. When light enters the eye, the iminium ion absorbs it and isomerizes to the lower energy all-*trans* iminium ion. The iminium ion's change in shape is converted into an electrical impulse that enters the brain via the optic nerve. Meanwhile, the all-*trans*-retinal is hydrolyzed from the opsin and transported to the back of the eye, where the enzyme retinal isomerase uses acid catalysis and ATP to

convert it back to the higher energy 11-*cis* form. The 11-*cis*-retinal is then sent back to the front of the eye, ready to receive the next photon.



• A compound with an electron in a high-energy orbital may transfer the electron to a compound that has a lower energy orbital. Most often the electron donor is a metal or reduced metal salt such as Li, Na, or SmI_2 , but the donor may also be a lone-pair-bearing compound such as an amine or phosphine, especially if it is photoexcited. (Photoexcitation promotes an electron from a nonbonding orbital into a higher energy orbital, whence it is more likely to participate in electron transfer.) The orbital accepting the electron is usually a π^* orbital, most often one associated with an aromatic ring or a $\text{C}=\text{O}$ π bond. In this case, it is convenient to use a one-electron electron-flow arrow to show the electron transfer from the electron donor to one of the atoms of the π bond, and a two-electron electron-flow arrow to show both electrons of the π bond moving to the other atom of the π bond. If the compound being reduced does not have a π^* orbital to accept the electron, it must go into a σ^* orbital. In this case, it may be most acceptable to transfer the electron to a heavy atom, giving it a nonet of electrons. After the electron is accepted, the product is called a *radical anion*.




Aromatic radical anions are often drawn in their “toilet bowl” or “happy alien” resonance form, but it is easier to keep track of all of the electrons with the localized resonance structures, and they are therefore recommended. About 18 different resonance structures in which a pair of electrons and an unpaired electron are localized on two atoms of the π system can be drawn. The three electrons can be distributed on any two ortho or para atoms of the ring.


There is a subtle difference between how we use two-electron and one-electron electron-flow arrows. In the case of two-electron arrows, if one wants to show atom A using a pair of electrons to form a bond to B, it is acceptable to draw the arrow pointing either from atom A *between* atoms A and B or from atom A *directly* to atom B.

(The former is slightly more preferred.) However, in the case of one-electron arrows, if one wants to indicate atom A using a single electron to form a bond to B, one must draw the arrow pointing from atom A to *between* atoms A and B. By contrast, a one-electron electron-flow arrow pointing from atom A *directly* to atom B indicates an electron transfer from A to B. There is no need to show electron transfer with a two-electron electron-flow arrow, because the transfer of two electrons simultaneously is exceedingly rare.


Both of the two-electron electron-flow arrows originating at A indicate bond-forming...




... but one of the one-electron electron-flow arrows originating at A indicates bond-forming, and the other indicates electron transfer!




The radical anion derived from a ketone is called a *ketyl*. The dark blue, sterically and electronically stabilized benzophenone ketyl is widely used in solvent stills as a deoxygenating agent.




Electron transfer is also the first step of the $S_{RN}1$ substitution mechanism (Chap. 2). In reactions that proceed by the $S_{RN}1$ mechanism, the electron donor is usually the nucleophile. The nucleophile may be photoexcited to give its electron more energy and make it more prone to transfer.




One-electron oxidation of organic substrates gives radical cations. Oxidation is much less common in synthesis than is reduction. Certain metal salts such as $Pb(OAc)_4$, $Mn(OAc)_3$, $Cu(OAc)_2$, $Fe(NO_3)_3$, and $(NH_4)_2Ce(NO_3)_6$ (ceric ammonium nitrate, CAN) are one-electron oxidizing agents.




$\text{Mn}(\text{OAc})_3$ is usually used to remove $\text{H}\cdot$ from the α -carbon atoms of carbonyl compounds. The $\text{Mn}(\text{III})$ makes an enolate, and $\text{Mn}-\text{O}$ σ bond homolysis generates $\text{Mn}(\text{II})$ and the enoxy radical.




Quinones such as DDQ (2,3-dichloro-5,6-dicyano-1,4-benzoquinone) and chloranil can also be used to remove one electron from a substrate.




• The *cycloaromatization* of certain highly unsaturated organic compounds can give diradicals. These reactions can be thought of as six-electron electrocyclic ring closings (Chap. 4), but whether the p orbitals of C3 and C4 of the six-atom system actually participate in the reaction is unclear. The best-known cycloaromatization reaction is the *Bergman cyclization* of an enediyne such as 3-hexene-1,5-diyne to give a 1,4-phenylene diradical. Allenlenynes (1,2,4-trien-6-yne) undergo cycloaromatizations, too.



The Bergman cyclization was discovered in the late 1960s and studied for its academic interest, but it suddenly became a hot topic of research in the mid-1980s when certain naturally occurring antitumor antibiotics that used the Bergman cyclization to attack DNA were discovered. In calicheamycin γ_1 , the aryl and sugar groups bind to DNA, and the polyunsaturated “warhead” portion of the molecule (the left-hand portion in the drawing) damages the DNA.



The warhead works as follows. Reduction of an S–S bond in the warhead portion of the molecule by endogenous substances in the cell nucleus generates a thiolate, which adds to the enone in an intramolecular conjugate addition. Rehybridization of the β -carbon of the enone from sp^2 to sp^3 upon conjugate addition brings the two ends of the enediyne close enough that they can undergo Bergman cyclization. The 1,4-diradical species that is thereby obtained abstracts H \cdot atom from the nearby DNA, causing damage and eventual cell death.



Other enediyne antitumor antibiotics (neocarzinostatin, esperamycin, dynemicin) may have similar or different mechanisms of activation, but they all use cycloaromatization as the key step in generating the DNA-damaging species.

5.1.3 Typical Reactions


Free radicals undergo eight typical reactions (the last two are two-electron reactions): addition to a π bond, fragmentation, atom abstraction (reaction with a σ

bond), radical–radical combination, disproportionation, electron transfer, addition of a nucleophile, and loss of a leaving group. *The first three are by far the most important.* Atom abstraction and addition reactions involve the reaction of a free radical with a closed-shell species, and fragmentation is the conversion of a free radical to a new free radical and a closed-shell species. Addition and fragmentation reactions are the microscopic reverse of one another. In general, the propagation part of a chain mechanism consists exclusively of addition, fragmentation, and atom abstraction steps.* Radical–radical combination, disproportionation, and electron transfer reactions are found in the termination part of chain mechanisms and in nonchain mechanisms. Chain mechanisms can be initiated by electron transfer, too.


*There is a radical–radical combination step in the propagation part of the chain mechanism for the autoxidation reaction. The propagation part of the $S_{RN}1$ mechanism (Chap. 2) consists of loss of a leaving group, addition of a nucleophile, and electron transfer.

The free-radical chain mechanism was discussed in Chap. 1. It is *essential* that you be familiar with the rules for drawing a chain mechanism!


- A free radical can *add to a π bond* of a closed-shell species to give a new radical. The radical ($X\cdot$) adds to a $Y=Z$ π bond to give $X-Y-Z\cdot$, in which the new $X-Y$ σ bond is made up of one electron from the radical and one electron from the former π bond. The $Y=Z$ π bond may be polarized or nonpolarized. Intermolecular additions of radicals to π bonds usually occur in such a way that the lowest energy radical forms, but intramolecular additions are often subject to stereoelectronic requirements that may cause the higher energy radical to form. The addition of free radicals to π bonds is mechanistically similar to the addition of π bonds to carbocations.




A free radical does not always add to a polarized π bond in the same way that a nucleophile would add. For example, the $Bu_3Sn\cdot$ radical adds to the S atom of $C=S$ π bonds, not to the C atom.




Free radicals can also add to stable “carbenes” such as CO and isocyanides RNC. The former carbene C has an unshared electron in the product.




The addition of free radicals to nitrones and nitroso compounds gives very stable aminoxyls. In fact, nitrones are commonly used as *spin trapping reagents* for the study of free radicals by electron paramagnetic resonance (EPR), the electronic analog of NMR. Free-radical intermediates in reactions have too fleeting a lifetime to be examined directly, but their aminoxyl derivatives are long-lived and can be studied by EPR.




• *Fragmentation* is the microscopic reverse of addition to a π bond. A σ bond that is *adjacent* (β) to a radical center homolyzes, and one of the electrons of that σ bond and the former unshared electron together form a new π bond at the former radical center. The fragmentation of a radical is mechanistically similar to the fragmentation of a carbocation.




CO can be lost from an acyl radical by a fragmentation reaction. In this case, the bond that breaks is *directly attached* (α) to the radical center.




The combination of Et_3B and O_2 is widely used to initiate radical reactions. The mechanism involves two unusual radical reactions. Addition of O_2 to the empty orbital of BEt_3 provides a one-electron bond between B and O, and a fragmentation follows to provide $\text{Et}\cdot$ and $\text{Et}_2\text{BOO}\cdot$.



• In an *atom abstraction reaction*, a radical $\text{X}\cdot$ attacks a Y-Z σ bond to give a new closed-shell species X-Y and a new radical $\cdot\text{Z}$. One of the electrons in the original σ bond is used to form the X-Y bond, and the other one ends up on Z. The transferred atom, Y, is usually H or halogen, but not always. **Common error alert:** *The abstraction of hydrogen atom $\text{H}\cdot$, which has a low activation energy, is not to be confused with the abstraction of hydride anion H^- , which is a very high energy process.*




The tributyltin radical ($\text{Bu}_3\text{Sn}\cdot$) is often used to abstract heavy atoms X from C-X bonds. The atom X is usually Br or I, but it may be Se or even S. The Sn-Br bond is strong enough that $\text{Bu}_3\text{Sn}\cdot$ can abstract $\text{Br}\cdot$ from aryl bromides to generate very high energy aryl radicals. $\text{Bu}_3\text{Sn}\cdot$ can itself be generated by $\text{H}\cdot$ abstraction from Bu_3SnH .



Food containing BHT is preserved from oxidative degradation because O_2 abstracts $\text{H}\cdot$ from the phenol group of BHT instead of from the food. The resulting phenoxy radical is persistent and unreactive due to steric encumbrance and resonance stabilization.

Common error alert: *Abstraction of C (e.g., $X\cdot + R_3C-Y \rightarrow X-CR_3 + \cdot Y$) does not occur in free-radical reactions.* An addition–fragmentation mechanism can be drawn for an apparent atom abstraction of $C(sp^2)$ or $C(sp)$. If your mechanism requires an abstraction of $C(sp^3)$, it is almost certainly incorrect. Even abstraction of O is very rare.



BDEs offer a good guide to the likelihood of atom abstraction. The smaller the BDE, the weaker the bond, and the more likely the bond will be broken by atom abstraction.


Common error alert: *Homolytic bond strengths are very different from heterolytic bond strengths.* In polar mechanisms, the likelihood of bond cleavage is usually related to the *heterolytic* bond strength. In radical reactions, on the other hand, the likelihood of bond cleavage is usually related to the *homolytic* bond strength. For example, under basic conditions, the RO–H bond is very likely to be cleaved in a heterolytic fashion (by deprotonation), whereas the Me_3C-H bond is not. However, the RO–H bond has a much larger BDE than the Me_3C-H bond, so abstraction of $H\cdot$ from RO–H by a free radical is much less favorable than abstraction of $H\cdot$ from Me_3C-H by the same free radical.

The *rate* of the atom abstraction reaction, $X\cdot + Y-Z \rightarrow X-Y + \cdot Z$, is dependent not only on the strength of the X–Y and Y–Z bonds, but also on the strength of the X–Z bond: The weaker the X–Z bond, the faster the abstraction. This phenomenon explains why the abstraction of $H\cdot$ from ArOH by O_2 is so fast: the weakness of the O–O bond causes the reaction to proceed very quickly.


The solvents of choice for free-radical reactions (CH_3OH , H_2O , benzene) share the feature that their X–H bonds have very large BDEs, so that the solvents are unlikely to participate in the reaction. Free-radical reactions executed in ether, THF, toluene, CH_2Cl_2 , and $CHCl_3$ are often complicated by atom abstraction from the solvent. Acetone is sometimes used as a solvent for free-radical reactions, because it can be photoexcited to act as an initiator, but it can also complicate free-radical reactions by giving up $H\cdot$ to another radical to afford the relatively stable 2-oxopropyl (acetyl) radical.

Unlike radical addition and fragmentation reactions, atom abstraction has no common counterpart in carbocation chemistry.

• Two radicals can react with one another in one of two ways: *radical–radical combination* or *disproportionation*. Radical–radical combination is the opposite of σ bond homolysis. Each of the two radical centers contributes its lone electron to form a new σ bond. Radical–radical combination is also known as *homogenesis* (opposite of homolysis). Radical–radical combination reactions are usually very fast and favorable. Most free radicals are very unstable because they undergo very rapid radical–radical combination.




In *disproportionation*, one radical $\text{X}\cdot$ abstracts $\text{H}\cdot$ atom from another radical $\text{H}-\text{Y}-\dot{\text{Z}}$ to give the two electron-sufficient species $\text{X}-\text{H}$ and $\text{Y}=\text{Z}$. The abstracted atom is almost always H, and it is always β to the radical center Z. The two radicals may be the same or different. Disproportionation, like radical–radical combination, is a very fast and favorable process.




The reaction is called *disproportionation* because two radicals with the same formula become two products with different formulas. (In the preceding example, $\text{C}_8\text{H}_9 + \text{C}_8\text{H}_9 \rightarrow \text{C}_8\text{H}_8 + \text{C}_8\text{H}_{10}$.)


In chain mechanisms, radical–radical combination and disproportionation reactions are seen only in the termination part of the mechanism. The one exception is the combination of O_2 with a free radical, one of the propagation steps in the autoxidation chain mechanism.




Nonchain mechanisms, though, often include radical–radical combinations and disproportionations. Aminoxyls can be used to trap alkyl radicals that may be present in a reaction medium by a radical–radical combination reaction, giving an electron-sufficient species that is more easily studied than the free radical. The photochemical reactions of carbonyl compounds often involve radical–radical combination and disproportionation steps.




• A radical can undergo *one-electron transfer* (oxidation or reduction) in the presence of an oxidizing or reducing agent to give an even-electron species. In nonchain mechanisms, a radical that undergoes electron transfer is itself usually generated by an electron transfer. A chain mechanism can be initiated or terminated by electron transfer. The final propagation step of the $S_{RN}1$ mechanism (Chap. 2) involves the one-electron oxidation of a radical anion by electron transfer.




• A radical anion can lose an anionic leaving group to give a neutral free radical, and, in the reverse direction, a neutral free radical can combine with an anionic nucleophile to give a new radical anion. A radical cation can also combine with a neutral nucleophile to give a new radical cation. Such steps occur in the $S_{RN}1$ mechanism (Chap. 2), in dissolving metal reductions, and in oxidative deprotections. These two-electron reactions have obvious counterparts in carbocation chemistry.



I have drawn analogies between free radicals and carbocations several times, but one of the typical reactions of carbocations, the concerted 1,2-shift, does not occur in free radicals. A concerted 1,2-radical shift is allowed only when one of the components can react *antarafacially*. The 1,2-hydrogen atom shift is geometrically impossible, and the geometric requirements of the 1,2-alkyl radical shift are so stringent that it is not observed.




Unsaturated groups, however, can shift by a two-step addition–fragmentation mechanism via a discrete cyclopropane radical intermediate. Phenyl groups are especially good at undergoing radical 1,2-shifts; 1,2-shifts of acyl, alkenyl, and, to a lesser extent, alkynyl and cyano groups are also seen.




Note that the most stable radical that could be obtained would result from a 1,2-*methyl* shift, but this is not the shift that occurs, because 1,2-methyl shifts cannot occur in free radicals.

Problem 5.1 Draw a mechanism for the following radical rearrangement.



Heavy atoms such as Br and Se can also undergo a radical 1,2-shift by an addition–fragmentation mechanism. An intermediate that features a heavy atom with a *nonet* of electrons intervenes. First-row elements cannot accommodate a nonet of electrons like heavy elements can, so the addition–fragmentation mechanism is disallowed for them.



Atom abstraction of Se and other heavy atoms may also take place by an addition–fragmentation mechanism involving a nine-electron intermediate.

5.1.4 Chain Versus Nonchain Mechanisms

A free-radical reaction may proceed by a chain or a nonchain mechanism. There are many experimental methods for determining whether a chain or a nonchain mechanism is operative in a reaction, but these methods do not help much in pencil-and-paper problems such as the ones in this book. Luckily, the reagents or reaction conditions will usually indicate which type of mechanism is operative.

- Reactions involving stoichiometric amounts of one-electron reducing or oxidizing agents such as Li, Na, SmI_2 , or $\text{Mn}(\text{OAc})_3$ always proceed by nonchain mechanisms, as free electrons are available throughout the reaction to quench the intermediate radicals. Reactions that generate two radicals simultaneously and in close proximity, such as cycloaromatizations and many photochemical reactions, also usually proceed by nonchain mechanisms.
- All chain reactions require an initiator, and there are only a few widely used initiators (O_2 , peroxides, AIBN, $h\nu$), so the presence of these initiators is a good sign of a chain mechanism. Be aware, though, that the (apparent) absence of an initiator does not rule out a chain mechanism. For example, the O_2 in the ambient atmosphere can act as an initiator, and many 3° alkyl iodides can undergo spontaneous C–I bond homolysis to initiate a chain reaction upon gentle heating. If a free-radical reaction involves a tin compound (e.g., Bu_3SnH), it proceeds by a chain mechanism. However, not all reactions involving Bu_3SnH are free-radical reactions. (A few transition-metal-catalyzed reactions also use Bu_3SnH .)


You may have noticed that $h\nu$ may indicate either a nonchain or a chain mechanism. A good rule of thumb for distinguishing light-initiated nonchain and chain mechanisms is that unimolecular rearrangements or eliminations usually proceed by nonchain mechanisms, whereas addition and substitution reactions (and especially intermolecular ones) almost always proceed by chain mechanisms. However, there are a few exceptions to this rule (photochemical pinacol reaction, Barton reaction). Of course, many pericyclic reactions require light, too (Chap. 4)!

5.2 Chain Free-Radical Reactions

5.2.1 Substitution Reactions


Probably the best-known example of a free-radical reaction is the halogenation of alkanes with Br_2 or NBS. This chain reaction is initiated by homolytic cleavage of Br_2 induced by light. The propagation part consists of two atom abstraction reactions.

Example




The termination parts of free-radical chain mechanisms are almost always the same: two free radicals from the propagation part react with each other, either in a radical–radical combination or disproportionation reaction. I will not routinely draw termination parts of chain mechanisms in this text.

Free-radical halogenation is most commonly applied to allylic or benzylic halogenation, as the radicals formed at these positions are lowest in energy. Of course, in allylic halogenation, transposition of the double bond can easily occur.




In brominations with NBS, it is thought that Br_2 is the actual halogenating agent. The Br_2 is generated by reaction of HBr (the coproduct of halogenation) with NBS. This polar reaction intervenes between the $\text{H}\cdot$ abstraction and $\text{Br}\cdot$ abstraction steps of the propagation part of the chain mechanism.



Elemental chlorine can be used in free-radical halogenation reactions, too, but these reactions are less easily controlled, because the $\text{Cl}\cdot$ radical is more reactive than the $\text{Br}\cdot$ radical and hence less selective. The reagents $t\text{-BuOCl}$ and SO_2Cl_2 are used as alternative chlorinating agents. The $\text{F}\cdot$ radical is so reactive, and the reaction $\text{F}\text{--}\text{F} + \text{C}\text{--}\text{H} \rightarrow \text{H}\text{--}\text{F} + \text{C}\text{--}\text{F}$ is so exothermic, that free-radical fluorinations can result in violent and uncontrollable exotherms (explosions). At the other extreme, free-radical iodinations of alkanes do not work well at all, as the $\text{H}\cdot$ abstraction step is too endothermic.


Free-radical *dehalogenations* are common, too. In these reactions, a $\text{C}\text{--}\text{X}$ bond is replaced with a $\text{C}\text{--}\text{H}$ bond. The reducing agent is most commonly Bu_3SnH , although $(\text{Me}_3\text{Si})_3\text{SiH}$ or a combination of a catalytic amount of Bu_3SnCl and a stoichiometric amount of NaBH_4 may be used instead as environmentally more friendly reagents. A catalytic amount of AIBN or $(\text{BzO})_2$ is commonly used as a free-radical initiator. Initiation involves abstraction of $\text{H}\cdot$ from Bu_3SnH by a radical derived from the initiator. In the propagation part, $\text{Bu}_3\text{Sn}\cdot$ abstracts $\text{X}\cdot$ from the $\text{C}\text{--}\text{X}$ bond to give Bu_3SnX and an alkyl radical, which then abstracts $\text{H}\cdot$ from Bu_3SnH to give the alkane and regenerate $\cdot\text{SnBu}_3$.


Example



Alcohols are deoxygenated in the *Barton–McCombie reaction*. The alcohol is first converted into a xanthate (ROCS₂CH₃) or another thiocarbonyl compound, and then the entire functional group is removed by Bu₃SnH and replaced with H. In the propagation part of the mechanism, Bu₃Sn· adds to S of the S=C bond, and the resulting radical fragments to give the alkyl radical and a carbonyl compound. The alkyl radical then abstracts H· from Bu₃SnH to regenerate the chain-carrying radical ·SnBu₃. Formation of the strong C=O π bond provides the driving force for fragmentation of the C–O σ bond.


Example





The substitution of H with OOH in organic compounds is called *autoxidation*. (“Autoxidation” is a misnomer, because the substrate is not oxidizing itself; O_2 is doing the oxidizing.) Autoxidation proceeds by a free-radical chain mechanism. The O_2 serves as both an initiator and as a stoichiometric reagent. Note that the mechanism includes a very rare radical–radical combination step in the propagation part. The radical–radical combination step doesn’t terminate the chain in this particular reaction because O_2 is a 1,2-diradical.


Example




Common error alert: Students are often tempted to draw a nonchain mechanism for autoxidation that involves the combination of the two radicals produced in

the initiation step. Resist this temptation! The concentration of O_2 , and hence its rate of reaction with the alkyl radical, is much higher than that of $\cdot OOH$.


WRONG!



Ethers are most prone to autoxidation because O lowers the energy of a radical at the adjacent C atom. Aldehydes are also quite prone to autoxidation. In the latter case, the immediate products, carboxylic peracids, react with the starting aldehydes to give carboxylic acids by a Baeyer–Villiger reaction (Chap. 3).



Autoxidation is one of the key steps in the industrial synthesis of phenol and acetone from benzene and propylene. In the second step of this synthesis, cumene (isopropylbenzene) autoxidizes to cumyl hydroperoxide.




Problem 5.2 Draw mechanisms for all three steps of the phenol synthesis.

Autoxidation is one of the most important abiotic processes by which degradation of organic compounds occurs. Autoxidation of ethers like diethyl ether, THF, and other common solvents leads to the formation of hydroperoxides, which are explosively heat- and shock-sensitive. Diisopropyl ether is so prone to autoxidation that it is necessary to dispose of it *immediately* after opening a bottle of it. Autoxidation of biological compounds may be partly responsible for the aging process. The autoxidation of oily rags in garages releases heat, accelerating the autoxidation process, leading more heat to be released and eventually causing a fire.

In the *Hofmann–Loeffler–Freitag* reaction, an *N*-chloroammonium ion is converted by a free-radical substitution reaction into a 4-chloroalkylammonium ion,

which then undergoes intramolecular S_N2 substitution to give a pyrrolidine. In the free-radical substitution mechanism, the abstraction step occurs in an intramolecular fashion. Entropic and stereoelectronic factors make the regioselectivity very high for the C4 hydrogen.


Example



5.2.2 Addition and Fragmentation Reactions


5.2.2.1 Carbon–Heteroatom Bond-Forming Reactions

The anti-Markovnikov addition of HBr to alkenes was probably the first free-radical addition reaction to be discovered. The discovery was inadvertent; around the turn of the twentieth century, scientists studying the regiochemistry of addition of HBr to alkenes found that the proportion of Markovnikov to anti-Markovnikov addition products varied inexplicably from run to run. Eventually it was discovered that impurities such as O_2 and peroxides greatly increased the amount of anti-Markovnikov addition product. The results were later explained by a free-radical addition mechanism. The anti-Markovnikov regiochemistry derives from the addition of $\text{Br}\cdot$ radical to the less substituted C atom of the alkene (steric reasons) to give the lower energy, more substituted radical (electronic reasons). The eventual product has the Br atom attached to the C atom that was *less* substituted in the original alkene. By contrast, in a polar reaction, the Br atom ends up attached to the C atom that was *more* substituted in the original alkene.

Example



In contrast to HBr, the acids HCl and HI do not undergo free-radical addition to alkenes, even in the presence of peroxides or O_2 . Abstraction of $\text{H}\cdot$ from HCl is too endothermic, and addition of $\text{I}\cdot$ to an alkene is too endothermic. However, thiols (RSH) add to alkenes by a free-radical mechanism exactly analogous to the addition of HBr. The initiator is usually AIBN or $(\text{BzO})_2$. The alkene may be electron-rich or electron-poor. In fact, the conjugate addition of thiols to electron-poor alkenes can occur either by a free-radical mechanism or by a polar, nucleophilic mechanism.

Problem 5.3 Draw a free-radical mechanism for the following addition reaction.



Tributyltin hydride adds across $\text{C}=\text{C}$ π bonds by a free-radical mechanism. Addition of Bu_3SnH across alkynes is one of the best ways of making alkenyltin compounds, which are useful reagents in organic synthesis. The mechanism is exactly the same as the one for addition of HBr across an alkene. The intermediate alkenyl radical is stabilized by hyperconjugation with the relatively high energy $\text{C}-\text{Sn}$ bond.


Problem 5.4 Draw a free-radical mechanism for the following addition reaction.




5.2.2.2 Carbon-Carbon Bond-Forming and -Cleaving Reactions

The most important free-radical chain reaction conducted in industry is the free-radical polymerization of ethylene to give polyethylene. Industrial processes usually use $(t\text{-BuO})_2$ as the initiator. The $t\text{-BuO}\cdot$ radical adds to ethylene to give the beginning of a polymer chain. The propagation part has only one step: the addition of ethylene to an alkyl radical at the end of a growing polymer to give a new alkyl radical at the end of a longer polymer. The termination steps are the usual radical–radical combination and disproportionation reactions.


Example



Example




Free-radical cyclization reactions (i.e., the intramolecular addition of an alkyl radical to a C=C π bond) have emerged as one of the most interesting and widespread applications of free-radical chemistry to organic synthesis. Free-radical cyclizations are useful because they are so fast. The cyclization of the 5-hexenyl radical to the cyclopentylmethyl radical is very fast, occurring at a rate of about $1.0 \times 10^5 \text{ s}^{-1}$. In fact, the rate of formation of the cyclopentylmethyl radical is much *faster* than the rate of cyclization to the more stable cyclohexyl radical. This *stereoelectronic* effect is derived from the fact that the overlap between the p orbital of the radical and the π^* MO of the double bond is much better when C1 attacks C5 than when it attacks C6. The relative rates of 5-*exo* and 6-*endo* ring closures are strongly dependent on the nature of the substrate and especially on the amount of substitution on the π bond. Cyclization of the 6-heptenyl radical in the 6-*exo* mode is also very favorable.



The mechanisms of intramolecular free-radical cyclization reactions are no different from their intermolecular counterparts.


Example




A two-step addition–fragmentation process involving a nine-electron Se atom intermediate could be drawn in place of the atom abstraction reaction.

Problem 5.5 Draw mechanisms for the following free-radical cyclization reactions. All cyclization steps should give five- or six-membered rings, if possible.

(a)




(b)




A free radical can add to CO or an isocyanide (RNC) in the course of a free-radical cyclization reaction, too, to give an acyl radical ($\dot{\text{R}}\text{C}=\text{O}$) or an *iminyl* radical ($\dot{\text{R}}\text{C}=\text{NR}$), either of which can undergo further reactions. In the following example, an alkyl radical adds to the terminal C of *t*-BuNC to give an iminyl radical. The iminyl radical then fragments to give *t*-Bu· and an alkyl cyanide ($:\text{N}\equiv\text{CR}$). In a different substrate, the iminyl radical might undergo an addition or an abstraction reaction instead.

Example




A second interesting feature of this reaction is that a catalytic amount of Bu_3SnCl and a stoichiometric amount of NaBH_3CN are added to the reaction mixture. The small amount of Bu_3SnCl that is added to the reaction mixture is reduced to Bu_3SnH with a small amount of NaBH_3CN . Within each catalytic cycle, the Bu_3SnH is converted to Bu_3SnI , and the stoichiometric NaBH_3CN reduces it back to Bu_3SnH . This technique allows one to minimize the quantity of malodorous and toxic Sn compounds used in the reaction, but care must be taken to ensure that the rates of the additional reaction steps are properly balanced to avoid accumulation of radical intermediates.

Problem 5.6 Draw a mechanism for the following free-radical cyclization reaction.



Some free-radical cyclization reactions require only a catalytic amount of Bu_3SnH or $\text{Bu}_3\text{SnSnBu}_3$. Such a reaction, instead of replacing a C–X bond with a C–H bond, simply relocates the X atom. These *atom transfer cyclizations* differ from more conventional free-radical cyclizations in that the last step in the propagation involves abstraction of X· from a C–X bond not by $\cdot\text{SnBu}_3$, but by the cyclized starting material. The last step is kinetically viable only when a stronger bond is made from a weaker one. In the following example, a Si–I bond is made at the expense of a C–I bond.


Example



Compounds with weak C–H bonds can add to alkenes by a free-radical chain mechanism. Compounds that can add to alkenes in this way include RCHO compounds (aldehydes, formates, etc.) and 1,3-dicarbonyl compounds. In the initiation


part of the mechanism, an initiator radical abstracts H· from the weak C–H bond to give an alkyl radical. In the propagation part of the mechanism, the alkyl radical adds across the C=C π bond, and then the new radical abstracts H· from the weak C–H bond to give the product and regenerate the first alkyl radical.

Example




Problem 5.7 Draw free-radical mechanisms for the following addition reactions.

(a)




(b)




The addition of a free radical to a π bond is sometimes followed directly by fragmentation of the new free radical. For example, alkyl halides and selenides react with (allyl)SnBu₃ in a *free-radical allylation reaction* to give a product in which the halogen or selenium is replaced with an allyl group. In the propagation part of the

mechanism, $\text{Bu}_3\text{Sn}\cdot$ abstracts $\text{X}\cdot$ from the starting material to generate an alkyl radical, which adds to the terminal C of the allyl group of the stannane. Fragmentation then occurs to give the product and to regenerate $\cdot\text{SnBu}_3$.


Example


Problem 5.8 Draw an addition–fragmentation mechanism for the following reaction.




The fragmentation of cyclopropylmethyl radicals to give 3-butenyl radicals is one of the fastest reactions known, occurring at a rate of $2.1 \times 10^8 \text{ s}^{-1}$! Phenyl-substituted cyclopropylmethyl groups open at even faster rates. These *radical clocks* can be used to probe the mechanism of very fast reactions, especially those in enzymes. If a substrate undergoes a reaction that involves a radical intermediate, and the lifetime of the intermediate is longer than about 10^{-8} s , then an analog of that substrate that has a cyclopropyl group attached to the putative radical center will give a product in which the cyclopropyl ring has opened. Lack of ring opening does *not* mean that there was no radical intermediate; instead, it simply means that the lifetime of the radical intermediate was shorter than the lifetime of the cyclopropylmethyl radical. However, if the lifetime of a radical intermediate is

shorter than the fastest reaction known, then, practically speaking, one can say that it does not exist.



In the *Hunsdiecker reaction*, the silver salt of a carboxylic acid (RCO_2Ag) is treated with Br_2 to give an alkyl bromide (RBr) with one fewer C atom. The reaction does not work well with aromatic acids, suggesting that a free-radical mechanism is involved. The carboxylate and bromine react to give an acyl hypobromite, which decomposes by a free-radical chain mechanism.

Example




5.3 Nonchain Free-Radical Reactions


The major classes of nonchain free-radical reactions are photochemical reactions, reductions and oxidations with metals, and cycloaromatizations.

5.3.1 Photochemical Reactions


The photoexcitation of a carbonyl compound to a 1,2-diradical is often followed by a fragmentation reaction. The fragmentation can take one of two courses, called *Norrish type I* and *Norrish type II* cleavages. In *Norrish type I* cleavage, the bond between the α -carbon and the carbonyl carbon cleaves to give an acyl radical and an alkyl radical. These radicals can subsequently undergo a variety of reactions. For example, the acyl radical can decarbonylate to give a new alkyl radical, which can undergo radical–radical combination with the alkyl radical generated in the *Norrish type I* cleavage. Alternatively, the acyl and alkyl radicals can undergo disproportionation to give an aldehyde and a C=C π bond. A third possibility, radical–radical recombination, simply regenerates the starting material.




In *Norrish type II* cleavage, the O radical abstracts H from the γ -carbon in a six-membered TS, and the 1,4-diradical then fragments to give an alkene and an enol, the latter of which tautomerizes to the ketone. Sometimes the 1,4-diradical undergoes radical–radical combination to give a cyclobutane, instead. The *Norrish type II* cleavage is closely related to the *McLafferty rearrangement* that is often seen in the mass spectra of carbonyl compounds.



Problem 5.9 The 2-nitrobenzyl group is used as a base- and acid-stable but photolabile protecting group for alcohols. Draw a Norrish mechanism for the release of an alcohol from a 2-nitrobenzyl ether upon photolysis.




Photoexcited ketones can undergo other reactions typical of free radicals. Benzophenone dissolved in isopropyl alcohol undergoes a *photochemical pinacol coupling* merely upon exposure to sunlight. The *i*-PrOH acts as a hydrogen atom donor.



In the *Barton reaction*, an alkyl nitrite is converted into an alcohol–oxime. The nitrite is photoexcited to a 1,2-diradical. It fragments to NO and an alkoxy radical (RO•), and the latter abstracts H• from the nearest C–H bond. The resulting alkyl radical then combines with NO to give a nitroso compound, which then tautomerizes to the oxime, probably by a polar stepwise mechanism. The Barton reaction has been used for the remote functionalization of hydrocarbons, especially steroids.

Example



One could write a perfectly reasonable chain mechanism for the Barton reaction, but a nonchain mechanism is appropriate because NO is a stable free radical, and it hangs around until it is able to combine with the alkyl radical to form a strong C–N bond.

Finally, it should be mentioned that the photochemically allowed [2 + 2] cycloaddition reaction of alkenes can be considered to be a radical-mediated process. Photoexcitation of an alkene gives a 1,2-diradical. The radical at C1 adds to one terminus of the other alkene to give a 1,4-diradical, which then cyclizes to give the observed product. Spectroscopic measurements at the femtosecond time scale have proven that the 1,4-diradical is a true intermediate along the reaction pathway of [2 + 2] cycloadditions. However, the lifetime of the 1,4-diradical is shorter than the rate of rotation about C–C σ bonds, as [2 + 2] cycloadditions are stereospecific.



5.3.2 Reductions and Oxidations with Metals

Reductions for which group 1 metals and other one-electron reducing agents are used in organic chemistry can be divided into two classes: those that involve addition of H_2 across a π bond, such as conjugate reduction and the Birch reduction, and those in which σ bonds between non-H atoms are formed or broken, such as the reduction of C–X bonds and acyloin and pinacol condensations.

5.3.2.1 Addition of H_2 Across π Bonds

Reductions involving addition of H_2 across a π bond follow one or both of the following two sequences of events.

1. An electron is transferred from the metal to the substrate to give a radical anion.
2. A second electron transfer to the radical anion occurs to give a closed-shell dianion.
3. The dianion is protonated to give a closed-shell anion.

or


1. An electron is transferred from the metal to the substrate to give a radical anion.
2. The radical anion is protonated to give a neutral radical.
3. A second electron transfer occurs to give a closed-shell anion.

The solvent is usually liquid ammonia, in which the electrons from the metal are solvated, giving a dark blue solution. The proton source is usually an alcohol or ammonia itself.

Dissolving metals have been used for the *conjugate reduction* of α,β -unsaturated ketones for a very long time, and the method is still one of only a few good ones for accomplishing this transformation. In conjugate reduction, two electron transfers occur to give a closed-shell dianion. Protonation of the dianion occurs to give the


enolate. The enolate may be converted to the ketone by an aqueous workup, to the silyl enol ether by treatment with Me_3SiCl , or to an alkylated ketone by addition of an alkyl halide.

Example




Conjugate reduction is also useful for the regiospecific generation of enolates. Deprotonation of a 3-substituted cyclohexanone gives a nearly equimolar ratio of regioisomeric enolates, but either enolate can be regiospecifically generated by conjugate reduction of the appropriate cyclohexenone.


Deprotonation leads to a mixture of regioisomeric enolates...



... but conjugate reduction leads to regiospecific enolate formation.




Saturated ketones are reduced to alcohols in the *Bouveault–Blanc reduction* by an almost identical mechanism. This old reaction has been largely superseded by the advent of complex metal hydrides like NaBH_4 and LiAlH_4 , but it is still useful because it always gives the lowest energy diastereomer. By contrast, in reductions with metal hydrides, the major product is often the higher energy diastereomer.



Problem 5.10 Draw a mechanism for the Bouveault–Blanc reduction of the preceding ketone.


In the reduction of alkynes to *trans* alkenes, the second electron transfer occurs *after* the first protonation. The stereochemistry-determining step is protonation of the carbanion obtained after the second electron transfer. The lower energy *trans* product is obtained.

Example




The *Birch reduction* converts arenes to 1,4-cyclohexadienes. The mechanism, again, is electron transfer to the ring, protonation of the radical anion, a second electron transfer to give a carbanion, and protonation to give the neutral product. The reaction is highly regioselective. The protonation steps determine the regiochemistry of the reduction. They occur *para* and *ipso* to electron-withdrawing groups, and *ortho* and *meta* to electron-donating groups. As a result, in the product, electron-donating groups such as MeO are conjugated to the π bonds, and electron-withdrawing groups such as $-\text{CO}_2\text{H}$ (actually, $-\text{CO}_2^-$, because the reaction conditions are basic) are placed at the sp^3 -hybridized positions.


Example



When a benzoic acid derivative is reduced, the final protonation step does not occur, and a carboxylate enolate is obtained. The enolate can be protonated upon workup to give the usual product, or it can be alkylated by addition of an electrophile. The proton or the electrophile adds ipso to the carboxylate group exclusively. This position has the largest coefficient in the HOMO of the pentadienyl anion.




Birch reductions are highly intolerant of functionality. All benzylic ethers, alcohols, and carbonyl groups are reduced away and replaced with H, as are halogens anywhere in the compound. Nonbenzylic carbonyls may or may not be reduced to alcohols, but alkynes and conjugated alkenes are reduced to simple alkenes.



The reductive cleavage of benzylic ethers makes the benzyl group a useful protecting group for alcohols. It is stable to many acidic and basic conditions, and it


can be removed by reduction with Li in liquid NH_3 . (It can also be removed by Pd-catalyzed hydrogenolysis; see Chap. 6). The products of the reductive cleavage are the desired alcohol plus toluene or methylcyclohexadiene (either of which is easily removed by evaporation).



Problem 5.11 Draw a mechanism for the dissolving metal reduction of acetophenone (PhCOMe) to ethylbenzene and thence to 1-ethyl-1,4-cyclohexadiene.


5.3.2.2 Reduction of C–X Bonds. Reductive Coupling

Leaving groups on the α -carbon of carbonyl compounds (e.g., Br and OR) are reduced away by one-electron reducing agents. α -Bromocarbonyl compounds are reduced to the corresponding enolates by Zn in the *Reformatsky reaction* (Chap. 2). After the initial electron transfer, several pathways are possible, but all lead to the enolate. The enolate is usually allowed to react immediately with an electrophile such as another carbonyl compound. Before the advent of strong, nonnucleophilic bases such as LDA, the Reformatsky reaction was the only way to prepare enolates of simple carbonyl compounds quantitatively.




Samarium diiodide (SmI_2), an oxophilic, one-electron reducing agent, is particularly useful for the α -deoxygenation of ketones. The metal in SmI_2 is in the +2 oxidation state, but it prefers to be in the +3 oxidation state, so it transfers one electron to a $\text{C}=\text{O}$ π bond to give the ketyl. (Sm ketyls are usually drawn as $\text{R}_2\dot{\text{C}}-\text{OSm}$ instead of $\text{R}_2\dot{\text{C}}-\text{O}^-$.) The ketyl can do any of its usual chemistry, including adding to pendant π bonds. When there is a hydroxy or alkoxy group α to the carbonyl group, though, a second equivalent of SmI_2 coordinates to it. Sigma bond homolysis then gives ROSmI_2 and the deoxygenated carbonyl compound as its enolate, which can be protonated in situ or upon workup.

Example



In this example, three equivalents of SmI_2 are used in order to provide an excess of the reagent.


In the *pinacol coupling*, two ketones are reductively coupled to give a 1,2-diol. (Compare the photochemical pinacol coupling discussed earlier.) The two ketones are usually identical, but intramolecular dimerizations can give unsymmetrical 1,2-diols. There are two possible mechanisms. Both begin by electron transfer to the ketone to give a ketyl radical anion. In mechanism (a), the radical anion then dimerizes to give a dialkoxide. The problem with this mechanism is that it requires that two negatively charged compounds to react with one another. In mechanism (b), the C of the ketyl radical adds to the carbonyl C of the starting ketone, and a second electron transfer then gives the dialkoxide. In either case, workup then provides the diol.




The *acyloin condensation* converts two esters to an α -hydroxyketone (an acyloin), often in an intramolecular fashion. Modern acyloin condensations are usually executed in the presence of Me_3SiCl in addition to the metal, and a bis(silyloxy)

alkene is obtained as the immediate product. The bis(silyloxy)alkene may then be hydrolyzed to the acyloin upon workup. The Me_3SiCl may improve the yield by reacting with the ketyl to give a neutral radical, which can add more easily to the other carbonyl group or ketyl radical. The reaction proceeds by a mechanism very similar to the pinacol coupling, except that there are two elimination steps and two additional electron transfer steps. The intramolecular reaction works well for a wide variety of ring sizes.


Example




The compound *S*-adenosylmethionine (SAM) has two major roles in biology. One of its roles is to methylate nucleophiles, acting as a source of electrophilic CH_3 , much like CH_3I , but its other role is as a precursor to an alkyl radical. In the latter role, a cluster of Fe and S atoms in the active site of a radical SAM enzyme transfers an electron to the positively charged S atom, which then undergoes S–C bond cleavage to give free methionine and 5'-deoxyadenosyl radical (dAdo·).



The *dAdo*· radical can then go on and do chemistry typical of 1° alkyl radicals. For example, in the biosynthesis of biotin, *dAdo*· abstracts H· from a methyl group of a cyclic urea substrate, and the resulting 1° alkyl radical makes a bond to a nearby S atom that is bound to two Fe(III) atoms, reducing one of them to Fe(II). Subsequently, another *dAdo*· abstracts another H· from a methylene group in the substrate, and the resulting 2° alkyl radical makes a bond to the same S atom, forming biotin and reducing the second Fe(III) to Fe(II).




Problem 5.12 Draw a mechanism for the isomerization of the pyridoxal phosphate imine of L-lysine to that of L- β -lysine catalyzed by *dAdo*·. (You can find a discussion of the structure and chemistry of pyridoxal phosphate in Chap. 3.)




5.3.2.3 One-Electron Oxidations

The *p*-methoxyphenyl group can be removed from N or O by a one-electron oxidation promoted by CAN or DDQ. The aryl group is further oxidized to the quinone after it is cleaved from the substrate, so at least two equivalents of oxidant is required.


Example




The enzyme cytochrome P450 metabolizes tertiary amines in the liver by a one-electron transfer mechanism. An electron is transferred from N to a heme group featuring an Fe=O bond to give an aminium radical cation and the radical anion [Fe]–O·. An α -hydrogen atom is then abstracted by the oxygen-based radical to give an iminium ion. Hydrolysis of the iminium ion affords a secondary amine and an aldehyde, both of which are further oxidized into water-soluble compounds and then excreted. The oxidation of tertiary amines to secondary amines can also be executed in the laboratory.



Problem 5.13 Draw a reasonable mechanism for the following reaction. Why aren't any of the C atoms adjacent to the ring N oxidized?




Another class of Fe-containing oxidizing enzymes, the *hydroxylases*, replace C–H bonds with C–OH bonds by a radical mechanism. An Fe(IV) oxo species uses its O atom to abstract H \cdot from the substrate, giving an alkyl radical and an Fe(III) hydroxide. The C \cdot then abstracts $\cdot\text{OH}$ from the Fe(III) hydroxide to give the new C–OH bond and Fe(II). The Fe(II) is converted back to Fe(IV) by O_2 and, in some hydroxylases, 2-oxoglutarate.



5.3.3 Cycloaromatizations

The synthetic potential of cycloaromatizations has barely been explored. The two aryl radicals that are generated in the cycloaromatization are usually trapped by abstraction of H \cdot from a compound such as 1,4-cyclohexadiene. In vivo, the H \cdot source is DNA. Alternatively, one of the aryl radicals may add to a nearby π bond to give a new radical, which may itself be quenched by H \cdot abstraction.


Example



5.4 Miscellaneous Radical Reactions


5.4.1 1,2-Anionic Rearrangements. Lone Pair Inversion

The Stevens rearrangement and the Wittig rearrangement (nonallylic version) (Chap. 4) can be classified as four-electron [1,2] sigmatropic rearrangements. The Woodward–Hoffmann rules state that for a four-electron sigmatropic rearrangement to be allowed, one of the components must be antarafacial, yet it is geometrically impossible for either component in the Stevens and Wittig rearrangements to react antarafacially. How can this be?




One of the conditions of the Woodward–Hoffmann rules is that they are applicable only if the reaction proceeds in a concerted fashion. The fact that the Stevens and the Wittig rearrangements proceed can be explained by a two-step, nonconcerted mechanism involving free radicals. After deprotonation of the position α to the heteroatom, homolysis of the bond between the heteroatom and the migrating group occurs to give a radical and a radical anion. The resonance

structure of the radical anion shows that it is a ketyl. Radical–radical combination of the migrating group with the ketyl C gives the rearranged product. Note, in this example, it is reasonable to propose $\text{CH}_3\cdot$ as an intermediate, though it is never reasonable to propose CH_3^+ .



Problem 5.14 Draw the mechanism for the Stevens rearrangement.


The lone pairs on amines are nonstereogenic; that is, a compound such as $\text{MeN}(\text{Et})(i\text{-Pr})$ is pyramidalized and chiral, but the rapid inversion of the N lone pair (the “umbrella effect”) at room temperature makes it impossible to isolate the enantiomers of all but a few amines. By contrast, lone-pair-bearing heavy atoms such as S and P do not undergo inversion at room temperature, and trivalent S and P compounds are configurationally stable at normal temperatures ($<100\text{ }^\circ\text{C}$). Sulfoxides do racemize when they are heated to sufficiently high temperatures. The mechanism of racemization is thought *not* to involve inversion of the lone pair on S. Instead, the racemization is thought to proceed by homolysis of a S–C bond. The divalent S radical no longer has a configuration. Radical–radical recombination can then occur to give either enantiomer of the starting material.



5.4.2 Triplet Carbenes and Nitrenes


Upon photolysis of a diazo compound or an azide, a triplet carbene or nitrene is generated. The two unshared electrons in triplet carbenes have aligned spins and reside in different orbitals. Triplet carbenes and nitrenes undergo all the typical reactions of singlet carbenes and nitrenes (Chap. 2) but with one important difference: the reactions are not stereospecific. The lack of stereospecificity in the reactions of triplet carbenes and nitrenes is due to their 1,1-diradical character. For example, consider a cyclopropanation reaction. The two electrons in the π bond have opposite spins, but the two electrons in the triplet carbene have aligned spins. For the cyclopropanation to be concerted, all four electrons have to flow smoothly into two new σ bonding orbitals, but this is not possible when three electrons are aligned opposite the fourth. The reaction therefore proceeds in a stepwise fashion: one bond forms, the two lone electrons of the 1,3-diradical lose contact with each other and randomize their spins, then the second bond forms. The lifetime of the 1,3-diradical intermediate is long enough that rotation about σ bonds can occur, causing a loss of stereochemical purity about the former π bond.

Example




Do not use the notation $R_2C\pm$ to describe triplet carbenes. The “ \pm ” in “ \pm ” represents a pair of electrons, but the two electrons in triplet carbenes are unpaired. The notation $R_2C:$ describes either a singlet or triplet carbene.

Triplet carbene and nitrene C–H insertion reactions occur with loss of stereochemical purity around the C from which the H is abstracted, in contrast to C–H insertion reactions of singlet carbenes and carbenoids (Chap. 2). The triplet carbene or nitrene, a 1,1-diradical, abstracts H· from the substrate to give two radical intermediates. After the lone electrons lose track of each other’s spins, radical–radical combination gives the product. The nitrene insertion reaction is the basis of *photoaffinity labeling*, in which the ligand of a biological receptor is modified with an azido group and a radioactive or fluorescent tag, allowed to bind to the protein, and then photolyzed to install the label covalently and specifically in the binding pocket.



The singlet form of carbenes substituted with a carbonyl group is much lower in energy than the triplet, so the photolysis of α -diazocarbonyl compounds gives singlet carbenes. The photo-Wolff rearrangement (Chap. 2) of α -diazoketones occurs upon photolysis of these compounds.



The reactions of carbenes are complicated by the fact that *intersystem crossing* (i.e., interconversion of the triplet and singlet states by a spin flip of an electron) can occur readily, as in the photo-Wolff rearrangement. Which of the two states of a particular carbene is lower in energy is also strongly dependent on the nature of the substituents. In general, singlet carbenes are more useful synthetically because they react stereospecifically. Most carbene-generating techniques give singlet carbenes.

5.5 Summary

Free radicals are seven-electron, electron-deficient species, whereas *carbocations* are six-electron, electron-deficient species. Carbocations undergo three typical reactions: addition of a nucleophile, fragmentation, and rearrangement by a 1,2-shift. *Carbenes* are also six-electron, electron-deficient species. They undergo four typical reactions: cyclopropanation, insertion into a C–H bond, addition of a nucleophile, and rearrangement by a 1,2-shift. The similarities that exist among free radicals, carbocations, and carbenes are apparent. The differences among them are due to their different electron counts and the presence or absence of an unshared pair of electrons.

Free radicals undergo eight typical reactions, but three are most important: atom abstraction, addition to a π bond, and fragmentation. (The other five are radical–radical combination, disproportionation, electron transfer, addition of a nucleophile, and loss of a leaving group.) Many free-radical reactions proceed by chain mechanisms, but photochemical rearrangements, oxidations and reductions, and cycloaromatizations do not.


5.6 Problems

1. Methyl *tert*-butyl ether, MTBE, and ethyl *tert*-butyl ether, ETBE, are added to gasoline in order to increase the efficiency of gasoline combustion, which reduces the quantity of volatile organic compounds (VOCs) that escape into the atmosphere and cause smog. The chemical industry is very interested in using


MTBE as a substitute for THF and diethyl ether, because autoxidation of THF and diethyl ether is a major safety problem for chemical companies. The industry is less interested in ETBE as a solvent substitute.

- (a) Why is MTBE less prone to autoxidize than ether and THF?
 - (b) Why is ETBE of less interest than MTBE as a substitute for diethyl ether and THF?
 - (c) Draw a mechanism for the synthesis of MTBE from methanol and isobutylene. What kind of conditions are required?
 - (d) Senators from farm states have pushed EPA to require a certain percentage of ETBE (but not MTBE) in gasoline oxygenates. Why? (*Hint*: What starting materials are used to prepare ETBE, and what do they have to do with farming?)
 - (e) MTBE has been banned in California because it has contaminated groundwater, imparting a very bad odor to it. Its presence there derives from leaking underground gasoline storage tanks. Ironically, gasoline leakage from the same tanks is not causing a groundwater contamination problem. Propose two reasons why MTBE is much more prone to contaminate groundwater.
2. The production of chlorofluorocarbons, or CFCs, has been banned by international treaty because of their deleterious effect on the ozone layer. The ozone layer absorbs much of the Sun's dangerous UV radiation before it reaches the Earth's surface. CFCs are extremely stable in the lower atmosphere (one reason why they are so useful), but when they reach the stratosphere they decompose, producing potent catalysts of ozone destruction. Ozone destruction is most evident above Antarctica during the spring, when this region is exposed to the Sun for the first time in months. Dichlorodifluoromethane (CF_2Cl_2) is a typical CFC.
- Hydrochlorofluorocarbons, or HCFCs, have been used as replacements for CFCs that are less ozone-depleting. HCFCs, unlike CFCs, have at least one C–H bond. HCFCs are not less prone than CFCs to decompose in the stratosphere, but there is a pathway by which HCFCs can decompose in the *lower* atmosphere (where they cannot damage ozone) that is not accessible to CFCs. 2,2,2-Trichloro-1,1-difluoroethane (CHF_2CCl_3) is a typical HCFC.
- (a) What is the first step in the decomposition of CFCs in the stratosphere?
 - (b) Propose the first step of a mechanism by which HCFCs decompose in the lower atmosphere.


3. Draw mechanisms for each of the following reactions.




(b) Can you explain the regioselectivity of the first reaction?




(c) An alkylative Birch reduction.




(d) The starting material can react by two pathways. Both pathways give the four-membered ring shown. One pathway gives the ketene as the coproduct; the other gives PhCHO and CO (1:1).




(e)




(f)




(g)




(h)





(i)




(j)




(k)






(l) Note the use of *catalytic* quantities of Bu_3SnH .

(m)







(o) There is no typo in the following reaction.




(aa)




(bb)




(cc)




(dd)




(ee)



4. The following reaction of C_{60} appeared in a respected journal. The reaction requires O_2 .



The authors proposed the following mechanism. C_{60} is an electrophilic compound, and both RC_{60}^{\cdot} radicals and RC_{60}^- anions are quite stable and long-lived species, so the first two steps are perfectly reasonable.



- (a) Using your knowledge of free-radical reactions, determine which if any of the last four steps of this mechanism are unreasonable, and explain why.
- (b) Propose an alternative mechanism for this reaction. The first step in your mechanism should be the same as the one proposed by the authors; subsequent steps may or may not be the same as those proposed by the authors.

Transition-Metal-Mediated and -Catalyzed Reactions

6

6.1 Introduction to the Chemistry of Transition Metals

Many widely used organic reactions require the use of transition metals. You have probably already learned about metal-catalyzed hydrogenations of alkenes and alkynes, dihydroxylation of alkenes using OsO_4 , and the use of lithium dialkylcuprates (Gilman reagents) as “soft” nucleophiles. Although the mechanisms of many of these reactions appear mysterious, in fact they are quite easy to understand (in most cases) using some very basic principles. This chapter discusses some of the typical reactions of transition metals. These principles will then be applied to understanding some of the organic transformations mediated and catalyzed by these metals.


The reactions in this chapter are organized according to the overall transformation achieved. An organization by mechanistic type (insertions, transmetalations, etc.) was considered and rejected. The purpose of this text is to teach the student how to go about drawing a mechanism for an unfamiliar reaction. A student who does not already know the mechanism for a reaction will find it easier to narrow down the possible mechanisms by considering the overall transformation rather than by trying to determine the mechanistic type. An organization by metal (early, middle, or late) was also considered and rejected, because it would obscure the important similarities between the reactions of different metals.

No attempt is made to cover every aspect of organometallic chemistry. Many interesting organometallic reactions, such as the reactions of Cr arene complexes, have been discovered and even investigated extensively but have not been widely adopted by organic chemists for one reason or another. These reactions are not discussed. Moreover, as in previous chapters, questions of stereochemistry are deemphasized in favor of concentration on electron-pushing. The reader is urged to consult any of the excellent textbooks on organometallic chemistry for further coverage of these important topics.







Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_6) contains supplementary material, which is available to authorized users.

6.1.1 Conventions of Drawing Structures


The conventions for drawing organometallic and inorganic compounds differ in subtle ways from those used to draw “ordinary” organic compounds. The most important difference is the way in which bonds are drawn. In organic compounds, one simply does not use a line to connect a bond to an atom. In organometallic and inorganic compounds, however, a line sometimes connects an atom to a σ or a π bond. In this case, the line indicates that the pair of electrons in the σ or π bond is shared with the metal also.



An even more confusing situation arises in complexes in which the electrons in a π system spread over three or more atoms are used to make a bond to a metal. In this case, the usual convention is to use a curved line to indicate the π system and a single line to connect the π system to the metal, regardless of the number of electrons in the π system (the organometallic chemists' convention). However, sometimes the curved line is omitted, and single lines are used to connect the metal to each of the atoms in the π system (the crystallographers' convention). The representation that would make the most sense to organic chemists, in which a single line represents a two-electron σ bond and a dative bond is used to show two-electron bonds between each individual C=C π bond and the metal, is simply never used.

<i>organometallic chemists' convention</i>	<i>crystallographers' convention</i>	<i>organic chemists' convention</i>	<i>number of electrons in bond between metal and π system</i>
			four
			six

Formal charges are usually omitted in inorganic and organometallic complexes. Only the overall charge on the complex is indicated. For example, formal charges are usually not assigned in Lewis acid–base complexes involving transition metals. The acid–base bond is sometimes indicated by an arrow pointing from the ligand to the metal, but more often it is indicated by an ordinary line.



6.1.2 Counting Electrons


The chemistry of any particular metal complex can be understood by examining its *total electron count*, its *number of d electrons*, and the metal's *oxidation state*.

6.1.2.1 Typical Ligands. Total Electron Count

Main group elements like C and S have four valence AOs, one s and three p , and they follow the octet rule (although heavier main group elements can extend their octet). Transition metals, by contrast, have nine valence AOs—one s , five d , and three p , in that order—and they follow the *18-electron rule*. The 18-electron rule is much less rigorous for transition metals than the octet rule is for main-group elements. First, it can be difficult to surround a metal, especially an early metal, with sufficient numbers of substituents to provide 18 electrons to the metal. Second, the valence orbitals of metals are sufficiently extended from the nucleus that the nucleus does not care much about what is going on in its valence shell.

It is more difficult to obtain a count of the total number of electrons around a metal than it is around a main group element. Unlike in main-group compounds, where substituents almost always bring one or two electrons to an atom, substituents (or *ligands*) attached to metals can provide anywhere from one to six electrons to the metal. However, just a few classes of ligands are widely used in organometallic chemistry, and it's not too hard to remember how many electrons each one donates.


- Monovalent groups such as alkyl, RO, H, R_2N , halogen, etc., that are singly bonded to metals are one-electron donors.
- Divalent fragments such as $R_2C=$ (carbenes or alkylidene groups), $RN=$ (imido groups), or $O=$ (oxido groups) that are doubly bonded to a metal are two-electron donors.
- Lewis bases such as R_3N , $RC\equiv N$, H_2O , and R_3P are also two-electron donors, as are carbon monoxide ($:C\equiv O$) and the isoelectronic isocyanides ($:C\equiv NR$). (When CO is attached to a metal, it is called a *carbonyl* group.) The bond between a Lewis basic ligand and the Lewis acidic metal is sometimes called a *dative* bond. Again, note the omission of formal charges.




- The N -heterocyclic carbenes (NHCs) are also Lewis-basic two-electron donors. These carbenes are fairly stable because they have resonance structures that depict them as electron-sufficient amidinium ylides. NHCs make very stable σ bonds to many transition metals; back-bonding from a filled metal d orbital to the allyl cation

π system of the ligand does not seem to be a major factor. **Common error alert:** Chemists have an unfortunate habit of depicting an NHC–metal complex with the coordinated C atom participating only in three bonds, making it appear as if there is an H atom attached to the C atom, even though there is not one there. Some chemists use a curved line to indicate the allylic nature of the ligand, but this representation, although easier to understand at a glance, is less common.


N-heterocyclic carbene resonance structures:




Common depictions of NHC–metal complexes:




- Alkenes and alkynes can also act as Lewis bases toward metals by using the two electrons in their π bonds. Such an interaction is called a π complex. The metal–alkene bond is a σ bond due to its spherical symmetry around the axis formed by the metal and the midpoint of the C=C π bond. Even σ bonds such as the H–H and C–H bonds can act as two-electron donors to metals in this manner, and these compounds are called σ complexes. When a σ complex is formed in an intramolecular fashion, the bond is called an *agostic bond* or *agostic interaction*. Both π and σ complexes can be thought of as two-electron, three-center bonds in which three contributing atomic orbitals comprise a doubly occupied bonding molecular orbital.




- Trivalent fragments such as $\text{RC}\equiv$ (carbyne or alkylidyne group) and $\text{N}\equiv$ (nitride group) that are triply bonded to a metal are three-electron donors.
- The allyl group can be either a one- or a three-electron donor. Imagine a three-electron allyl group as being a one-electron donor through the C–M σ bond and a two-electron donor from its π bond.



- Dienes are four-electron donors. Alkynes are four-electron donors when they use one π bond to form a σ bond and the other π bond to form a π bond to metal orbitals of the proper symmetry. When only two of the three π bonds in a benzene ring interact with a metal, the ring is a four-electron donor.



- The cyclopentadienyl group (C_5H_5 or Cp) is a five-electron donor. Conceptually, one electron is derived from a covalent bond to C, and each of the two π bonds of the group acts as a two-electron donor ligand. In fact, though, the five C atoms of the Cp ring are indistinguishable. Occasionally the Cp group can “slip” and decoordinate one π bond to turn itself into a three-electron donor. Acyclic pentadienyl groups are five-electron donors, also.



Cp group (five-electron donor)

- Benzene rings can act as six-electron donors.
- Ligands with lone pairs, such as RO, R_2N , X, and =O groups, can use their lone pairs to make π bonds to the metal, as in $M-OR \leftrightarrow M=OR$. (Again, formal charges are usually not drawn.) Thus, these groups can be three- (RO, R_2N , X), four- (=O), or even five-electron donors (RO, X), if the metal needs the extra electron density and it has orbitals of the right symmetry to overlap with the donor orbitals.

To calculate the total electron count around a metal, add the number of electrons that each ligand donates to the number of valence electrons that the metal brings, and subtract or add electrons for total charges on the complex. The number of valence electrons brought by a metal is given by its Arabic group number or by its Roman group number plus 2. Thus, Ti is a group 4, a IIA, or a IIB metal, depending on which nomenclature system you use, but it always has four valence electrons.

Another method for determining total electron count treats odd-electron donor ligands (alkyl, Cp, etc.) as anionic, *even-electron* donors. The number of electrons contributed by the metal is calculated from the metal's oxidation state. Both methods give the same answer for total electron count.

Alkenes and alkynes have special characteristics as Lewis base donors. The face-on interaction of the π bond of an alkene with a p or d orbital on the metal


produces a σ bond, as shown in the first of the following structures. This interaction is a simple Lewis acid–base interaction, no different from a lone pair on PR_3 donating to the same orbital. However, if the metal has a pair of electrons in another d orbital, the d orbital can overlap with the empty π^* orbital of the alkene, producing a second, “back-bonding” interaction as shown in the second structure. This second bonding interaction weakens the $\text{C}=\text{C}$ π bond (by pushing electron density into the π^* orbital), but it also strengthens the $\text{M}-\text{C}$ interactions (by increasing the number of electrons residing in delocalized orbitals from two to four). Thus, two resonance structures for alkene–metal complexes can be written, as shown on the right, in one of which (a *metallacyclopropane*), the π bond is gone, and there are *two* $\text{M}-\text{C}$ σ bonds. The total electron count around a metal in an alkene–metal complex is the same regardless of whether the dative resonance structure or the metallacyclopropane resonance structure is drawn.




The preceding pair of resonance descriptions is called the *Dewar–Chatt–Duncanson* model of π bonding. Similar pictures can be drawn for metal–alkyne complexes, regardless of whether the second π bond is acting as a π donor, and for metal–1,3-diene complexes. **Common error alert:** *The metallacyclopropane resonance structure is valid only if the metal has at least two valence electrons available for back-bonding. It should not be drawn for metals with no valence electrons.*



A similar picture can be drawn for σ complexes. H_2 can use the two electrons in its σ bond to form a σ complex with a metal, $\text{M}-(\text{H}_2)$. If the metal has at least two valence electrons, it can back-bond to the σ^* orbital, lengthening and weakening the $\text{H}-\text{H}$ bond until the complex is better described as a dihydride complex $\text{H}-\text{M}-\text{H}$. In fact, a continuum of H_2 complexes of metals has been discovered from one extreme to the other.



CO and RNC ligands can also interact with lone pairs on a metal. A metal carbonyl can thus be thought of as a metallaketene.



You might imagine that a metal with a total electron count of less than 18 displays electrophilic character, but this is not always the case. The 18-electron complex $\text{Pd}(\text{PPh}_3)_4$ is used as a nucleophilic catalyst, but it is actually the 16- or 14-electron complex $\text{Pd}(\text{PPh}_3)_3$ or $\text{Pd}(\text{PPh}_3)_2$ that does the chemistry. (Yes, metals can be nucleophilic!) The Ph_3P groups are too bulky to allow $\text{Pd}(\text{PPh}_3)_4$ to undergo any reactions, and one or two ligands must dissociate before the complex can react.

6.1.2.2 Oxidation State and *d* Electron Count


A second important determinant of the reactivity of a metal is its *oxidation state*. The assumption in calculating a metal's oxidation state is that all groups attached to the metal are more electronegative than the metal, and so all σ bonds are ionic bonds. If both electrons in every σ bond "belong" to the ligand, the metal is left with a charge, and that is its oxidation state. In practice, you can determine the oxidation state by counting the number of *covalent* bonds (not dative ones) to the metal. Starting with the total charge on the complex, add 1 for each R, H, RO, R_2N , X, allyl, and Cp group, add 2 for groups like $\text{R}_2\text{C}=\text{}$, $\text{RN}=\text{}$, and $\text{O}=\text{}$, and add 3 for $\text{N}\equiv$ and $\text{RC}\equiv$, but do not add anything for ligands such as R_3P , CO, H_2O , π bonds, dienes, and arenes, all of which are Lewis bases that form dative bonds to the metal.

Oxidation states may be written in three ways: Fe^{3+} , Fe^{III} , or Fe(III). The first way is not really appropriate for nonionic complexes, so it will not be used in this book. Either of the other ways is fine.

The *d electron count* of the metal is calculated by subtracting the metal's oxidation state from the number of valence electrons (including the two *s* electrons) in its elemental state. The "*d* electron count" is an inorganic chemistry term for "unshared valence electrons." The *d* electron count of a metal has important ramifications for reactivity. For example, one cannot draw metallacyclopropane resonance structures for alkene complexes of d^0 metals. **Common error alert:** Do not confuse total electron count, *d* electron count, and oxidation state with one another. All three characteristics are important to the reactivity of the metal.

The *d* electron count is written as a superscript, e.g., a d^2 complex. The two valence *s* electrons are always counted toward the *d* electron count. Thus, Pd(0) is said to be d^{10} , even though it has eight *3d* valence electrons and two *4s* valence electrons.


In alkene-metal complexes, the oxidation state of the metal in the metallacyclopropane resonance structure is 2 units higher than in the dative resonance structure. In the following example, the metal has two covalent bonds (to the Cp ligands) in the dative resonance structure, but it has *four* covalent bonds in the metallacyclopropane resonance structure.



6.1.3 Typical Reactions


Almost all the reactions of metals can be classified into just a few typical reactions, and the reactions that metals promote in organic chemistry are simple combinations of these typical reactions. If you learn these typical reactions, you will have no trouble drawing metal-mediated mechanisms. The typical reactions of metal complexes are ligand addition/ligand dissociation/ligand substitution, oxidative addition/reductive elimination, insertion/ β -elimination, α -insertion/ α -elimination, σ -bond metathesis (including transmetalations and abstraction reactions), [2 + 2] cycloaddition, and electron transfer.

• *Ligand addition and dissociation* reactions are simple Lewis acid–base reactions, either in the forward direction to make a bond (addition) or in the reverse direction to break a bond (dissociation). Many metal catalysts undergo a dissociation or association reaction to form the actual active species, as in $\text{Pd}(\text{PPh}_3)_4 \rightarrow \text{Pd}(\text{PPh}_3)_3 + \text{PPh}_3$. In an addition (or dissociation), the total electron count of the metal increases (or decreases) by 2, but the d electron count and the oxidation state do not change. Metals also easily undergo *ligand substitution* reactions. These reactions usually proceed in two steps by addition–dissociation or dissociation–addition, rather than in a concerted fashion like an $\text{S}_{\text{N}}2$ reaction.



Electron-flow arrows may or may not be used to show association and dissociation reactions, depending on your taste. They may be especially problematic when trying to depict the association and dissociation of π bonds from a metal. The word “association” or “dissociation” below the arrow often suffices.

The deprotonation of M-H to give M^- and H^+ is one quite common “dissociation” reaction in which the pair of electrons of the bond goes to the *metal*. The metal does not change its total electron count, and its oxidation state decreases by 2. It’s strange to think of a deprotonation as causing a reduction of the metal. The conundrum arises because of the oddities of the language that we use to describe metal complexes. The oxidation state of a complex with a M-H bond is calculated as if the bond were polarized toward H, i.e., $\text{M}^+ \text{H}^-$. Thus, when metal hydrides are deprotonated, it *seems* as if the metal is gaining electrons (from the hydride) that it did not have before.




Of course, the reverse reaction can also occur: protonation of a metal gives a metal hydride in a higher oxidation state.


It is often not clear when or whether ligand addition or dissociation occurs in the course of a metal-mediated or -catalyzed reaction, and in fact knowledge of such details is often not necessary to draw a reasonable mechanism. For this reason, the metal center and its associated ligands are often indicated merely as L_nM or $[M]$.

• *Oxidative addition* and *reductive elimination* are the microscopic reverse of one another. In oxidative addition, a metal inserts itself into an X–Y bond (i.e., $M + X-Y \rightarrow X-M-Y$). The X–Y bond breaks, and M–X and M–Y bonds form. The reaction is called an oxidation because the metal's oxidation state increases by 2 (and its d electron count decreases by 2), but the metal also increases its total electron count by 2, so it becomes less electron-deficient. The apparent paradox that the “oxidation” of a metal results in a larger electron count is an artifact of the language with which we describe compounds.

Oxidative additions can occur at all sorts of X–Y bonds, but they are most commonly seen at H–H (also H–Si, H–Sn, or other electropositive elements) and carbon–halogen bonds. In the oxidative addition of H_2 to a metal, a d orbital containing a lone pair interacts with the σ^* orbital of H_2 , lengthening and breaking the H–H σ bond. The two pairs of electrons from the metal and the H_2 σ bond are used to form two new M–H bonds. C–H bonds can oxidatively add to metals in the same way, and this process, called *C–H bond activation*, is of enormous current interest. Si–H, Si–Si, B–B, and other bonds between electropositive elements undergo oxidative addition, too.




Alkyl halides, pseudohalides like triflates (R–OTf) and phosphates $[R-OP(O)(OEt)_2]$, and other C–X species readily undergo oxidative addition. Oxidative addition is usually fastest for X = I, but not always. Oxidative additions at C–X bonds are fundamentally different from oxidative additions at H–H and C–H bonds. For C(sp^3)–X bonds, the same substitution mechanisms that operate in purely organic systems— S_N2 , $S_{RN}1$, and S_N1 —also operate in organometallic systems. For example, $Pd(PPh_3)_4$ undergoes oxidative addition to CH_3I to give $(PPh_3)_2Pd(CH_3)I$. After dissociation of PPh_3 to give a 16-electron, d^{10} Pd(0) complex, Pd reacts with CH_3I in what is probably a straightforward S_N2 reaction to give the 16-electron, d^8 Pd(II) complex $(PPh_3)_3Pd-CH_3$ and I^- . The I^- then displaces another PPh_3 group to give the final neutral, 16-electron, d^8 Pd(II) complex $(PPh_3)_2Pd(CH_3)I$.



When stereochemically pure 2° alkyl halides undergo oxidative addition to Pd(0), inversion of configuration at C is observed, supporting the S_N2 mechanism.


Oxidative addition can also occur at C(sp²)-X bonds (i.e., at vinyl and aryl halides). It always occurs with retention of configuration about the double bond. Oxidative addition at C(sp²)-X obviously cannot proceed by an S_N2 mechanism. The S_{RN}1 mechanism is a possibility. Another possibility is that the Pd coordinates first to the π bond of, say, vinyl iodide, to form a π complex. The metallacyclopropane resonance structure of the π complex can be drawn. An electrocyclic ring opening of the metallacyclopropane (Chap. 4) can then occur. Cleavage of the Pd-C bond occurs concerted with departure of I⁻ to give a new cationic Pd-vinyl complex. The ring opening is torquoselective: the alkyl terminus rotates so that the electrons in the breaking Pd-C bond are anti to the I atom. When I⁻ associates with the Pd, the overall result is oxidative addition with retention of configuration.



Any metal with a *d* electron count of *d*² or greater can undergo oxidative addition, but 18-electron complexes do not undergo oxidative addition reactions. Oxidative addition is very common for late metals like Pd, Pt, Ir, Rh, and the like.


Common error alert: *d*⁰ Metals cannot undergo oxidative addition reactions.

Reductive elimination, X-M-Y → M + X-Y, is the microscopic reverse of oxidative addition. This reaction is usually most facile when the X-Y bond is strong (e.g., H-Ti-Bu → Bu-H + Ti). Not as much is known about the mechanism of reductive elimination as is known about oxidative addition. It is known that the two groups must be adjacent to one another in the metal's coordination sphere. In square planar Pd complexes [(R₃P)₂PdR₂], if the R groups are forced to be trans to one another, reductive elimination does not take place. Reductive elimination is accompanied by a decrease in the total electron count around the metal, a decrease in the oxidation state, and an increase in the *d* electron count.




• *Insertions* and *β-eliminations* are also the microscopic reverse of each other. In an *insertion*, an A=B π bond inserts into an M-X bond (M-X + A=B → M-A-B-X). The M-X and A=B bonds break, and M-A and B-X bonds form. Insertion is usually preceded by coordination of the A=B π bond to the metal, so it is sometimes called *migratory insertion*. In an insertion, an M-X bond is replaced with an M-A

bond, so there is no change in oxidation state, d electron count, or total electron count. However, a new σ bond is formed at the expense of a π bond. The nature of the reaction requires that the new C–M and C–H bonds form to the same face of the alkene, resulting in syn addition. The reaction of a borane (R_2BH) with an alkene to give an alkylborane is a typical insertion reaction that you have probably seen before.




Both early- and late-metal complexes undergo insertions. The likelihood of insertion, though, depends on the nature of X, A, and B. When X is H, as in metal hydrides such as B–H, Zr–H, and Pd–H, insertion is very facile. Insertions of C=C π bonds into M–C and M–H bonds are very important, as will be seen soon. On the other hand, insertions where X is halogen and alkoxy are much rarer. The A=B π bond may be C=C, C=N, C=O, or any other.


β -Elimination is the microscopic reverse of insertion. Like an insertion, a β -elimination causes no change in the oxidation state, d electron count, or total electron count of the metal. By far the most common β -elimination is the β -hydride elimination, in which $M-A-B-H \rightarrow M-H + A=B$. The β -hydride elimination is the bane of the organometallic chemist's existence, as it causes many metal-alkyl bonds to be extremely labile. β -Alkoxy and β -halide eliminations are also known, as in the reaction of $BrCH_2CH_2Br$ with Mg.




Insertions are generally thermodynamically favorable, providing a new σ bond at the expense of a π bond. β -Eliminations are very fast reactions, however, so insertions are readily reversible even when they are thermodynamically favorable. For example, when $Cp_2Zr(H)Cl$, a 16-electron d^0 complex, is allowed to react with an internal alkene, the alkyl group in the product is 1° , not 2° ! A rapid series of insertions and β -eliminations takes place until the 1° alkyl–Zr bond, which is lowest in energy, forms. None of the intermediates are observed. Alkylboranes can undergo this reversible series of reactions, too, albeit at much higher temperatures.




Carbenoid species such as CO and RNC also undergo insertions and eliminations (e.g., $M-R + CO \rightleftharpoons M-C(O)-R$). These are 1,1-insertions, as opposed to the more common 1,2-insertions. Again, there is no change in total electron count or oxidation state of the metal, except transiently as CO coordinates to the metal before insertion. The insertion of CO into a M–C bond is a key step in many important reactions. Again, the insertion is reversible.




• α -Insertions and α -eliminations are considerably less common than migratory insertions and β -eliminations. In an α -insertion, a ligand on a metal migrates to an adjacent atom that is doubly bound to the metal, and the electrons of the π bond migrate to the metal (i.e., $X-M=Y \rightleftharpoons \ddot{M}-Y-X$). In an α -insertion, in contrast to its β -relative, the total electron count around the metal decreases by 2, the oxidation state decreases by 2, and the d electron count increases by 2. The opposite occurs in an α -elimination. α -Insertions and α -eliminations are most commonly seen in third-row transition metals, which are more likely to form multiple bonds.



• *Sigma-bond metathesis* reactions involve the swapping of M–X and Y–Z σ bonds to give M–Z and X–Y (or M–Y and X–Z). The reaction is concerted, involving a four-center transition state. No change in oxidation state or total electron count occurs, and for this reason the reaction is seen especially often among early, d^0 transition metals. (In metals with a d^2 or greater valence electron count, a two-step oxidative addition–reductive elimination pathway can be invoked to explain the same overall reaction.) The group that is transferred to the metal is often H, because its nondirectional s orbital provides better overlap in the four-center transition state, although it may also be Si or another element. The group that is transferred from the metal may be almost anything, including C and O.




Transmetalations, in which M–X and M'–Y swap partners to give M–Y and M'–X, are a special kind of σ -bond metathesis reaction. Sometimes transmetalations are quite obviously thermodynamically favorable, as in $2 \text{ BuLi} + \text{Cp}_2\text{ZrCl}_2 \rightarrow \text{Cp}_2\text{ZrBu}_2 + 2 \text{ LiCl}$, but sometimes not, as in $(\text{Ph}_3\text{P})_2\text{Pd}(\text{Ph})\text{I} + \text{R-SnBu}_3 \rightarrow (\text{Ph}_3\text{P})_2\text{Pd}(\text{Ph})\text{R} + \text{I-SnBu}_3$. Transmetalations involving relatively electronegative metals like Sn are not very well understood, but transmetalations from electropositive elements such as Li or Mg to transition-metal halides can be thought of as simple $\text{S}_{\text{N}}2$ displacements of the halides.




Hydride abstraction reactions are four-center, concerted processes that are closely related to σ -bond metathesis. β -Hydride abstraction occurs most often in d^0 metal dialkyl complexes such as Cp_2ZrEt_2 . In this reaction, one Et group uses the electrons in the Zr–Et bond to make a new bond to the β -hydrogen on the other Et group. The electrons in the breaking C–H bond are then used to form a new bond from C of the breaking bond to Zr. The products are an alkane and a metallacyclopropane; the latter can also be described as an alkene–metal π complex. No change in oxidation state occurs if the product is considered to be in its metallacyclopropane oxidation state, although, as discussed earlier, the metals in metallacyclopropanes can be considered to be in a lower oxidation state in their alternative, dative resonance structures. The products of β -hydride abstraction are


the same as the products of a two-step, β -hydride elimination–reductive elimination sequence, and experimental evidence is required to distinguish between the two mechanistic pathways.




α -Hydride abstraction reactions, which produce a metal=C π bond, occur most often among third-row transition metals, which readily form multiple bonds to C. A dialkylmetal complex (R–M–CH₂R') loses alkane RH to give an alkylidene complex (M=CHR') in a concerted, four-center mechanism. No change in metal oxidation state occurs, and the metal may have any number of *d* electrons.



Hydride abstraction reactions that form four-membered or larger metallacycles are usually called *concerted metallation–deprotonation* reactions. These reactions are often driven by both steric compression in the starting complex and increased entropy among the products. Again, no change in metal oxidation state occurs, and the metal may have any number of *d* electrons.



• The [2 + 2] cycloaddition (Chap. 4) is another typical reaction of metals. The reaction is quite common among both early and late metals that feature M=C, M=N, or M=O double bonds. The reaction may be preceded by coordination of the alkene π bond to the metal. No change in oxidation state occurs in [2 + 2] cycloadditions. [2 + 2] Retrocycloadditions are also seen.




- Metals also undergo one-electron transfer reactions (Chap. 5).


6.1.4 Stoichiometric Versus Catalytic Mechanisms

Whether a reaction requires stoichiometric or catalytic quantities of a transition metal has a strong bearing on how one draws a mechanism for the reaction. The mechanism of a reaction that requires stoichiometric quantities of the metal can be written in a linear fashion like a polar or pericyclic mechanism. However, the mechanisms of metal-catalyzed reactions are usually drawn in a circular fashion, showing how the original metal species is regenerated at the end of each catalytic cycle. Whether a mechanism is catalytic or stoichiometric in metal is usually clear from the reaction conditions.

A stoichiometric reaction mechanism:



A catalytic reaction mechanism:



Because it is not the case that every line represents exactly two electrons in a drawing of an organometallic or inorganic compound, it follows that you cannot apply the electron-flow arrow convention for showing the movement of electrons unambiguously when you draw reaction mechanisms involving transition metals. For this reason, in mechanisms involving transition metals, the name of each individual mechanistic step (insertion, transmetalation, oxidative addition, etc.) is indicated in place of electron-flow arrows. You may use electron-flow arrows to show electron movement in some steps if you wish, but it is more important for you to name every step.

Even more than in traditional areas of organic chemistry, it is often possible to draw more than one mechanism for transition-metal-mediated and -catalyzed reactions. One reason is that the mechanisms of transition-metal-mediated and -catalyzed reactions have not been investigated as closely or for as long a time as those of purely organic reactions, so less is known about them. Another reason is that because multiple oxidation states and coordination levels are tolerated by transition metals, more than one mechanism often operates in a single flask, and seemingly insignificant changes in solvent or ligand can sometimes alter the mechanism.


Organometallic and inorganic catalysts are often classified as *homogeneous* or *heterogeneous*. These two terms simply mean *soluble* or *insoluble*. Homogeneous catalysts are easier to study and often have more predictable behavior than heterogeneous catalysts. Heterogeneous catalysts tend to be used more in large-scale industrial synthesis. The first catalysts to be discovered for many of the reactions described in this chapter were heterogeneous. Afterwards, homogeneous catalysts were developed and used both to clarify the mechanism of the reaction and to increase the scope of the reaction.

6.2 Addition Reactions

6.2.1 Late-Metal-Catalyzed Hydrogenation and Hydrometallation (Pd, Pt, Rh)

One of the first metal-catalyzed reactions learned by organic chemistry students is the Pd-catalyzed hydrogenation of alkenes and alkynes. The reaction is generally stereospecifically *syn* (i.e., the two H atoms add to the same face of the π bond). A wide variety of catalysts can be used for this reaction: Pd metal supported on activated C, Pd poisoned by Pb or Ba salts (Lindlar catalyst), Pd(OH)₂, PtO₂, Rh metal supported on alumina, Wilkinson's catalyst, and Ru–phosphine complexes are just some examples. For a long time, the mechanisms of the heterogeneous hydrogenations, those reactions in which the metal did not dissolve in the solution, were considered quite mysterious, but with the advent of homogeneous catalysts like Wilkinson's catalyst, it became possible to study the mechanisms in detail.

Consider the reaction of 2,3-dimethyl-2-butene with H₂ catalyzed by Pd/C. Two new C–H bonds are made, and a C=C π bond breaks. The fact that the addition is stereospecifically *syn* suggests that an insertion reaction is occurring. The Pd metal is in the (0) oxidation state (i.e., d^{10}), so it can react with H₂ by an oxidative addition reaction to give a new compound with two Pd–H bonds. At this point, Pd is in the (II) oxidation state. Coordination and insertion of the alkene into one of the Pd–H bonds gives Pd–C and C–H bonds. Finally, reductive elimination gives the product and regenerates Pd⁰, which begins the catalytic cycle anew.




Note that electron-flow arrows are typically *not* used to show electron flow in each mechanistic step. However, the catalytic cycle is explicitly drawn, and every step is one of the typical reactions of metals.


Every late-metal hydrogenation catalyst, whether homogeneous or heterogeneous, probably uses exactly the same catalytic cycle, although some catalysts, particularly sterically encumbered ones such as Wilkinson's catalyst, require that ligand dissociation or substitution occur before the catalytic cycle gets underway. In the case of metals supported on solids such as activated C, silica, and alumina, the support may participate in the reaction in ways that need not concern you here.

In the hydrogenation of unsymmetrical π bonds like $R_2C=O$ (or $R_2C=NR$), insertion into the M–H bond can occur to give either H–M–O–CHR₂ or H–M–CR₂–OH. Either complex can then undergo reductive elimination to give the alcohol product. On first glance the M–O–CHR₂, with its metal–oxygen bond, seems more favorable, but it happens that the strengths of bonds of carbon and oxygen to late metals like Ru and Pd are about the same. Either mechanism may be operative in any particular reaction.

Formic acid and 1,4-cyclohexadiene are sometimes used as alternative H₂ sources in hydrogenation and hydrogenolysis reactions. Protonation of Pd(0) by formic acid and association of the formate counterion gives the oxidative addition product H–Pd(II)–O₂CH. β -Hydride elimination then gives H–Pd(II)–H and CO₂. Similarly, coordination of Pd(0) to the π bond of 1,4-cyclohexadiene and oxidative addition of Pd to the allylic C–H bond gives cyclohexadienyl–Pd(II)–H, and, after allylic migration, β -hydride elimination gives benzene and H–Pd(II)–H. In both cases, β -hydride elimination may in principle take place before or after insertion of the alkene into the Pd–H bond. Certain classes of hydrogenations proceed better using these H₂ sources.




(a) protonation; (b) coordination; (c) β -hydride elimination.




(a) coordination; (b) oxidative addition; (c) allylic migration; (d) β -hydride elimination.

Late-metal complexes of Pd, Pt, and Rh can also catalyze hydrosilylation, hydrostannylation, hydroboration, and diborylation reactions of π bonds. Both C=C and C=O bonds may be hydrosilylated or hydroborated, whereas hydrostannylation is usually carried out only on C=C bonds. (Some boranes add to C=O and C=C bonds in the absence of catalyst, but less reactive ones, such as catecholborane [(C₆H₄O₂)BH] require a catalyst. Moreover, the metal-catalyzed reactions sometimes display different selectivities from the uncatalyzed variants.) The mechanisms of all these reactions are the same as hydrogenation, except that oxidative addition of H-H is replaced by oxidative addition of an R₃Si-H (R₃Sn-H, R₂B-H, R₂B-BR₂) bond.

Problem 6.1 Draw a mechanism for the following diborylation reaction.



After oxidative addition of an unsymmetrical σ bond (E-H) to the metal, an unsaturated compound can insert into either the M-E or the M-H bond. In some cases, such as the hydrosilylation of carbonyl compounds, the π bond of the substrate inserts into the M-E bond, while in others, insertion of the π bond of the substrate into the M-H bond occurs faster. In any case, either pathway gives the same product after reductive elimination.




Problem 6.2 Draw the mechanism for the hydrosilylation of acetophenone in which insertion of the C=O π bond into the Rh-H σ bond (instead of the Rh-Si bond) occurs. Your mechanism should give the same product as the one above.

Many metal complexes with chiral ligands such as phosphines, phosphites, or imidates will catalyze asymmetric hydrogenations, hydrosilylations, and the like. Extremely high enantioselectivities have been achieved with a wide variety of substrates.

All the steps in the catalytic cycles just illustrated are reversible. In principle, a M–H species can undergo a series of insertions and β -hydride eliminations to give a product whose π bond has been isomerized to a different position. In fact, this is an occasional side reaction in Pd-catalyzed hydrogenations.

6.2.2 Hydroformylation (Co, Rh)

Rh and Co complexes catalyze *hydroformylation*, the addition of H_2 and CO to a $C=C$ π bond to give an aldehyde ($H-C-C-CHO$). Hydroformylation was one of the first organometallic reactions to be used industrially. The hydroformylation of propene is used to make butyraldehyde, which is hydrogenated to give butanol, a widely used solvent. The original reaction was carried out using a Co catalyst in molten Ph_3P , but today the reaction is carried out under much milder conditions. The mechanism of hydroformylation is nearly the same as the mechanism of hydrogenation that was discussed earlier. Oxidative addition of H_2 to the metal(I) complex occurs to give a metal(III) dihydride. Insertion of an alkene occurs next to give an alkylmetal(III) complex. Steps not found in the hydrogenation mechanism occur next: CO coordinates to the metal and then inserts into the M–C bond to give an acylmetal(III) compound. Finally, reductive elimination gives the product and regenerates the metal(I) complex.




(a) oxidative addition; (b) coordination; (c) insertion; (d) reductive elimination.

Insertion of propene into the M–H bond can give two isomers, one with a 1° alkyl–metal bond (as shown) and one with a 2° alkyl–metal bond. The first isomer leads to *n*-butyraldehyde, whereas the second isomer leads to isobutyraldehyde. The first isomer predominates under all conditions, but the isomeric ratio is dependent on the metal, the temperature, and the ligands. As the technology has improved, higher and higher ratios in favor of *n*-butyraldehyde have been obtained.


The mechanism of the *silylformylation* reaction, in which silanes (R_3Si-H) are substituted for H_2 , is exactly the same as the mechanism for hydroformylation.

Problem 6.3 Draw a mechanism for the following silylformylation reaction.




6.2.3 Hydrozirconation (Zr)

In hydroboration, a boron hydride (R_2BH) adds across an alkene ($R'CH=CH_2$) to give $R'CH_2CH_2BR_2$. The 16-electron, d^0 Zr(IV) complex $Cp_2Zr(H)Cl$, popularly known as *Schwartz' reagent*, undergoes a closely related reaction. The mechanism involves coordination of an alkene to the electrophilic Zr center followed by migratory insertion of the alkene into the Zr–H bond. The reaction proceeds for alkynes also, by exactly the same mechanism.




The alkylzirconium(IV) complexes produced by hydrozirconation are usually used as reagents in further transformations. The C–Zr bond is moderately nucleophilic at C, so hydrolysis cleaves the C–Zr bond and gives an alkane, whereas treatment with an electrophilic halogen such as NBS or I_2 gives an alkyl halide. Addition of CO or an isocyanide (RNC) results in the insertion of a one-carbon unit into the Zr–C bond; hydrolysis then gives the corresponding aldehyde or imine, and halogenation gives the acyl halide or nitrile. Transmetalation of the C–Zr bond to another metal such as Cu, Zn, Pd, etc., may also occur, and these alkyl- or alkenylmetal compounds can be used to carry out Pd-catalyzed cross-coupling reactions with organic halides (*vide infra*) and the like. All these reactions (except CO insertion) are usually drawn as σ -bond metathesis processes, although not much mechanistic work has been carried out.



(a) σ -bond metathesis; (b) insertion; (c) transmetalation.

As mentioned earlier, hydrozirconation of *internal* alkenes gives *terminal* alkylzirconium compounds. The isomerization occurs so quickly that no intermediates are observed. The mechanism of the reaction is a series of insertions and β -hydride eliminations.




Problem 6.4 When internal alkenes are hydrozirconated, the Cp₂ZrCl group does not migrate to the terminus of the chain. Why not?

6.2.4 Alkene Polymerization (Ti, Zr, Sc, and Others)


The polymerization of ethylene to give polyethylene is one of the most important industrial reactions in the world. A free-radical process is most commonly used to execute the polymerization of ethylene. A free-radical process can also be used to execute the polymerization of higher alkenes, but the yields are not as good, and questions of stereoselectivity and regioselectivity arise. The polymerization of higher alkenes such as propene, styrene, and butadiene is instead usually carried out using early metal catalysts called *Ziegler–Natta catalysts*. The first Ziegler–Natta catalysts were heterogeneous catalysts that consisted of Ti, Zr, or other early metal catalysts supported on surfaces. Later, homogeneous catalysts were developed that allowed chemists to carry out studies on the mechanism of polymerization. More recently, the efficiency of the homogeneous catalysts has improved to the point to which they are now competitive with the heterogeneous catalysts in terms of cost, at least for the higher value polymers.

The most widely studied homogeneous Ziegler–Natta catalysts are the group 4 metallocenes, especially zirconocene. Zirconocene dichloride (Cp₂ZrCl₂) is an air- and moisture-stable 16-electron, *d*⁰ complex. Its derivative Cp₂ZrMe₂ is a pre-catalyst for the polymerization of alkenes. The pre-catalyst is made active by the addition of a Lewis acid; methylalumoxane, (MeAlO)_{*n*}, prepared from the addition of one equivalent of water to Me₃Al, is commonly used, as is B(C₆F₅)₃. The Lewis acid serves to abstract Me[−] from Cp₂ZrMe₂ to give the 14-electron, *d*⁰ complex Cp₂ZrMe⁺, the active catalyst.

The catalytic cycle for alkene polymerization, the *Cossee mechanism*, is extremely simple. Coordination of the alkene to Cp₂ZrR⁺ is followed by insertion to give a new complex Cp₂ZrR⁺. No change in the oxidation state of Zr occurs in either of these steps.




There are several mechanisms for termination of the growing polymer chain. One common chain termination step is β -hydride elimination to give Cp_2ZrH^+ and the polymer with a terminal double bond. When the polymerization is carried out under H_2 , a σ -bond metathesis can take place to give the saturated polymer and Cp_2ZrH^+ .




Group 4 metallocene complexes in which the Cp groups are substituted with alkyl or other groups are also effective in the reaction. The Cp groups can even be replaced with other five-electron donors such as RO groups (using their two lone pairs to make π bonds to the metal) and even three-electron donors like R_2N groups. Group 3 and lanthanide complexes are also widely used to study and carry out alkene polymerization reactions. Polymerizations using any of these d^0 metals proceed by the mechanism shown for Cp_2ZrMe^+ .


An alternative mechanism for alkene polymerization, the *Green mechanism*, has been demonstrated for the 12-electron d^2 Ta(III) complex $(\text{Me}_3\text{P})_2\text{I}_2\text{TaCH}_2\text{R}$. α -Hydride elimination gives a Ta(V) complex ($\text{H}-\text{Ta}=\text{CHR}$). [2 + 2] Cycloaddition of the alkene with this alkylidene complex gives a Ta(V) tantalacyclobutane, and reductive elimination gives the starting catalyst with a chain extended by two C atoms. The Green mechanism requires an increase in the oxidation state of the metal, and for this reason, d^0 metals cannot polymerize alkenes by the Green mechanism.



A number of other one-atom transfer reactions are mechanistically similar to the Rh- and Cu-catalyzed cyclopropanations. For example, chiral Mn(II) salen complexes are widely used to catalyze the *Jacobsen* or *Jacobsen–Katsuki epoxidation* of alkenes. The oxidant can be NaOCl (bleach), $\text{PhI}=\text{O}$, or another source of electrophilic O. Salen (salicylaldehyde ethylenediamine) is a dianionic, eight-electron, tetradentate ligand that resembles heme or porphyrin. A mechanism very similar to cyclopropanation can be drawn for the *Jacobsen* epoxidation. Addition of ClO^- (for example) to the (salen)Mn(II) complex gives an anionic Mn(II) *ate* complex (one in which the metal has a formal negative charge), and displacement of Cl^- by a lone pair on Mn gives a Mn(IV) oxo complex ($\text{Mn}=\text{O}$). Metal oxides are known to undergo $[2 + 2]$ cycloadditions with alkenes, so a $[2 + 2]$ cycloaddition of the alkene to the oxo complex to give a Mn(IV) metallaoxetane could occur next. Reductive elimination would give the epoxide and regenerate the catalyst.




Ugly facts, unfortunately, sometimes invalidate a beautiful mechanism. The *Jacobsen* epoxidation sometimes proceeds with loss of configurational purity of acyclic alkenes. This feature of the reaction can be explained by invoking radicals. Homolysis of the Mn–C bond in the manganooxetane intermediate can give a Mn(III) 1,4-diradical complex, and attack of the alkyl radical on O with displacement of Mn(II) would give the epoxide and regenerate the catalyst.




There still exists a problem with the mechanism: the square planar geometry of the salen ligand is unlikely to allow both a Mn–O and a Mn–C bond on the same face of the complex. An alternative mechanism that does not involve a Mn–C bond can be proposed. Electron transfer from the alkene to the Mn(IV) oxo complex might give a Mn(III) radical anion and an organic radical cation. Addition of the oxide to the cation would then give the same Mn(III) 1,4-diradical seen before.

Whether or not a manganaoxetane intermediate actually occurs in the Mn-catalyzed epoxidation of alkenes is unclear.




The O atom source can be replaced with a source of NR such as $\text{PhI}=\text{NTs}$, and in this case, an aziridination reaction is catalyzed. The catalyst is usually a Cu(II) complex. When the complex is chiral, asymmetric aziridination can be achieved.


Problem 6.6 Draw a reasonable mechanism for the following reaction. You may find it useful to draw $\text{PhI}=\text{NTs}$ in an alternative resonance form.



The *Sharpless epoxidation* proceeds by a completely different mechanism from these reactions. This asymmetric O-transfer reaction uses catalytic amounts of $\text{Ti}(\text{O}-i\text{-Pr})_4$ and diethyl (+)- or (-)-tartrate to catalyze the epoxidation of allylic alcohols by $t\text{-BuOOH}$. The enantioselectivities are usually very good.




The metal acts essentially as a Lewis acid in this reaction. The terminal O atom of $t\text{-BuOOH}$ is made more electrophilic by coordination of both its O atoms to a tartrate-allylic alcohol-Ti complex, and the terminal O atom is then transferred selectively to one enantioface of the nucleophilic $\text{C}=\text{C}$ π bond. No change in Ti oxidation state or ligand count occurs. After the O atom transfer, a series of ligand substitution reactions regenerates the active species.




6.2.6 Dihydroxylation and Aminohydroxylation of Alkenes (Os)


When an alkene is treated with OsO_4 , an *osmate ester* containing two new C–O bonds is formed. The osmate ester is hydrolyzed, usually with aqueous NaHSO_3 , to give a 1,2-diol. The overall *dihydroxylation* reaction is stereospecifically syn.




There are two major contenders for the mechanism of osmate ester formation. One is a one-step, [3 + 2] cycloaddition between the alkene and OsO_4 to give the osmate ester. The other is a two-step mechanism: the alkene and the OsO_4 undergo a [2 + 2] cycloaddition to give an osmaoxetane, and then the osmaoxetane undergoes α -insertion to give the osmate ester. Which mechanism is in fact operative remains controversial. In any case, the metal is reduced from Os(VIII) to Os(VI) upon osmylation. The hydrolysis of the osmate ester proceeds by simple ligand substitution reactions. The NaHSO_3 , a mild reducing agent, facilitates ligand substitution by reducing the Os further.



OsO_4 can catalyze the dihydroxylation of alkenes in the presence of a stoichiometric oxidant and water. The catalytic reaction is valuable because OsO_4 is very expensive and extremely toxic. The catalytic version also allows one to use the nonvolatile Os(VI) salt $\text{K}_2\text{OsO}_2(\text{OH})_4$ in place of the volatile Os(VIII) complex OsO_4 .




The mechanism of the catalytic osmylation is as follows. $\text{K}_2\text{OsO}_2(\text{OH})_4$ is in equilibrium with $\text{OsO}_2(\text{OH})_2$, and the latter complex is converted to OsO_4 by the stoichiometric oxidant. Addition of OsO_4 to the alkene by one of the mechanisms discussed above then gives an osmate(VI) ester, and water hydrolyzes the osmate ester in a ligand substitution process to regenerate $\text{OsO}_2(\text{OH})_2$. Stoichiometric oxidants include amine oxides R_3NO such as *N*-methylmorpholine *N*-oxide (NMO) and transition-metal salts such as potassium ferricyanide, $\text{K}_3\text{Fe}(\text{CN})_6$. When the stoichiometric oxidant is NaIO_4 , the diol is subsequently cleaved to two carbonyl compounds in a process that is an alternative to ozonolysis.




Problem 6.7 Propose a mechanism by which the oxidation of $\text{OsO}_2(\text{OH})_2$ to OsO_4 by R_3NO may occur. Hint: The OsO_4 product contains the O atom derived from the amine oxide.

OsO_4 -mediated dihydroxylation is greatly accelerated by amines. When an alkene is combined with a catalytic amount of a chiral amine, a catalytic amount of OsO_4 or $\text{K}_2\text{OsO}_2(\text{OH})_4$, and stoichiometric amounts of an oxidant (usually NMO or $\text{K}_3\text{Fe}(\text{CN})_6$) and H_2O , catalytic asymmetric or *Sharpless dihydroxylation* occurs. The chiral amine- OsO_4 complex adds preferentially to one face of the alkene over the other, but the mechanism of the dihydroxylation reaction is not fundamentally changed. The amine is usually a derivative of dihydroquinine (DHQ) or dihydroquinidine (DHQD), and exotic abbreviations such as $(\text{DHQD})_2\text{PHAL}$ are commonly used for these compounds. The mixture of reagents required for Sharpless dihydroxylation is commercially available as AD-mix- α or AD-mix- β .



Chiral amines and $\text{K}_2\text{OsO}_2(\text{OH})_4$ are also used to catalyze the *Sharpless asymmetric aminohydroxylation*. The stoichiometric oxidant in aminohydroxylation is a deprotonated *N*-haloamide, whose mechanistic behavior is very similar to NMO. The reaction proceeds by a mechanism essentially identical to that of Sharpless dihydroxylation.


Problem 6.8 Draw a mechanism for the following Sharpless aminohydroxylation.




KMnO_4 can also dihydroxylate alkenes, particularly electron-poor ones. More electron-rich alkenes may be oxidized further to the dicarbonyl compound. KMnO_4 can also oxidize alkylbenzenes to arylcarboxylic acids. The mechanism of the latter reaction remains quite obscure.

6.2.7 Nucleophilic Addition to Alkenes and Alkynes (Hg, Pd)

You may remember that the acid-catalyzed addition of H_2O to alkenes is usually a difficult reaction to carry out because of the side reactions that can occur under the strongly acidic conditions required for the reaction. However, in the presence of Hg(II) salts such as HgCl_2 , nucleophiles such as H_2O add readily to alkenes to give organomercury compounds. The C–Hg bond can then be converted to a C–H bond by the addition of NaBH_4 .




The alcohol is nucleophilic, so the alkene must be made electrophilic. The HgCl_2 first coordinates to the alkene to form a π complex. The coordination of the Hg(II) makes the alkene electrophilic by drawing electron density away from the carbons. (In principle, one could draw a metallacyclopropane resonance structure for the π complex, but in this resonance structure Hg would be in the (IV) oxidation state, and Hg(IV) is a high-energy oxidation state.) The coordination weakens the C=C π bond and makes its C atoms electrophilic. The nucleophile then adds to one of the C atoms of the π complex, and the electrons from the C=C π bond move to form a σ bond between Hg(II) and the other C to give a stable, isolable organomercury compound.



An alternative mechanism begins with formation of an O–Hg bond. Insertion of the C=C π bond into the O–Hg bond could then follow.


Note how the curved arrow formalism is not well suited to show the movement of electrons in the nucleophilic addition step.

The second part of the reaction proceeds by a free-radical chain mechanism. First, the NaBH_4 converts RHgCl to RHgH by nucleophilic substitution.




RHgH then undergoes free-radical decomposition to give RH and $\text{Hg}(0)$. (Yes, a little ball of mercury appears at the bottom of the flask at the end of the reaction!) The decomposition of RHgH is initiated by R–Hg σ -bond homolysis. The alkyl radical thus obtained ($\text{R}\cdot$) abstracts $\text{H}\cdot$ from H–Hg–R to give R–Hg(I) , and homolysis of the R–Hg(I) bond gives $\text{Hg}(0)$ and the chain-carrying species. Although in the particular example shown, the alkyl radical $\text{R}\cdot$ merely abstracts $\text{H}\cdot$

from the H–Hg bond, in other substrates, R· may undergo other typical free-radical reactions such as intramolecular addition to a π bond.




Mercury-mediated reactions of alkenes have largely been superseded by other, more efficient, less toxic procedures.


Problem 6.9 Draw a reasonable mechanism for the following reaction.



The addition of H_2O to alkynes is catalyzed by $\text{Hg}(\text{II})$ under acidic conditions. (The uncatalyzed reaction is extremely difficult to carry out due to the instability of alkenyl cations.)




The mechanism begins the same way as the Hg-mediated nucleophilic addition to alkenes. In the first step, an electrophilic π complex forms between the alkyne and $\text{Hg}(\text{II})$. Water adds to one of the C atoms of the π complex in Markovnikov fashion to give a 2-hydroxy-1-alkenylmercury(II) compound, a Hg-containing enol, which is protonated on the C bearing the Hg atom to give a carbocation on the neighboring C atom. Fragmentative loss of $\text{Hg}(\text{II})$ then occurs to give a metal-free enol, which tautomerizes to give the ketone product.



Palladium salts also promote the addition of nucleophiles to alkenes and alkynes. The Pd-catalyzed additions of nucleophiles to alkynes, which is useful for intramolecular cyclizations such as the isomerization of 2-alkynylphenols to benzofurans, proceeds by exactly the same mechanism as does the Hg-catalyzed reaction. However, the Pd-catalyzed additions of nucleophiles to alkenes takes the course of *substitution* rather than *addition* because alkylpalladium complexes are unstable toward β -hydride elimination. The Pd-catalyzed nucleophilic substitutions of alkenes are discussed later in this chapter.


Problem 6.10 Draw a mechanism for the Pd-catalyzed cyclization shown.



6.2.8 Conjugate Addition Reactions (Cu)

Compounds containing a C–Cu bond undergo conjugate addition to α,β -unsaturated carbonyl compounds, especially ketones. A wide variety of Cu-containing reagents undergo the reaction, including RCu , R_2CuLi , $\text{R}_2\text{Cu}(\text{CN})\text{Li}_2$, and others. Different types of reagents are useful for different reactions; careful optimization of conditions is often required.


The mechanism by which Cu compounds undergo conjugate additions has been highly controversial. The mechanism almost certainly changes based on the stoichiometry of the Cu species, the presence of other Cu-bound ligands, the counterion, the solvent, additives, and of course the substrate. Electron transfer steps have been implicated. Chemists' understanding of the mechanism is further complicated by a lack of information about the true nature of the Cu species. A very simple picture of the conjugate addition of Me_2CuLi to an enone has the 16-electron Cu species coordinate to the alkene to make an 18-electron species. Migratory insertion of the alkene into the Me–Cu bond and dissociation of neutral MeCu then give the product enolate. The enolate is sometimes trapped in situ by Me_3SiCl (which probably participates in the reaction mechanism) or an alkyl halide. The MeCu coproduct does not usually participate in further reactions.



(a) coordination; (b) insertion; (c) dissociation.

In the presence of a catalytic amount of a Cu(I) salt, Grignard reagents add exclusively to the β -carbon of α,β -unsaturated carbonyl compounds. The reaction proceeds via transmetalation of the Grignard reagent (RMgX) with CuX to give either RCu or R_2Cu^- . The alkylcopper compound undergoes conjugate addition to the enone as discussed above. Transmetalation of the Cu enolate with RMgX gives the Mg enolate and completes the catalytic cycle.


Problem 6.11 Propose a mechanism for the following Cu-catalyzed conjugate addition.





6.2.9 Reductive Coupling Reactions (Ti, Zr)

The group 4 metals, especially Ti and Zr, are most stable in their (IV) oxidation states. In their (II) oxidation states, they act as reducing agents, but in a very specific way. They use the two excess electrons to create a new C–C bond between two $\text{C}=\text{X}$ or $\text{C}\equiv\text{X}$ species to give a new $\text{X}-\text{C}-\text{C}-\text{X}$ or $\text{X}=\text{C}-\text{C}=\text{X}$ compound. (X may be N, O, or C.)

The reductive coupling of two carbonyl compounds using reduced Ti reagents is called *McMurry coupling*. The products may be 1,2-diols or alkenes.




Many Ti reagents (e.g., $\text{TiCl}_3/\text{LiAlH}_4$, TiCl_3/Zn , etc.) have been used for this reaction. The nature of the active species in McMurry couplings is obscure, but it definitely involves Ti in a lower oxidation state, at least Ti(II) and possibly lower. The mechanism is also obscure. One can imagine that the reduced Ti(II) forms a π complex with one carbonyl group to give a Ti(IV) titanoxirane. Coordination and insertion of a second carbonyl gives the Ti complex of a 1,2-diol. If a second Ti(II) species then coordinates to one of the O atoms, further reduction of the 1,2-diol can take place to give an alkene and two Ti(IV) species.




In another mechanism for McMurry coupling, a Ti(IV) ketyl forms from Ti(III) and the carbonyl. Radical-radical combination then gives the 1,2-diol in a pinacol coupling (Chap. 5).


Reductive coupling of alkynes or alkenes may be carried out with Cp_2ZrCl_2 , $\text{Ti}(\text{O}-i\text{-Pr})_4$, or other Ti(IV) and Zr(IV) complexes. The reaction is often carried out in an intramolecular fashion to achieve better control of regiochemistry. The diyne or other polyunsaturated compound is added to a mixture of the Zr(IV) (or Ti(IV)) complex and a reducing agent such as BuLi. After formation of the intermediate metallacycle, the C–M bonds are cleaved by treatment with an electrophile such as H^+ or I_2 to give the organic product.



The reductive coupling requires that the Zr(IV) be reduced to Zr(II). Metals such as Mg may be used to reduce Zr(IV) to Zr(II) by electron transfer, but the most widely used method today involves the addition of two equivalents of BuLi to Cp_2ZrCl_2 . Transmetalation to give Cp_2ZrBu_2 is followed by β -hydride abstraction to give a Zr(IV) metallacyclopentane, which can also be described as a Zr(II)–butene complex.




Next, 1-butene is displaced from Zr(II) by an alkyne to give a new π complex; then the other alkyne coordinates to the Zr(IV) metallacyclopentene and inserts into the C–Zr bond to give a Zr(IV) metallacyclopentadiene.




(a) association; (b) dissociation; (c) insertion.

When an *enyne* is reductively coupled in an intramolecular fashion with Zr(II) or Ti(II), the metallacyclopentene that is obtained initially may be carbonylated to the corresponding bicyclic cyclopentenone with CO. The reaction proceeds by insertion of CO and reductive elimination. In Ti-promoted cyclization, in fact, under certain conditions, the Ti(II) fragment produced by reductive elimination can promote reductive coupling of another enyne, providing a basis for a variant of this reaction that is catalytic in Ti.




(a) coordination, insertion; (b) reductive elimination.

The π complex that is the common intermediate in all these reactions can be generated in other ways. For example, Cp_2ZrPh_2 undergoes β -hydride abstraction upon heating to generate a benzyne complex of $\text{Cp}_2\text{Zr(II)}$. The complex is highly reactive, and it can be trapped by a π compound such as an alkyne, alkene, nitrile, or carbonyl to give a five-membered metallacycle.




(a) β -hydride abstraction; (b) coordination, insertion.


In fact, a wide variety of π complexes $\text{Cp}_2\text{Zr}(\text{X}=\text{Y})$, including complexes of alkynes, cycloalkynes, arynes, cyclopropenes, imines, and thioaldehydes, can be generated by β -hydride abstraction from complexes of the type $\text{Cp}_2\text{Zr}(\text{Me})\text{X}-\text{Y}-\text{H}$. These complexes can in turn be made by hydrozirconation of $\text{X}=\text{Y}$ with $\text{Cp}_2\text{Zr}(\text{H})\text{Cl}$ followed by addition of MeLi , or by addition of $\text{X}-\text{YH}$ to $\text{Cp}_2\text{Zr}(\text{Me})\text{Cl}$.



The *Kulinkovich cyclopropanation*, in which an ester and two equivalents of a Grignard reagent are combined to make a cyclopropanol in the presence of a catalytic amount of Cp_2TiCl_2 , is a useful variant of reductive coupling reactions. A cyclopropylamine can be obtained instead if a tertiary amide substitutes for the ester.




The reaction is initiated by the addition of two equivalents of Grignard reagent to the Ti catalyst to make a dialkyltitanium compound, the first compound of the catalytic cycle, which undergoes β -hydride abstraction to give a titanacyclopropane. The $\text{C}=\text{O}$ π bond of the ester inserts into this compound to give a titanaoxolane that is also essentially a hemiacetal. A β -alkoxide elimination gives an intermediate that has a nucleophilic $\text{Ti}-\text{C}$ bond poised close to the ketone. Insertion of the $\text{C}=\text{O}$ π bond into the $\text{Ti}-\text{C}$ bond gives the cyclopropanol, and ligand substitution completes the catalytic cycle. The oxidation state of the Ti remains at (IV) throughout the reaction. Note that the reaction of the Grignard reagent with the Ti complex is faster than addition of the Grignard reagent to the ester.




(a) ligand substitution; (b) β -hydride abstraction; (c) insertion; (d) β -alkoxide elimination.

The conventional Kulinkovich cyclopropanation uses two equivalents of a Grignard reagent, but only one equivalent is incorporated into the product; the other is lost as alkane. This aspect of the reaction is not a problem when the Grignard reagent is inexpensive, but when the Grignard reagent is precious, its waste should be avoided. One of the intermediates in the Kulinkovich reaction is a titanacyclopropane, a compound that can also be described as an alkene–titanium complex. When an external alkene is added to the reaction mixture, ligand exchange can generate a new alkene–titanium complex into which the ester can insert. Thus, two equivalents of a cheap Grignard reagent can be sacrificed to couple a precious alkene to the ester or amide. This reaction can also be carried out in intramolecular fashion.




Problem 6.12 Write a reasonable mechanism for the following Kulinkovich cyclopropanation.




6.2.10 Pauson–Khand Reaction (Co)

The *Pauson–Khand reaction* combines an alkyne, an alkene, and CO to give a cyclopentenone. This highly convergent reaction is mediated by the complex $\text{Co}_2(\text{CO})_8$, $(\text{CO})_4\text{Co}-\text{Co}(\text{CO})_4$, which contains an unusual metal–metal bond. Each Co atom in $\text{Co}_2(\text{CO})_8$ has its full complement of 18 electrons, and each is in the Co(0) oxidation state.




The Pauson–Khand reaction gives the same product as the group 4 metal-mediated reductive coupling and carbonylation, and both reactions proceed by essentially the same mechanism: formation of an alkyne–metal π complex, insertion of an alkene, insertion of CO, and reductive elimination. Some details differ, however. When an alkyne is added to $\text{Co}_2(\text{CO})_8$, CO evolves, and an isolable, chromatographable alkyne– $\text{Co}_2(\text{CO})_6$ complex is obtained. This “butterfly” complex contains four Co(II)–C bonds, and the Co–Co bond is retained. The

formation of the alkyne- $\text{Co}_2(\text{CO})_6$ complex involves the formation of an ordinary π complex of the alkyne with one $\text{Co}(0)$ center, with displacement of CO . The π complex can be written in its $\text{Co}(\text{II})$ cobaltacyclopropene resonance structure. The π bond of the cobaltacyclopropene is then used to form a π complex to the other Co center with displacement of another equivalent of CO . This second π complex can also be written in its cobaltacyclopropene resonance structure. The alkyne- $\text{Co}_2(\text{CO})_6$ complex has two 18-electron $\text{Co}(\text{II})$ centers.




The alkyne- $\text{Co}_2(\text{CO})_6$ complex is now combined with an alkene. Initially, nothing happens, because the alkyne- $\text{Co}_2(\text{CO})_6$ complex is a relatively inert 18-electron complex. Heat, light, or addition of *N*-methylmorpholine *N*-oxide (NMO) causes one CO ligand to leave to generate a 16-electron Co complex. Coordination of the alkene to Co then occurs. Migratory insertion of the alkene into one of the $\text{Co}-\text{C}$ bonds occurs, followed by migratory insertion of CO . Reductive elimination gives a π complex of the cyclopentenone with $\text{Co}_2(\text{CO})_4$, and enone dissociation occurs to give the cyclopentenone product.



Problem 6.13 NMO oxidizes one CO ligand of the alkyne- $\text{Co}_2(\text{CO})_6$ complex to CO_2 and gives an alkyne- $\text{Co}_2(\text{CO})_5$ complex. Write a mechanism for this transformation.


The Pauson–Khand reaction is especially useful for the intramolecular cyclization of 1,6-enynes to give bicyclo[3.3.0]octenones. The intermolecular reaction has problems of regioselectivity when unsymmetrical alkynes or alkenes are used, although some substrates give especially good selectivity for various reasons.




Other metal complexes have been found to promote the Pauson–Khand reaction, including $\text{Mo}(\text{CO})_6$, $\text{Fe}(\text{CO})_5$, $\text{W}(\text{CO})_6$, and $\text{Cp}_2\text{Ti}(\text{CO})_2$, and variants of the Pauson–Khand reaction that use catalytic amounts of the metal (such as the $[\text{Rh}(\text{CO})_2\text{Cl}]_2$ -catalyzed reaction) have also been developed, but stoichiometric $\text{Co}_2(\text{CO})_8$ remains a widely used method for effecting this transformation.

6.2.11 Dötz Reaction (Cr)


In the *Dötz reaction*, an unsaturated chromium carbene complex is combined with an alkyne to give a substituted phenol. The unsaturated group may be an alkenyl, cycloalkenyl, or aryl group. There is almost always a methoxy or other alkoxy group attached to the carbene.



By numbering the atoms, we see that the alkylidene portion of the Cr complex contributes three C atoms to the new aromatic ring, and the alkyne contributes two. The sixth C atom with its associated O must come from a CO ligand. Make: C2–C7, C4–C5, C5–C8. Break: Cr–C2, Cr–C5.




Compounds with metal–carbon double or triple bonds are prone to undergo [2 + 2] cycloadditions. Such a reaction in this system makes the C2–C8 bond and generates a metallacyclobutene. In this system, the [2 + 2] cycloaddition is preceded by loss of CO from the unreactive, 18-electron carbene complex and coordination of the alkyne.




(a) ligand substitution; (b) [2 + 2] cycloaddition.

Three reasonable possibilities can be formulated for incorporation of the CO group into the ring and formation of the two remaining C–C bonds. For example, the metallacyclobutene complex can undergo sequential electrocyclic ring opening and ring closing to give a metallacyclohexadiene complex. CO insertion, reductive elimination, and tautomerization then give the observed product.




(a) electrocyclic ring opening; (b) electrocyclic ring closing; (c) insertion;
(d) reductive elimination; (e) tautomerization (two steps).

Alternatively, migratory insertion of a CO group of the metallacyclobutene into the Cr–C(sp^3) bond affords a metallacyclopentenone, which can undergo reductive elimination to give a cyclobutenone. Sequential electrocyclic ring opening, ring closing, and tautomerization gives the product.



(a) insertion; (b) reductive elimination; (c) electrocyclic ring opening;
 (d) electrocyclic ring closing; (e) tautomerization (two steps).


Finally, the dienyliketene complex formed upon electrocyclic ring opening of the metallacyclobutene can undergo migratory insertion of a CO group into the $\text{Cr}=\text{C}$ π bond (leaving the $\text{Cr}-\text{C}$ σ bond unchanged) to give a chromacyclopropanone. A dienyliketene- $\text{Cr}(\text{CO})_3$ resonance structure can be drawn for this compound. Loss of $\text{Cr}(\text{CO})_3$, electrocyclic ring closing, and tautomerization provides the phenol.




(a) insertion;
 (b) electrocyclic ring closing;
 (c) dissociation of $\text{Cr}(\text{CO})_3$;
 (d) tautomerization (two steps).

When the Dötz reaction is executed in EtOH , products derived from addition of EtOH to a dienyliketene are obtained, suggesting that either of the latter two mechanisms is correct.

The Cr-containing starting material for the Dötz reaction is usually prepared from $\text{Cr}(\text{CO})_6$. The C atoms in $\text{Cr}(\text{CO})_6$ are electrophilic, as is best illustrated by the metallaketene resonance structure of this compound. Addition of an unsaturated organolithium reagent to $\text{Cr}(\text{CO})_6$ affords a chromaenolate, which is *O*-methylated (Meerwein's reagent, $\text{Me}_3\text{O}^+ \text{BF}_4^-$, is often used) to afford the carbene complex.




The carbene complex $(\text{CO})_5\text{Cr}=\text{C}(\text{CH}_3)\text{OMe}$, prepared from $\text{Cr}(\text{CO})_6$ and MeLi , can also be used to prepare other Cr carbene complexes. The five CO groups attached to Cr in this compound exert such a strong electron-withdrawing effect on the $\text{Cr}=\text{C}$ π bond that the latter becomes polarized toward Cr. In fact, the $\text{Cr}(\text{CO})_5$ fragment is so electron-attracting that the CH_3 group becomes as acidic as a methyl ketone! Addition of an aldehyde and a Lewis acid causes an aldol reaction to occur, thereby producing an unsaturated Cr carbene complex.



Problem 6.14 Draw a mechanism for the BF_3 -promoted aldol reaction of $(\text{CO})_5\text{Cr}=\text{C}(\text{CH}_3)\text{OMe}$ and PhCHO .


Chromium carbene complexes undergo other reactions, too. The mechanisms of these reactions consist of steps ([2 + 2] cycloadditions, electrocyclic reactions) that are similar to those seen in the mechanism of the Dötz reaction.

Problem 6.15 Draw a mechanism for the following reaction.




6.2.12 Metal-Catalyzed Cycloaddition and Cyclotrimerization (Co, Ni, Rh)


Certain late-transition-metal complexes have the ability to catalyze [4 + 2], [4 + 4], and [5 + 2] cycloadditions. Despite their appearance, these reactions are not concerted cycloadditions. For example, $\text{Ni}(0)$ catalyzes intramolecular [4 + 4] cycloadditions.




The mechanism probably begins by coordination of Ni(0) to the diene to give a Ni(0)–diene complex, which can also be described as a Ni(II) nickelacyclopentene. Insertion of a C=C π bond into the Ni–C bond, allylic rearrangement of the Ni–C bond, and reductive elimination completes the mechanism. Similar mechanisms can be drawn for Ni- and Rh-catalyzed [4 + 2] cycloadditions.




Problem 6.16 Draw a reasonable mechanism for the following Ni-catalyzed [4 + 2] cycloaddition.



The Rh-catalyzed [5 + 2] cycloaddition combines a vinylcyclopropane and an alkyne (or an alkene or allene) to give a cycloheptadiene.




One reasonable mechanism for this reaction begins with coordination of Rh(I) to the alkyne to give a Rh(III) rhodacyclopentene. Reductive coupling of the π bond of the vinylcyclopropane with the alkyne gives a rhodacyclopentene, but this compound is also a cyclopropylmethylrhodium complex, and ring strain drives a very rapid homoallylic rearrangement. Reductive elimination then affords the cycloheptadiene.




Problem 6.17 An alternative mechanism for the [5 + 2] cycloaddition begins with coordination of the Rh(I) to the vinyl group and puts the homoallylic rearrangement *before* coupling to the alkyne. Draw this mechanism.

The Rh-catalyzed [5 + 2] cycloaddition can be combined with a [4 + 2] cycloaddition in a tandem process. A tandem reaction is one in which the product of one step is the starting material for the next.

Problem 6.18 Draw a reasonable mechanism for the following reaction.




Various Ni and Co complexes catalyze cyclotrimerization reactions of alkynes to give arenes. These reactions are formally [2 + 2 + 2] cycloadditions. The cyclotrimerization of $\text{PhC}\equiv\text{CPh}$ using $\text{CpCo}(\text{CO})_2$ as catalyst is illustrative.




The 18-electron complex $\text{CpCo}(\text{CO})_2$ must lose at least one CO ligand before it is able to coordinate to $\text{PhC}\equiv\text{CPh}$, another two-electron donor. One can draw two resonance structures for this complex, one of which is a Co(III) cobaltacyclopentadiene. Loss of a second CO ligand (before or after coordination of $\text{PhC}\equiv\text{CPh}$) and coordination of another equivalent of $\text{PhC}\equiv\text{CPh}$ is followed by an insertion


reaction to give a cobaltacyclopentadiene. Coordination and insertion of another equivalent of $\text{PhC}\equiv\text{CPh}$ gives a cobaltacycloheptatriene, and reductive elimination gives the product and the 14-electron complex CpCo(I) , which recoordinates $\text{PhC}\equiv\text{CPh}$ to reenter the catalytic cycle.



The end of the catalytic cycle can be drawn differently. The cobaltacyclopentadiene is particularly well arranged to undergo a Diels–Alder reaction with another equivalent of $\text{PhC}\equiv\text{CPh}$. A [4 + 1] retrocycloaddition then gives the product C_6Ph_6 and regenerates the catalyst CpCo(I) .




The cyclotrimerization reaction has been used to prepare some remarkable compounds. Bis(trimethylsilyl)acetylene ($\text{Me}_3\text{SiC}\equiv\text{CSiMe}_3$) does not undergo cyclotrimerization with itself due to steric hindrance, but it does cyclotrimerize with other alkynes. Slow addition of hexaethynylbenzene to CpCo(CO)_2 in $\text{Me}_3\text{SiC}\equiv\text{CSiMe}_3$ gave a triply cyclotrimerized product. The product shows bond alternation in the central ring due to its desire to avoid antiaromatic cyclobutadiene rings around its perimeter.




6.3 Substitution Reactions

6.3.1 Hydrogenolysis (Pd)


Hydrogenolysis catalyzed by Pd/C is widely used to convert benzylic ethers $\text{ArCH}_2\text{-OR}$ to ArCH_3 and ROH . The reaction is often accelerated by acid. The simplest possibility for a catalytic cycle is oxidative addition of both H_2 and Bn-OR to Pd(0) to give a Pd(IV) complex, followed by reductive elimination of both Bn-H and H-OR to regenerate Pd(0) . This mechanism seems very unlikely, because the Pd(IV) oxidation state is high in energy.




Still, it seems likely that an oxidative addition must be the first step. Oxidative addition of Pd(0) to the Bn-OR bond may give Bn-Pd(II)-OR . Sigma-bond metathesis may take place next to give Bn-H (toluene) and H-Pd(II)-OR , which undergoes reductive elimination to give ROH and regenerate the Pd(0) .




An alternative catalytic cycle can be drawn. The first step, oxidative addition of Pd(0) to Bn-OR , is the same as before. The Bn-Pd(II)-OR complex might then form a σ -bond complex with H_2 , with the H-H σ bond acting as a two-electron donor. The H atoms are made electrophilic upon coordination. Intramolecular deprotonation of the σ complex by OR^- would then give ROH and Bn-Pd(II)-H , and the latter would undergo reductive elimination to complete the catalytic cycle.



A third possibility begins with oxidative addition of H_2 to $\text{Pd}(0)$ to give a H-Pd(II)-H complex. Deprotonation gives an anionic $[\text{Pd}(0)\text{-H}]^-$ complex. Simple $\text{S}_{\text{N}}2$ displacement of ROH from BnO(H)R by the anionic $[\text{Pd}(0)\text{-H}]^-$ complex then gives Bn-Pd(II)-H and ROH . Finally, reductive elimination of toluene regenerates $\text{Pd}(0)$. Although it seems that the acceleration of hydrogenolyses by acid is not consistent with an anionic palladium intermediate, it is possible that the $\text{S}_{\text{N}}2$ step, not the deprotonation of Pd , is rate-limiting, and this step is likely to be promoted by acid.




Finally, a different sort of catalytic cycle can be drawn. Oxidative addition of H_2 to Pd gives a H-Pd(II)-H complex, and one of the π bonds of the benzyl ether undergoes insertion into the Pd(II)-H bond to give a cyclohexadienyl- Pd(II)-H complex. Isomerization to put the Pd on the ipso C is followed by a β -alkoxide elimination to give isotoluene and H-Pd(II)-OR , which undergoes reductive elimination to give ROH and regenerate the catalyst. The isotoluene undergoes isomerization to toluene under the reaction conditions, possibly catalyzed by $\text{Pd}(0)$ with a series of insertions and β -hydride eliminations. If this mechanism were correct, one would expect that Pd would reduce aromatic rings under the conditions required for hydrogenolysis, which it does not. Nevertheless, this mechanism is accepted by some.



6.3.2 Carbonylation of Alkyl Halides (Pd, Rh)

A $\text{Pd}(0)$ catalyst such as $(\text{Ph}_3\text{P})_4\text{Pd}$ catalyzes the *alkoxycarbonylation* of an organic halide (RX) to an ester (RCO_2Me) in basic MeOH under a CO atmosphere. (Any alcohol can be used.) The first step in any late metal-catalyzed substitution reaction


of a C–halogen bond is almost always oxidative addition. Oxidative addition of R–X to Pd(0) gives R–Pd(II)–X, and coordination and insertion of CO gives RCO–Pd(II)–X. The acylpalladium complex can be regarded as a complicated acyl “halide”. The Pd–C bond can be replaced by a MeO–C bond by an addition–elimination reaction. Loss of X[−] from the Pd(0) complex regenerates the catalyst. The active catalytic species is often designated as L_nPd, as ligands may be associating and dissociating with the catalyst throughout the course of the reaction. The active species is probably (Ph₃P)₂Pd, derived from (Ph₃P)₄Pd by loss of 2 Ph₃P, but it may be (Ph₃P)₃Pd.



(a) oxidative addition; (b) coordination; (c) insertion; (d) dissociation.

Other Pd ligands besides Ph₃P, usually di- or triarylphosphines like Ph₂PCH₂CH₂PPh₂ (diphos or dppe), 1,1'-bis(diphenylphosphino)ferrocene (dppf), (*o*-tolyl)₃P, trifurylphosphine, and the like, are also used. Ph₃As is sometimes used, too. The ligands help keep the Pd(0) in solution, and they can also modulate the rates of certain steps along and off the catalytic cycle. Experimentation is required to determine which ligands are best for any particular transformation.

Sometimes a Pd(II) compound such as (Ph₃P)₂PdCl₂ or Pd(OAc)₂ is added to the reaction mixture as catalyst. The Pd(II) must be reduced to Pd(0) before the catalytic cycle can proceed. Et₃N can act as the reducing agent. Coordination to Pd(II) and β-hydride elimination gives a Pd(II) hydride, which is deprotonated to give Pd(0). Triarylphosphines can also reduce Pd(II) to Pd(0) by electron transfer.




(a) ligand substitution; (b) β-hydride elimination.




The Pd-catalyzed carbonylation of alkyl halides is an extraordinarily useful reaction. The “classic” way to accomplish this transformation would be to convert RX to the Grignard reagent, add CO₂, and esterify the carboxylic acid. Many functional groups cannot survive the strongly reducing and basic Grignard conditions. The Pd-catalyzed reaction proceeds at room temperature or slightly higher temperatures and requires only a weak base like Et₃N. The reaction proceeds best with X = I or Br, although especially bulky phosphine ligands such as *t*-Bu₃P allow even aryl chlorides to undergo coupling at room temperature. It also proceeds well

with pseudohalides; $X = \text{OTf}$ is widely used, as it is easily prepared from the corresponding ketone. An important limitation to the reaction, however, is that R must almost always be $C(sp^2)$. The only $C(sp^3)$ halides that can undergo the reaction are those lacking β -hydrogens, such as methyl, benzyl, and neopentyl halides ($\text{Me}_3\text{CCH}_2\text{X}$). Alkyl halides that have β -hydrogens undergo β -hydride elimination after the oxidative addition step, affording only the product derived from elimination of HX .


Problem 6.19 Draw a reasonable mechanism for the following alkoxyacetylation reaction.



The *Monsanto process*, one of the most successful industrial homogeneous catalytic processes, uses a Rh complex and catalytic HI to carbonylate MeOH to MeCO_2H . A Rh precatalyst (almost any Rh complex will do) is converted into $\text{Rh}(\text{CO})_2\text{I}_2^-$, the active catalyst, under the reaction conditions. The mechanism of the reaction involves three steps. In the first step, MeOH and HI are converted to MeI and H_2O by an $\text{S}_{\text{N}}2$ mechanism. In the second step, MeI and CO are converted to MeCOI under Rh catalysis. In the third step, H_2O (generated in the first step) hydrolyzes MeCOI to afford MeCO_2H and to regenerate HI .




The catalytic cycle of the second step proceeds by oxidative addition of MeI to $\text{Rh}(\text{I})$ to give a $\text{MeRh}(\text{III})$ complex, insertion of CO to give the $(\text{MeCO})\text{Rh}(\text{III})$ complex, coordination of more CO , and reductive elimination of MeCOI to regenerate the $\text{Rh}(\text{I})$ complex.




6.3.3 Heck Reaction (Pd)

In the *Heck reaction*, an aryl or vinyl halide ($R-X$) and an alkene ($H_2C=CHR'$) are converted to a more highly substituted alkene ($R-CH=CHR'$) under Pd catalysis. Base is used to neutralize the coproduct (HX). The Heck reaction can be carried out in intra- or intermolecular fashion. In intermolecular reactions, the reaction proceeds best when the alkene is electrophilic. In intramolecular reactions, more highly substituted alkenes can be used.




In the example reaction, the C–I bond breaks, and a new C–C bond forms. The first step, as always, is oxidative addition of Pd(0) to the C–I bond to give a Pd(II)–Ph complex. Coordination of the alkene π bond to Pd and insertion of the π bond into the Pd(II)–Ph bond now takes place to give the new C–C bond. A β -hydride elimination gives the product and H–Pd(II)–I, which is deprotonated by base to regenerate Pd(0).




The Heck reaction has the same scope and limitations as Pd-catalyzed carbonylation. Pd(II) complexes are often added to the reaction mixture and are reduced in situ. Mostly *trans* alkenes are obtained due to conformational preferences in the rotamer from which β -hydride elimination takes place. Sometimes the β -hydride elimination occurs away from the new C–C bond, and in this case a new stereocenter is formed. If the starting material is prochiral, the reaction can be made asymmetric by the use of chiral phosphine ligands like BINAP (2,2'-bis(diphenylphosphino)-1,1'-binaphthyl).


Problem 6.20 Draw a reasonable mechanism for the following Heck reaction.



couple originally proposed. The active Ni(I) catalyst could be formed from the L_2NiCl_2 starting material by electron transfer from the Grignard reagent.




After the discovery of the Kumada reaction, intensive efforts were made to discover other group 10 metal-catalyzed reactions. These efforts paid off tremendously with the development of some of the most widely used C–C bond-forming reactions in organic synthetic methodology, including the *Stille* (pronounced “still-ee”) *coupling*, the *Suzuki* or *Suzuki–Miyaura coupling*, the *Negishi coupling*, and related reactions. In these reactions, an aryl or vinyl halide or pseudohalide undergoes a Pd-catalyzed substitution reaction with a “nucleophilic” alkylmetal compound such as $R-SnR'_3$ (Stille coupling), $R-B(OH)_2$ or other borane (Suzuki coupling), $R-ZnCl$ (Negishi coupling), or another. The catalytic cycle, shown for the Stille coupling, involves oxidative addition to the Ar–X bond, transmetalation, and reductive elimination. The catalytic cycle is exactly the same for the Negishi coupling and many other alkylmetal couplings. The catalytic cycle of the Suzuki coupling is almost the same, but the reaction requires aqueous NaOH; its role is to add to the six-electron B of the boronic acid or borane nucleophile, making the R group attached to B more nucleophilic and more prone to undergo transmetalation to Pd.




The catalyst that is added to the reaction mixture may be either a Pd(0) species like $(Ph_3P)_4Pd$ or $Pd_2(dba)_3$ (dba = dibenzylideneacetone) or a Pd(II) species like $(Ph_3P)_2PdCl_2$ or $Pd(OAc)_2$ and 2 $AsPh_3$. When the added catalyst is Pd(II), it is reduced to Pd(0) before the catalytic cycle begins. The reduction probably proceeds by two transmetalations from the nucleophile followed by reductive elimination.


Problem 6.21 Draw a mechanism for the following Stille coupling.




The reactions have a very wide scope. The nucleophile may be $C(sp)$, $C(sp^2)$, or $C(sp^3)$. Like Pd-catalyzed carbonylations, reactions proceed most quickly when $X = I$ and rather slowly when $X = Cl$, although especially bulky phosphine ligands such as *t*-Bu₃P allow even aryl chlorides to undergo coupling at room temperature. Again, triflates are also widely used, especially alkenyl triflates, which are easily prepared from the ketones. Most often, the electrophiles are $C(sp^2)$ -X compounds such as aryl, alkenyl, and acyl halides. Usually, $C(sp^3)$ -X electrophiles, with the exception of PhCH₂X and CH₃X, are poor substrates because they undergo rapid β -hydride elimination after the metal oxidatively adds to the C-X bond. However, certain very bulky phosphine ligands can suppress the β -hydride elimination, allowing even $C(sp^3)$ -X electrophiles to participate in the reaction.




Metal amides and alkoxides are also coupled to $C(sp^2)$ -X electrophiles under Pd catalysis in *Buchwald–Hartwig amination* or *etherification*. The use of amines or alcohols in Pd-catalyzed coupling might seem like an obvious extension from carbon nucleophiles, but, in fact, the Buchwald–Hartwig reactions were discovered much later. Especially bulky phosphine ligands such as *t*-Bu₃P are required for these reactions to proceed. The ligands are thought to enforce a lower coordination number of the Pd catalyst, making a more active catalyst.




As shown in the example, the Buchwald–Hartwig reaction normally uses a *neutral* amine along with an equivalent of a moderate base such as NaO-*t*-Bu. This detail makes it unlikely that the mechanism proceeds by oxidative addition, deprotonation of the amine, transmetalation, and reductive elimination, because NaO-*t*-Bu is not basic enough to deprotonate an amine. Instead, after oxidative addition, the amine coordinates to Pd(II). This step renders the amine much more acidic, allowing NaO-*t*-Bu to deprotonate it, which in turn triggers reductive elimination. The overall mechanism of a Buchwald–Hartwig amination, then, is oxidative addition, coordination of the amine, deprotonation of the amine, and reductive elimination, very similar to the catalytic cycles we have already discussed.




Many compounds containing metal–metal bonds undergo “Stille” and “Suzuki” couplings, too. Two of the most popular reagents for this purpose are hexamethyldistannane ($\text{Me}_3\text{Sn-SnMe}_3$) and pinacolborane [(pin)B–B(pin), where pin = 1,1,2,2-tetramethylethylene-1,2-dioxy]. In fact, even (pin)BH itself will convert aryl halides to arylboronates when an amine is present to neutralize the HX coproduct. In this case, the mechanism by which the B–H bond is converted to a B–Pd bond is somewhat murky.




The *carbonylative Stille coupling* is another extremely useful reaction. When the Stille coupling of Ar-X and $\text{R-SnR}'_3$ is carried out under an atmosphere of CO, the product is the ketone ArCOR . An insertion of CO intervenes between oxidative addition and reductive elimination.




Problem 6.22 Draw a mechanism for the following carbonylative Stille coupling.




Terminal alkynes ($\text{RC}\equiv\text{CH}$) undergo Pd-catalyzed *Sonogashira coupling* to alkyl halides ($\text{R}'\text{X}$) in the presence of base and a subcatalytic amount of CuI to give internal alkynes ($\text{RC}\equiv\text{CR}'$).




One can imagine that the Sonogashira coupling proceeds by a catalytic cycle very similar to the Stille coupling. The transmetalation step of the Stille coupling is replaced with a ligand substitution reaction, in which a deprotonated alkyne displaces X^- from the $\text{Pd}(\text{II})$ complex. The alkyne may be deprotonated by the Et_3N that is present in the reaction mixture.




The problem with this scenario is that alkynes are more acidic than most hydrocarbons ($\text{p}K_{\text{a}} \approx 25$), but they are not sufficiently acidic to be deprotonated by amines ($\text{p}K_{\text{b}} \approx 10$). The solution to this problem is found in the CuI that cocatalyzes the reaction. CuI lowers the temperature required for the Sonogashira coupling from $>100\text{ }^\circ\text{C}$ to room temperature. The CuI may convert the alkyne ($\text{RC}\equiv\text{CH}$) to a copper(I) acetylide ($\text{RC}\equiv\text{CCu}$), a species that can undergo transmetalation with Pd (II). Of course, now the question is, how is $\text{RC}\equiv\text{CH}$ converted to $\text{RC}\equiv\text{CCu}$? The alkyne may form a π complex with Cu , and this complex may be deprotonated ($\text{E}2$ -like elimination) to give the Cu acetylide, which can transmetalate with Pd .



Copper(I) salts such as CuCN and ROCu undergo aromatic substitution reactions very readily with ordinary aryl halides and aryldiazonium ions. The mechanism has not been established with certainty. One reasonable possibility is an $\text{S}_{\text{RN}}1$ mechanism. Another reasonable possibility involves oxidative addition of Ar-X to $\text{N}\equiv\text{C-Cu}(\text{I})$ to give a $\text{Cu}(\text{III})$ complex, followed by reductive elimination of Ar-CN to give CuX .



The only problem with the oxidative addition–reductive elimination mechanism is that Cu(III) is a relatively high energy species. The mechanism would be much more reasonable if the Cu cycled between Cu(0) and Cu(II) instead of Cu(I) and Cu(III). Such a mechanism can be proposed if one supposes an initial electron transfer from CuCN to CuCN to give $[\text{N}\equiv\text{C-Cu}(0)]^-$. Oxidative addition of Ar–Br to $\text{Cu}(0)^-$ and reductive elimination of Ar–CN from $\text{Cu}(II)^-$ affords the organic product and $[\text{Br-Cu}(0)]^-$. Finally, ligand exchange with another equivalent of $\text{N}\equiv\text{C-Cu}(I)$ regenerates $[\text{N}\equiv\text{C-Cu}(0)]^-$.




Other copper nucleophiles such as R_2CuLi and $\text{R}_2\text{Cu}(\text{CN})\text{Li}_2$ also undergo substitution reactions with aryl and alkenyl halides. Retention of double-bond geometry about alkenyl halides is observed. The mechanisms of the reactions of these other Cu(I) nucleophiles are likely very similar to the one shown for the reaction of CuCN and ArBr.

In the *Ullmann reaction*, Cu metal promotes the coupling of Ar–I to give Ar–Ar. The reaction mechanism almost certainly involves oxidative addition of Cu(0) to Ar–I to give Ar–Cu(II), then reduction by another equivalent of Cu(0) to give Ar–Cu(I). This species can then react with ArI by the same mechanism that has just been written for other Cu(I) salts.


6.3.5 Allylic Substitution (Pd, Ir)

A nucleophile such as $(\text{EtO}_2\text{C})_2\text{CMe}^-$ can undergo a substitution reaction with an allylic halide by an $\text{S}_{\text{N}}2$ mechanism. Allylic carbonates and allylic acetates do not normally undergo this reaction because ROCO_2^- and AcO^- are not sufficiently good leaving groups. In the presence of a Pd catalyst, though, allylic carbonates and acetates are substrates for the substitution reaction. Significantly, the Pd-catalyzed

reaction occurs with *retention* of stereochemistry, not the inversion of stereochemistry observed in S_N2 substitution reactions.




Whenever you see retention of stereochemistry, you should think “double inversion”, and in fact double inversion occurs in this reaction. The Pd(0) complex acts as a nucleophile toward the allylic carbonate or acetate, displacing MeOCO_2^- or AcO^- by backside attack and giving an allylpalladium(II) complex. The nucleophile then attacks the allylpalladium(II) complex, displacing Pd by backside attack to give the product and regenerate Pd(0). The regiochemistry of attack (S_N2 or S_N2') is dependent on the structure of the substrate.




The Pd catalyst may be any of the commonly used Pd(0) or Pd(II) species such as $(\text{Ph}_3\text{P})_4\text{Pd}$ or $(\text{Ph}_3\text{P})_2\text{PdCl}_2$. Pd complexes with chiral phosphine ligands can effect asymmetric allylations. The reaction works for allylic epoxides, too.

Problem 6.23 Draw a mechanism for the following Pd-catalyzed allylic substitution reaction.




Iridium catalysts have also been used to catalyze allylation reactions of allylic carboxylates. The dimeric Ir complex that is added to the reaction mixture dissociates into a monomeric P–Ir complex upon reaction with the phosphorus ligand.




In some cases, the reaction will also work with allylic alcohol substrates, as well. In these cases, the alcohol may be converted into a better leaving group in situ, or a Lewis acid may promote its departure.

Problem 6.24 Draw a mechanism for the following Ir-catalyzed allylic substitution reaction.




6.3.6 Pd-Catalyzed Nucleophilic Substitution of Alkenes. Wacker Oxidation

Pd(II) salts catalyze the reaction of nucleophiles such as alcohols and amines with alkenes to give more highly substituted alkenes. A stoichiometric amount of an oxidant such as benzoquinone, CuCl, or O₂ (with or without catalytic Cu salts) is required for the reaction to be catalytic in Pd.



The mechanisms of these reactions begin the same way as Hg-mediated nucleophilic addition to alkenes. The alkene coordinates directly to Pd(II) to form an electrophilic π complex. The nucleophile attacks one of the carbons of the π complex, and the electrons from the C=C π bond move to form a σ bond between Pd(II) and the other carbon to give an alkylpalladium(II) compound. The alkylpalladium(II) compound then undergoes β -hydride elimination to give the observed product and a palladium(II) hydride. Loss of H⁺ from the palladium(II) hydride gives Pd(0), which is oxidized back to Pd(II) by the stoichiometric oxidant. The Pd(II)–H sometimes catalyzes the migration of the π bond by a series of insertions and β -hydride eliminations.




The addition of nucleophiles to alkenes is *mediated* by Hg(II) salts and *catalyzed* by Pd(II) salts. The difference between the two reactions is the fate of the alkylmetal(II) intermediate


obtained after addition of the nucleophile to the π complex. The alkylmercury(II) intermediate is stable and isolable, whereas the alkylpalladium(II) intermediate undergoes rapid β -hydride elimination.

The addition of nucleophiles to *alkynes* is catalyzed by both Hg(II) and Pd(II) salts. The intermediate alkenylmetal(II) complex is stable to β -hydride elimination, but the C–metal bond can be replaced by a C–H bond by a protonation–fragmentation mechanism.

The *Wacker oxidation* (pronounced “vocker”) is used industrially to convert ethylene and O_2 into acetaldehyde. The Wacker oxidation is catalyzed by $PdCl_2$ and $CuCl_2$ and requires H_2O as solvent. The oxygen in the product comes from the *water*, not the O_2 .




The mechanism of the Wacker oxidation is simply another Pd-catalyzed nucleophilic substitution of an alkene, with H_2O as the nucleophile. H_2O adds to a Pd(II) complex of ethylene, and β -hydride elimination occurs to give a π complex of the enol of acetaldehyde. After rotation about the Pd(II)–alkene σ bond, the alkene reinserts into the Pd(II)–H bond to give a new Pd(II)–alkyl. This complex undergoes β -hydride elimination one more time to give acetaldehyde itself and Pd(II)–H. Deprotonation of the Pd(II) complex converts it to Pd(0), and oxidation of Pd(0) by air (see below) brings it back to Pd(II).



After the first β -hydride elimination, it is reasonable simply to allow the enol to dissociate from Pd and then undergo acid-catalyzed tautomerization.


For the reaction to be catalytic in Pd, the Pd(0) has to be reoxidized back to Pd(II). Two equivalents of $CuCl_2$ convert Pd(0) to Pd(II) and produce 2 $CuCl$. The Cu(I) is then reoxidized back to Cu(II) by O_2 .




The Wacker oxidation works well for terminal alkenes, too. The products are methyl ketones, not aldehydes, as expected from Markovnikov attack of H_2O on the Pd-alkene π complex.

Problem 6.25 Draw mechanisms for the following Pd-catalyzed oxidations.

(a)




(b)




6.3.7 C–H Activation Reactions (Pd, Ru, Rh)

In a *C–H activation reaction*, the H atom of a C–H bond is substituted with another group, often an electronegative atom but sometimes C. The term is generally reserved for cases where the C–H bonds are unreactive under polar conditions. The reaction is often catalyzed by a Pd(II) or Ru(II) compound, and the substrate usually contains a weak ligand such as a heteroaromatic group or a carboxylate that acts both as an activator and a director of the reaction.




This particular reaction begins by coordination of the pyridine N to the metal. The Pd(II) is now poised to undergo a *concerted metalation–deprotonation* reaction with the nearby C–H bond to give a Pd(II) metallocycle. The stoichiometric oxidant, $\text{PhI}(\text{OAc})_2$, then reacts with the cyclic Pd(II) complex in an unusual oxidative addition reaction to give a Pd(IV) intermediate. Reductive elimination then occurs to form the new C–O bond, and dissociation of the pyridine N from Pd provides the product and regenerates Pd(II). Note that this mechanism involves a Pd(IV) intermediate; the C–H activation reaction is one of only a few reactions where a Pd(IV) intermediate is reasonably invoked. However, it is possible to avoid invoking the Pd(IV) intermediate. For example, the C atom of the C–Pd bond in the cyclic Pd(II) complex could use the electrons of the C–Pd bond to directly attack the electrophile.




A common theme in C–H activation reactions is the presence of a weak ligand in the substrate that can coordinate the metal and induce it to undergo a concerted metallation–deprotonation reaction with a nearby C–H bond. Compounds with $N(sp^2)$ such as pyridines and imines quite often serve as ligands, but carboxylate ions can also do the job.

Problem 6.26 Draw mechanisms for the following C–H activation reactions.




Rh(II) compounds catalyze intramolecular amination reactions that proceed by C–H activation. Although the Rh-catalyzed C–H activation reaction also uses $\text{PhI}(\text{OAc})_2$ as an oxidant, the mechanism of the Rh-catalyzed reaction is quite different from that of the Pd-catalyzed reaction. In the Rh-catalyzed reaction, an NH_2 group in the substrate first reacts with the electrophilic I atom in $\text{PhI}(\text{OAc})_2$, with MgO serving as a mild base, to form a new compound with an $\text{N}=\text{I}$ π bond. This compound is the substrate for the Rh-catalyzed reaction. In the first steps of the catalytic cycle, Rh(II) replaces the IPh group attached to N to give a Rh(IV) nitrene. (You may recall the discussion of nitrenes in Chap. 2.) The nitrene then does one of its typical reactions, insertion into a nearby C–H bond, to give a cyclic amine, with a pair of π electrons from the $\text{N}=\text{Rh}$ bond returning to Rh to reduce its oxidation state back to Rh(II). Dissociation of Rh(II) from N then provides the cyclic product and regenerates the Rh(II) catalyst.




6.3.8 Tebbe Reaction (Ti)

The *Tebbe reaction* is an early-metal organometallic version of the Wittig reaction (Chap. 4). A carbonyl compound is converted to the corresponding methylene compound by treatment with the Tebbe reagent, which is a complex of $\text{Cp}_2\text{Ti}=\text{CH}_2$ with Me_2AlCl . The Tebbe reagent is prepared by combining Cp_2TiCl_2 with two equivalents of Me_3Al . Two transmetallations give Cp_2TiMe_2 , which undergoes α -hydride abstraction to give $\text{Cp}_2\text{Ti}=\text{CH}_2$. Coordination to ClAlMe_2 , produced in the transmetallation step, gives the Tebbe reagent.




The presumed mechanism of action of the Tebbe reagent is very simple: after dissociation of Me_2AlCl , [2 + 2] cycloaddition of $\text{Cp}_2\text{Ti}=\text{CH}_2$ and $\text{R}_2\text{C}=\text{O}$ is followed by [2 + 2] retrocycloaddition to give the product. Unlike the conventional Wittig reaction, the Tebbe reaction works well with esters.



(a) dissociation; (b) [2 + 2] cycloaddition; (c) retro [2 + 2] cycloaddition.


In the *Petasis reaction*, Cp_2TiMe_2 itself is used to carry out Tebbe reactions. Cp_2TiMe_2 is much easier to prepare (from Cp_2TiCl_2 and MeLi) and handle than is the Tebbe reagent. Upon heating, it undergoes α -hydride abstraction to give $\text{Cp}_2\text{Ti}=\text{CH}_2$. More highly substituted $\text{Cp}_2\text{Ti}(\text{CH}_2\text{R})_2$ complexes also convert carbonyl compounds to the corresponding alkenes. Unlike Wittig reagents, however, Petasis reagents are mostly limited to transferring alkylidene groups lacking β -hydrogens, such as methylidene and benzylidene. Cp_2TiR_2 compounds bearing alkyl groups that have β -hydrogens, such as Cp_2TiBu_2 , undergo β -hydride abstraction much more readily than they undergo α -hydride abstraction.

Problem 6.27 Draw a reasonable mechanism for the following Petasis reaction.




6.3.9 Propargyl Substitution in Co-Alkyne Complexes

Alkyne- $\text{Co}_2(\text{CO})_6$ complexes have uses in organic chemistry other than the Pauson-Khand reaction. When the complex forms from a propargyl alcohol or ether, the C-O bond is especially prone to undergo $\text{S}_{\text{N}}1$ substitution reactions, as the cation is hyperconjugatively well-stabilized by the neighboring high-energy Co-C bonds. The nucleophile is delivered exclusively to the propargylic C. Substitution reactions at Co-free propargylic C atoms are often plagued by the allenic products derived from addition of the nucleophile to the distal alkyne C.




The complex of an alkyne with $\text{Co}_2(\text{CO})_6$ can also be used to protect an alkyne in the presence of an alkene (e.g., in hydroborations). The $\text{Co}_2(\text{CO})_6$ can then be removed from the alkyne by oxidation with Fe(III) ion.




6.4 Rearrangement Reactions

6.4.1 Alkene Isomerization (Rh)

Wilkinson's catalyst catalyzes the isomerization of an alkene to its lowest energy isomer. Isomerization of allyl ethers in this manner gives enol ethers, which can be hydrolyzed to give the free alcohol and a carbonyl compound.




Other double-bond isomerizations (e.g., those that occur in the course of Pd-catalyzed hydrogenolyses or hydrogenations) proceed by insertion of the alkene into a M–H bond followed by β -hydride elimination. Wilkinson's catalyst, though, lacks a Rh–H bond into which an alkene can insert. The reaction may proceed by oxidative addition to an allylic C–H bond, then reductive elimination at the other end of the allylic system.




(a) oxidative addition; (b) allylic transposition; (c) reductive elimination.

6.4.2 Olefin and Alkyne Metathesis (Ru, W, Mo, Ti)


In the olefin metathesis reaction, the alkylidene fragments of two alkenes ($\text{R}^1\text{R}^2\text{C}=\text{CR}^3\text{R}^4$) are swapped to give ($\text{R}^1\text{R}^2\text{C}=\text{CR}^1\text{R}^2$) and ($\text{R}^3\text{R}^4\text{C}=\text{CR}^3\text{R}^4$).



This remarkable reaction is catalyzed by early and middle metals, primarily complexes of Ti, Mo, W, and Ru. All olefin metathesis catalysts either have an M=C π bond or are converted into compounds that have an M=C π bond under the reaction conditions. Some of the most widely used homogeneous catalysts are shown, but many other compounds have been shown to catalyze these reactions.




The olefin metathesis reaction proceeds by a series of [2 + 2] cycloadditions and retrocycloadditions. No change in metal oxidation state occurs in the course of the reaction. The reaction sets up an equilibrium between all the possible alkenes, but it is possible to drive the equilibrium in one direction or the other, for example, by removal of gaseous ethylene. The two Grubbs catalysts undergo dissociation of a Cy_3P ligand before the catalytic cycle begins so that coordination of the alkene to the metal may precede each [2 + 2] cycloaddition. In the first round of the catalytic cycle, R is the alkylidene substituent from the catalyst (often Ph); subsequently, R = Me (from the substrate).




(a) [2 + 2] cycloaddition; (b) [2 + 2] retrocycloaddition.

The olefin metathesis reaction has been known for a long time, but the first catalysts were heterogeneous, poorly characterized, and intolerant of functional groups, so the reaction was originally applied only to very simple olefins of industrial interest. Later, homogeneous, functional-group-tolerant catalysts that worked under mild conditions were developed, causing applications to complex molecule synthesis to proliferate. One of the most widely used variations of olefin metathesis is the *ring-closing metathesis* reaction (RCM), in which a diene is allowed to undergo intramolecular olefin metathesis to give a cyclic alkene and ethylene. The evaporation of the gaseous ethylene drives the equilibrium forward.




RCM has quickly been adopted as a premier method for preparing compounds with very large rings. By contrast, substrates that would lead to strained rings preferentially undergo polymerization in favor of cyclization when subject to metathesis catalysts.

Problem 6.28 Draw a mechanism for the following ring-closing metathesis reaction.




There are other variations of olefin metathesis. In the *cross-metathesis* reaction (CM), two different olefins are coupled. This reaction gives good yields and non-statistical mixtures if the two alkenes have electronically different properties.




In *ring-opening metathesis polymerization* (ROMP), a strained alkene such as norbornene is allowed to undergo metathesis with itself to give a polymer. Every cyclopentane ring in the product is *cis*-disubstituted, but the orientation of each cyclopentane ring with respect to its neighbors is random.

Problem 6.29 Draw a mechanism for the following ring-opening metathesis polymerization.




Alkyne metathesis catalysts have also been developed and applied to organic synthesis. The catalysts for these reactions either have an $M\equiv C$ triple bond (usually, $M = Mo$ or W) or are converted into compounds that have an $M\equiv C$ triple bond under the reaction conditions.



The mechanism of alkyne metathesis also consists of a series of [2 + 2] and [2 + 2] retrocycloadditions. The key intermediate, a metallacyclobutadiene, appears


to be antiaromatic, but apparently the metal uses a d orbital to form the $M=C$ π bond so that the ring is aromatic. In the first round of metathesis, $R = \text{Ph}$ (from the catalyst); subsequently, $R = \text{CH}_3$ (from the substrate).



6.5 Elimination Reactions

6.5.1 Oxidation of Alcohols (Cr, Ru)


Cr(VI) reagents are widely used to oxidize alcohols to aldehydes/ ketones or carboxylic acids. Commonly used reagents include CrO_3 , Jones reagent, PDC (pyridinium dichromate), and PCC (pyridinium chlorochromate). Alcohols coordinate to Cr(VI) reagents and undergo a β -hydride elimination to give the carbonyl compound and Cr(VI)-H. The hydride is deprotonated to give a Cr(IV) species, which may undergo further redox chemistry. If the oxidation is executed under aqueous conditions, the aldehyde may form a hydrate and then be oxidized further to the carboxylic acid.



Practical Cr-catalyzed oxidations of alcohols have not been developed, but $\text{Pr}_4\text{N}^+ \text{RuO}_4^-$ (TPAP, tetrapropylammonium perruthenate) catalyzes the oxidation of alcohols to aldehydes by a stoichiometric oxidant such as NMO, H_2O_2 , or O_2 itself. The Ru(VII) complex oxidizes alcohols by the same mechanism described for stoichiometric Cr species. The stoichiometric oxidant then reoxidizes the Ru(V) coproduct back to Ru(VII).

6.5.2 Decarbonylation of Aldehydes (Rh)

Wilkinson's catalyst $[(\text{Ph}_3\text{P})_3\text{RhCl}]$ mediates the decarbonylation of aldehydes ($\text{RCHO} \rightarrow \text{RH} + \text{CO}$). It's quite a remarkable reaction, yet the reaction mechanism is quite simple. Nucleophilic addition of Rh(I) to the aldehyde is followed by a 1,2-hydride shift from C to Rh to give an acyl Rh(III) complex, the product of an overall oxidative addition to the aldehyde C–H bond. Elimination of CO then gives the alkyl–Rh(III)–H complex, which undergoes reductive elimination to give the alkane and Rh(I). Unfortunately, the reaction is stoichiometric (not catalytic) in Rh, as the product complex $(\text{Ph}_3\text{P})_2\text{Rh}(\text{CO})\text{Cl}$ is inert toward oxidative addition. The electron-withdrawing CO group makes the Rh complex too electron-poor. Because Rh is so expensive, the reaction is useful only when the product is very valuable or when the reaction is carried out on very small amounts of material.



(a) dissociation; (b) elimination; (c) reductive elimination.

6.6 Summary

Metals catalyze a diverse set of reactions, and it is difficult to make generalizations, but some basic principles can be kept in mind.

- Any reaction involving a metal should be one of the typical reactions that have been discussed.
- Ligand association, dissociation, and substitution processes are facile, so the exact number of ligands on a metal center is usually not a major concern when mechanisms and catalytic cycles involving transition metals are drawn.
- The key step of reactions that involve addition of X–Y across a π bond is *insertion of the π bond into an M–X bond*. The M–X bond is often generated by oxidative addition of M across an X–Y bond.
- Substitution reactions of organic halides proceed by oxidative addition to the C–X bond.
- d^0 Metals are especially prone to undergo σ -bond metathesis reactions.
- Compounds with M=X bonds tend to undergo [2 + 2] cycloadditions, and metallacyclobutanes tend to undergo [2 + 2] retrocycloadditions.


- Third-row transition metals tend to undergo α -insertion and α -elimination reactions.
- Pd is used in a wide variety of popular reactions with diverse mechanistic pathways. How do you know how to start when facing a Pd-catalyzed reaction?
 - When a leaving group (usually attached to $C(sp^2)$ or $C(sp)$, allylic, or benzylic) undergoes substitution by a nucleophile, the first step of the catalytic cycle is usually oxidative addition of Pd(0) to the C–X bond. (In hydrogenolysis, though, the oxidative addition step is preceded in the catalytic cycle by generation of the $H-Pd(0)^-$ intermediate.)
 - When *nonpolar* X–Y is added across a π bond, the first step of the catalytic cycle is usually oxidative addition of Pd(0) across the X–Y σ bond. However, when a *nucleophile* adds to a π bond, a Pd(II) complex of the π bond may be the first intermediate.
 - The catalytic cycles of all Pd-catalyzed reactions other than nucleophilic substitutions at alkenes and C–H activation reactions begin with Pd(0), even when a Pd(II) complex is added to the reaction mixture.

No matter what the metal and what the transformation, remember to label the atoms, make a list of bonds to make and break, and obey Grossman's rule!


6.7 Problems

1. Palladium complexes are versatile and popular catalysts, catalyzing a wide variety of transformations in good yield under mild conditions. Draw mechanisms for the following Pd-catalyzed reactions.


(a)




(b) chiral diphosphinite = (*S*)-2,2'-bis(diphenylphosphinoxy)-1,1'-binaphthyl.




(c)




(d)




(e)




(f)




(g) dppf = 1,1'-bis(diphenylphosphino)ferrocene, a ligand for Pd.




(h)




(i)




(j)




- (k) One could draw a mechanism for this reaction that did not require Pd, but in fact both bond-forming steps are Pd-catalyzed.




- (l) DIBAL = *i*-Bu₂AlH.




- (m)




- (n)




- (o) This reaction is Pt-catalyzed, but its mechanism is very similar to many Pd-catalyzed reactions. *Note*: The active catalyst is a Pt(II) species, whereas H₂PtCl₆ is a Pt(IV) species (PtCl₄·2HCl).







- (p)





- (q)







(v) NIS = *N*-iodosuccinimide, and analog of NBS.




2. Many transition metals other than Pd also catalyze organic reactions. Draw mechanisms for the following metal-catalyzed reactions.




(b) Ar = 2,6-dimethylphenyl.





(c) BINAP = 2,2'-bis(diphenylphosphino)-1,1'-binaphthyl.




(d) BuLi is added to the Rh complex, *then* the substrate is added.




(e) Fcm = ferrocenylmethyl, a protecting group for N. Cy = cyclohexyl.




(g) R = *n*-hexyl. cod = 1,5-cyclooctadiene, a weak 4-electron donor ligand.




(h) Cp* = pentamethylcyclopentadienyl, C₅Me₅⁻.




(i) acac = acetylacetonate [MeC(O)CH=C(O⁻)Me].








- (k) The role of the AgOTf is simply to ionize the Rh–Cl bond and to make the Rh a more active catalyst.




- (l) acac = acetylacetonate $[\text{MeC}(\text{O})\text{CH}=\text{C}(\text{O}^-)\text{Me}]$.






3. Metal-mediated reactions are not as popular as metal-catalyzed ones, but they are still indispensable for some transformations. Draw mechanisms for the following metal-mediated reactions.









(d) The Grignard reagent reacts with the Ti complex *first*.




(g) $\text{CuBr}\cdot\text{SMe}_2$ is simply a more soluble form of CuBr .





4. The order of reactivity of aryl or alkenyl halides in Pd-catalyzed cross-couplings is $\text{I} > \text{Br} > \text{Cl}$. The preparation of enediynes by a Sonogashira coupling, however, is usually carried out with *cis*-dichloroethylene as the substrate; yields are considerably poorer when *cis*-dibromoethylene is used instead. Why? (*Hint*: The key intermediate may be more prone to undergo what side reaction when the dibromide or diiodide is used?)




Mixed-Mechanism Problems


7

In Chaps. 2–6 you learned how to draw polar basic, polar acidic, pericyclic, free-radical, and transition-metal-mediated and -catalyzed mechanisms. The reactions in the following problems may proceed by any of these mechanisms. Before you solve each problem, then, you need to identify its mechanistic class. See Chap. 1 if you have forgotten how to do it.

1. Solve the mechanism problems (problems 3 and 4) at the end of Chap. 1.
2. The following sequence of reactions was reported as part of a synthesis of the natural product qinghaosu, the active ingredient in a number of Chinese folk medicines. Qinghaosu is an antimalarial drug, a property of increasing importance as new strains of malaria appear that are resistant to the drugs that have been used until now.




Electronic supplementary material The online version of this chapter (https://doi.org/10.1007/978-3-030-28733-7_7) contains supplementary material, which is available to authorized users.




The compound in brackets has been shown to be an intermediate in the conversion of the hydroperoxide to the endoperoxide. Air is not required for its formation. In fact, it is isolable at low temperatures ($-20\text{ }^{\circ}\text{C}$) when air is excluded. If it is then exposed to air, it is transformed to the endoperoxide. Draw mechanisms for each of the steps in this sequence. Your mechanisms should take the preceding information into account.


3. The following questions are based on a total synthesis of isocomene, an angular triquinane natural product.
- (a) (i) Draw a mechanism for the formation of **1**.
 (ii) Name any pericyclic reactions in your mechanism. Be as specific as possible.
 (iii) Explain why **1** is obtained diastereoselectively.




- (b) Draw mechanisms for the conversion of **1** to **2** and the conversion of **2** to **3**.



- (c) (i) The conversion of **3** to **4** proceeds by a pericyclic mechanism. Name it.
 (ii) Does this reaction proceed thermally or photochemically?




- (d) Draw mechanisms for each transformation from **4** to **11** (isocomene).




4. The technology used in the preparation of isocomene can be modified to carry out several other interesting transformations.


- (a) Draw mechanisms for each transformation from **1** to **4**.




- (b) When **5** is treated with LiAlH_4 , an intermediate is obtained that retains the alcohol group. The $\text{Al}(\text{O}-i\text{-Pr})_3$ and acetone accomplish the oxidation of the alcohol to the corresponding ketone, which then spontaneously transforms into **6**. Draw mechanisms for the conversion of **5** to the intermediate alcohol and the conversion of the derived ketone to **6**.




- (c) Draw a mechanism for the conversion of **7** to **8**. LiDBB (lithium 4,4'-di-*t*-butylbiphenylide) is a source of Li metal that is soluble in THF; you may treat it as if it were Li metal.




5. Draw a reasonable mechanism for each step in the following synthetic sequence.



6. Two multistep mechanisms may be drawn for the following reaction. The two mechanisms differ both in the order of bond formation and the nature of some of the individual steps. Draw one or both of them.




7. Draw a reasonable mechanism for the following reaction.



Hints:

- (i) The order of bond formation is important.
 - (ii) One of the new bonds in the product is made, then broken, and then remade.
8. The following synthetic sequence appeared as the key part of a synthesis of some morphine analogs. Dbs = 2,6-dibenzosuberyl, a protecting group for N.



A Final Word

The purpose of this book has been to teach you how to draw a reasonable organic mechanism for almost any organic reaction you encounter. Sometimes, though, you may be unsure whether your mechanism is reasonable, sometimes more than one reasonable mechanism can be drawn, and sometimes what at first seems to be a reasonable mechanism may seem less reasonable when further information has been gathered. In these cases, you may want to go to the literature to see what is already known about the mechanism of the reaction.

Many sources discuss the mechanisms of particular organic reactions in greater detail than has been possible in this book. *March's Advanced Organic Chemistry*, 7th ed. (Wiley, 2013) is an indispensable reference for the synthetic organic chemist, both for its compendium of synthetic procedures, its detailed discussion of the mechanisms of many of these reactions, and its huge number of references to the primary and secondary literature. The *Organic Reactions* series includes discussions of the mechanisms of many widely used reactions. The encyclopedias *Comprehensive Organic Synthesis*, 2nd ed. (Elsevier, 2014), *Comprehensive Organometallic Chemistry II* (Pergamon, 1995), and *Comprehensive Organic Functional Group Transformations* (Pergamon, 1997) are also good places in which to look for the mechanisms of well-known reactions. The scientific publisher Thieme has compiled a database of ca. 12,000 English-language review articles of interest to synthetic organic chemists; you can download it for free from <https://www.thieme.de/en/thieme-chemistry/journals-synthesis-reviews-54851.htm>. This database includes reviews on almost every imaginable subject in organic synthesis. Reviews are sometimes the only places in the journal literature where reaction mechanisms are discussed in any detail.

Finally, the canon of knowledge presented in this text and the preceding references has been developed over a long period of time from difficult, detailed experimental investigations of the effects of concentration, solvent, isotopic substitution, substrate structure, and other variables on the rates and yields of reactions. In fact, writing a reasonable mechanism from one's own knowledge is a piece of cake compared with the work required to verify it experimentally. The experimental methods used to determine reaction mechanisms are discussed in great detail in several textbooks, including Carey and Sundberg, *Advanced Organic Chemistry*,

Part A; 5th ed. (Springer, 2007), Carroll, *Perspectives on Structure and Mechanism in Organic Chemistry*, 2nd ed. (Wiley, 2014), and Anslyn and Dougherty, *Modern Physical Organic Chemistry* (University Science Publishers, 2005). These books and others provide a more in-depth look at the very complex field of organic reaction mechanisms.

Index

A

- Abbreviations, for organic structures, 2, 2t
- Abiotic processes, 305
- Abstraction reactions, 353–354
- Acetalization, thermodynamics of, 165
- Acetals, 165, 168t
- Acetone, deprotonation, 23
- Acetyl, abbreviation for, 2t
- Acidity
- Brønsted, 18
 - of carbonyl compounds, 21
 - and pK_a Values, 18–21
 - polar reactions, 131–192
- Acids, pK_a values, 19t, 19–20
- Activation energy (ΔG^\ddagger), 22
- Acylation, 89–90
- Acylium ions, 157
- Addition reactions, 28–29
- free-radical, 284–285
 - metal-mediated
 - conjugate addition reactions, 370
 - dihydroxylation of alkenes, 365
 - hydrozirconation, 360
 - mercury-mediated nucleophilic, 368–370
 - Pauson–Khand reaction, 375–377
 - reductive coupling reactions, 371 - nucleophilic, 164–175
 - oxidative, 349–350
- 1,4-Addition reactions. *See* Conjugate addition reactions
- Addition–elimination mechanisms, 89
- at aromatic rings, 93
 - for substitutions at carbonyl C, 86–89
- Addition–elimination reactions
- electrophilic (S_EAr), 154
 - mechanisms in substitution reactions, 65
- Addition–fragmentation mechanisms, 144, 299
- Agostic bonds, 344
- AIBN, 287
- Alcohols
- acylation, 89
 - deoxygenation, 302–303
 - oxidation, 356, 405
 - production from σ -bond nucleophiles, 72–74
- Alcoholysis, acid-catalyzed, 164
- Aldehydes
- addition of σ -bond nucleophiles, 72–74
 - conversion to enol ethers, 166
 - decarbonylation, 406
 - interconversion with acetals, 165
 - structure of, 3
- Alder ene reaction, 197
- Aldol reactions, 76–77, 171
- Aldrin, 223
- Alkanes, halogenation of, 301
- Alkenes
- conjugate reactions, 84–86
 - dihydroxylation of, 365
 - electrophilic substitution, 163
 - HBr addition to, 306–307
 - hydroxylation by SeO_2 , 265–266
 - hydrozirconation, 360
 - isomerization, 402
 - ketene cycloaddition to, 238–239
 - as Lewis base donors, 345
 - nucleophilic additions, 368–370
 - nucleophilic substitution of, 396
 - nucleophilicity of, 38–39

- Alkenes (*cont.*)
oxidation reactions, 367–370
ozone reaction with, 227
photoexcited, 288
polymerization, 308, 361–363
reaction with dienes, 239–240
reaction with electrophiles, 32
substitution of, 151–154
- Alkoxy carbonylation, 385–387
- β -Alkoxyeliminations, transition metals, 351
- Alkoxy radicals, 285
- Alkyl halides
carbonylation of, 385–387
 S_N2 reactions with, 100
- Alkyl peroxides, 47
- Alkyl radicals, 283–286
- Alkyl shifts, 142–144, 254–256
- Alkylation, reductive, 168
- Alkylations, 156
- Alkyne metathesis, 404
- Alkynes
conjugate reactions with nucleophiles, 83–86
cyclo trimerization of, 363–365
as dienophiles, 222
as Lewis base donors, 345
nucleophilic addition to, 368
- Allyl cations, 204
- Allyl π system, 202
- Allylation reactions, 309
- Allylic sulfoxide-sulfenate rearrangements, 251–253
- Allylsilanes, 163
- Allylstannanes, 163
- Amides, hydrolysis of, 165
- Amination, reductive, 168
- Aminyl radicals, 285
- Anilines, aromatic substitution, 160–162
- Anionic H shift, 256
- Anionic oxy-Cope rearrangements, 248–249
- Antarafacial reactions, 214
- Antiaromatic compounds, and electron pairs, 17
- Anti-Markovnikov addition, 306–307
- Antiperiplanar orientation, 66
- Antitumor antibiotics, 292
- AO. *See* Atomic orbitals
- Aprotic solvents, 151
- Arbuzov reaction, 127
- Arene electrophilic substitution reactions, 163
- Arenes
Birch reduction, 321–322
nucleophilicity of, 38
production by cyclo trimerization, 363–365
reactivity of, 156
- Arndt–Eistert homologation, 112
- Aromatic compounds
electron pairs, 17–18
nucleophilic substitution, 94
- Aromaticity, 17–18
- Arrows, use of
curved, 7, 31
double, 6
double headed, 6
double-bodied, 219
half-headed (fish hooks), 8, 303
- Aryl, abbreviation, 2, 2t
- Atactic, definition, 363
- Atom abstraction reaction, 295
- Atomic orbitals (AOs)
of C, N, and O, 11–15
interaction of, 12
valence, 13
- Autoxidation, 304–305
- Aza-Cope rearrangements, 262
- Azide, 226, 330
- Azines, cyclic, 220–221
- Azomethine ylides, 225, 232, 237
- Azulene, 16
- B**
- Baeyer–Villiger oxidation, 112, 305
- Barton reactions, 318
- Barton-McCombie reaction, 303–304, 318
- Bases
classification as good or poor, 69–70
nonnucleophilic, 35
rearrangements promoted by, 109–110
- Basicity
Brønsted, 18
and group's leaving ability, 37
and nucleophilicity, 34
polar reactions, 61–130
- Beckmann rearrangement, 142
- Benzene
aromaticity, 17
Diels-Alder reactions, 220–221
as six-electron donor, 345
- Benzoin condensation, 79
- Benzophenone ketyl, 290
- Benzoyl, abbreviation, 2t
- Benzoyl peroxide, 287
- Benzyl, abbreviation, 2t
- Benzylic acid rearrangement, 110–112
- Benzylic radicals, 284
- Benzynes, 68
- Bergman cyclization, 291–292
- BHT, 286, 295

- Bicyclic compounds, 10
Birch reductions, 321–322
Bischler-Napieralski reaction, 156
Bond dissociation energies (BDEs), 268, 296
Boron, 114
Bouveault-Blanc reduction, 321
Bredt's rule, 10
Bromine (Br₂), halogenation reactions, 301–302
Bromoform, 106
Brønsted acidity, 18
Brønsted basicity, 18
Buchwald-Hartwig amination, 391
Butadienes
 cyclobutene electrocyclic equilibrium with, 202–203
 electrocyclic ring closing, 210
 MOs of, 201
 visualization of stereochemical results, 211
Butyl, abbreviation, 2t
sec-butyl, abbreviation, 2t
tert-butyl, abbreviation, 2t
- C**
Calicheamycin γ_1 , 292
CAN (ceric ammonium nitrate), 290
Captodative effect, 285
Carbenes
 and 1,2-shifts, 109
 combination with nucleophiles, 109
 electrophilicity of, 39
 generation, 107, 287
 insertion into C–H σ bond, 108
 and intersystem crossing, 332
 reaction of, 105–109
 singlet, 105
 triplet, 106, 330–331
Carbenium ions. *See* Carbocations
Carbenoids, 106
Carbocations, 131–145
 formation of, 37
 mechanism for stabilization, 132–136
 methods of generation, 182
 orbital interaction diagram for, 267
 protonation in generation of, 136–138
 in S_N1 and E1 mechanisms, 149–151
 stabilization, 286
 typical reactions, 139–145, 182
Carbon
 formal charge of, 4
 migration from B to, 114
 migration to C, 110–112
 migration to O or N, 112–113
 S_N2 mechanism, 146
 tetraivalent, 9
Carbon-carbon bond-cleaving reactions, 317–319
Carbon-carbon bond-forming reactions, 308–314
Carbonium ions. *See* Carbocations
Carbon(sp³)-X electrophiles, 66–71
Carbon(sp²)-X σ bonds, 86–100
Carbon(sp³)-X σ bonds, 61–71
Carbonyl complexes, hydrosilylation of, 366–367
Carbonyl compounds
 acidity of, 21
 addition and substitution reactions, 164
 addition of nucleophiles, 72–83
 conjugate addition reactions, 370
 kinetic stabilities of, 72
 McMurry coupling reaction, 371
 oxidation, 266–267
 photoexcitation, 317
 substitution at alkenyl C, 93–98
 substitution at aryl C, 93–98
 substitution at C, 86–92
 thermodynamic stabilities of, 72
Carbonyl interconversions, 168t
Carbonyl oxides, 228
Carbonyl photochemistry, 317–319
Carbonylation, of alkyl halides, 385–387
C–H bond activation, 349
Chain reactions, free-radical
 mechanism of, 297
 recognition of, 302
 steps in, 47
Charges. *See* Formal charges
Cheletropic reactions, 195, 231, 241
Chemical bonds, and AO interactions, 13
Chemical equilibrium, visualization, 6
Chlorine (Cl), 302
Chlorofluorocarbons (CFCs), 333
Chloroform, 106
Cholesterol, biosynthesis, 188
Chromium (Cr), 357
Chugaev reaction, 266
Claisen condensations, 90
Claisen rearrangements, 196, 247–250
Cobalt (Co)
 hydroformylation, 359
 metal-catalyzed cyclotrimerization, 380–383
 Pauson-Khand reaction, 375–377
 propargyl substitution, 401
Conjugate addition reactions
 to α,β -unsaturated carbonyl compounds, 370

- Conjugate addition reactions (*cont.*)
 of Grignard reagents, 371
 the Michael reaction, 83–86
- Conjugate reduction, 319–321
- Conrotatory, definition, 210
- Cope elimination, 265–266
- Cope rearrangements, 196, 247–250, 259–265
- Copper (Cu)
 conjugate addition reactions, 370
 metal-catalyzed cyclopropanation, 363–365
 Ullman reaction, 394
- Cossee mechanism, 362
- Covalent bonds, and oxidation state, 347
- C(sp³)-X, substitution and
 elimination reactions, 100–109,
 145–149
- Curtius degradation, 162
- Curtius rearrangement, 109–113
- Cyanohydrins, 75
- Cyclization reactions, 311–313
- Cycloaddition reactions, 194–195, 228–233,
 245–247 *See also* Retro
 cycloaddition reactions
- 1,3-dipolar, 245–247
- [2 + 1], 195, 231 *See also* Cheletropic
 reactions
- [2 + 2]
 of alkenes, 319
 in dihydroxylation of alkenes, 366
 light promotion, 240–241
 and transition metals, 354
 in olefin metathesis reactions, 403
 photochemical reactions, 200
 under thermal conditions, 237–240
- [3 + 2]
 in dihydroxylation of alkenes, 366
- electron reactions, 235–236
- [4+1], 230
- [4+2], 194–195, 231
 thermal reactions, 200
- [4+3], 195, 231, 241
- [4+4], 231
- [6+4], 195, 231, 241
- [8+2], 195, 231
 Diels-Alder reaction, 218–225
 dipolar, 225–227
 identifying, 231–232
 ketenes to alkenes, 238–239
 ketenes to cycloalkenes, 245–247
 naming conventions, 194
 regioselectivity, 233–234
 stereoselectivity, 242–247
- Stereospecificity, 235–236
- Woodward-Hoffmann rules, 240–232
- Cycloalkenes, 246–247
- Cycloaromatizations
 and free radical generation, 286
 generation of diradicals, 291
 synthetic potential of, 328
- Cyclobutadiene, 17
- Cyclobutenes
 electrocyclic reactions, 202–203
 visualization of stereochemical, 211
- Cyclooctatetraene, 17
- Cyclohexadienes, 203, 321–323
- Cyclopentadienes, 18, 220
- Cyclopentadienide, 17
- Cyclopentadienones, 17, 231
- Cyclopentadienyl groups, 345
- Cyclopropanations, 107, 363
- Cyclopropanones, 207
- Cyclopropyl cations, 207–208
- Cyclopropylmethyl radicals, 315
- Cyclotrimerization, 380
- D**
- D Electron count, and oxidation stat, 347
- Danishefsky's diene, 221
- Darzens glycidic ester synthesis, 125
- Dative bonds, 343
- DDQ (2,3-Dichloro-5,6-dicyano-
 1,4-benzoquinone), 291
- Decarbonylation, 406
- Decarboxylation reaction, 175–179
- Dehalogenation reactions, 302
- Dehydrogenative silane polymerization, 405
- Dewar benzene, 215
- Dewar–Chatt–Duncanson model, 346
- Diazo compounds, 226, 330
- Diazonium salts, 161–162
- Diborylation, 358
- Dibromoethane, 104
- Dieckmann condensations, 90
- Diels–Alder reactions, 194 *See also*
 Cycloaddition reactions, [4 + 2]
 acceleration by Lewis acids, 199
 of cobaltcyclopentadiene, 383
 cycloadditions, 218–226
 endo rule, 243–247
 regioselectivity, 233–235
 stereoselectivity, 242–247
 two-step polar mechanism, 199
- Dienes
 Cope rearrangements of, 259
 and the Diels-Alder reaction, 221–222
 as four-electron donors, 345

- Dienophiles, and the Diels-Alder reaction, 221
Diethyl azodicarboxylate (DEAD), 116
Dihydropyran (DHP), 152
Dihydroxylation, of alkenes, 365
 β -Diketones, 166
trans-3,4-dimethylcyclobutene, 216
2,4-Dinitrofluorobenzene (Sanger's reagent),
 reaction with amines, 93
1,3-Dipolar reactions, 225
1,3-Dipoles, 225–226
1,2-Diradicals, 288
 and photoexcitation, 317
1,4-Diradicals, 317
Disproportionation, 297
Disrotatory, definition, 210
DMAP (4-dimethylaminopyridine), 89
DNA, attack by antitumor antibiotics, 292
Dötz Reaction, 377
Duocarmycin, 123
Dynemicin, 292
- E**
E1cb mechanisms, for β -elimination, 66–69
E1 mechanism, for β -elimination, 149–150
E2 mechanisms, for (β -elimination, 66–69
Eighteen electron rule, 343
Electrocyclic equilibrium, 207
Electrocyclic reactions, 198, 202–218
 stereoselectivity, 216–218
 stereospecificity, 210–211
 typical reactions, 202–209
 Woodward-Hoffmann rules for, 213–215
Electrocyclic ring closing reactions
 of butadiene, 210
 charge neutralization and, 207–208
 1,3,5-hexatrienes, 212
 identification of, 208
Electrocyclic ring opening reactions
 allyl and pentadienyl cations in, 204
 of benzocyclobutene, 203
 of cyclopropyl cations, 207–208
 halocyclopropanes, 217–218
 of *trans*-3,4-dimethylcyclobutene, 216
Electron count, of transition metals, 343–347
Electron-deficiency, and chemical reactivity, 5
Electron demand
 normal, 221
Electronegative atoms, and resonance, 9
Electrons
 in chemistry of metal complexes, 341–356
 in resonance structures, 9
Electrophiles
 allylic leaving groups, 64
 carbon(sp³)-X, 66–69
 and leaving groups, 36–38, 41
 Lewis acid, 36
 π bonds, 36, 66–70
 in polar reactions, 30
 σ bond, 36–38
 substitution vs. elimination, 69–71
Electrophilic addition, 151–154
Electrophilic aliphatic substitution, 163–164
Electrophilic aromatic substitution, 154–161
Electrophilicity
 and chemical reactivity, 5
 confusion with formal positive charge, 39
Electropositivity, 5
Elimination–addition reactions
 mechanism, 65, 89
 substitution by, 93–104
 and substitution on aryl rings, 94, 97
Elimination reactions, 29–30
 Cope, 266
 at C(sp³)-X σ bonds, 61–71, 100–109
 dehydrogenative silane polymerization, 405
 E2, 71
 α -hydride, 362
 β -hydride, 351
 oxidation of alcohols, 405
 prediction of, 69t, 151
 selenoxide, 265–266
 α -Elimination reactions
 generation and reaction of carbenes,
 105–106
 and transition metals, 352
 β -Elimination reactions
 at C(sp³)-X, 149–151
 E1, 149–151
 E2, 66–69
 E1cb, 66–69
 transition metals, 351
Enamines, 75
Endo products, 245–246
Endo rule, 243
Endo selectivity, 245
Endothermic reactions, 22
Ene diyne antitumor antibiotics, 292
Ene reactions, 196–197, 264–267
Enolates, 76, 91, 320–321
Enol ethers, 167, 167t
Enols, 170t
Enthalpy (ΔH°), 22
Entropy (ΔS°), 22
Enynes, 373, 377
Equilibrium
 and reversibility, 23
 and tautomerism, 21
Ergocalciferol, 253

- Ergosterol, 215
Esperamycin, 292
Esters
 addition of enolates, 91
 reaction with nucleophiles, 91
 structure of, 3
 transesterification, 87
Ethyl, abbreviation, 2t
Ethyl acrylate, 242–243
Ethylene, polymerization, 308, 361
Exo products, 245
Exothermic reactions, 22
- F**
Favorable reactions, 22–23
Favorskii rearrangements, 111, 206–209
Fischer indole synthesis, 278
Five-electron donors, 345
Formal charges
 assignment of, 4–10
 confusion with electrophilicity, 38
 of even-electron atoms, 4t
 of odd-electron atoms, 4t
 in resonance structures, 9
Four-electron donors, 345
Fragmentation reactions, 267–268
 of carbocation in EI mechanism, 149
 carbocation reactions, 139–142
 of a radical, 294
Free energy (ΔG°), 22–23
Free radicals
 generation, 286–292
 persistent, 286
 stability, 283–286
Free-radical reactions, 30, 269, 319
 addition and fragmentation, 284–285
 mechanisms for, 45–46
 solvents of choice, 296
 substitution, 300
 typical, 292–299
Friedel-Crafts reactions, 156
Frontier molecular orbital (FMO) theory
 and butadiene electrocyclic ring closing, 211
 and Diels-Alder reactions, 222–225, 233
 and sigmatropic rearrangements, 253–256
Furan, 16
- G**
Galvinoxyl, 286
Germanes, 405
Gilman reagents, 341
Glucals, 224
Glycosylation reaction, 147
Green mechanism, 362
Grignard reactions
 dibromoethane in, 104
 metal insertion reaction, 98–100
Grignard reagents
 addition to carbonyl compounds, 73
 conjugate addition reactions of, 370
 in imine production, 83
 reaction with esters, 91–92
Grossman's rule
 and carbocations, 132
 and conventions of drawing structures, 2–3
 and drawing mechanisms, 25–28
Ground state, of resonance structures, 10–11
- H**
 β -Halide eliminations, 351
Halocyclopropanes, 217
Halogenation, of alkanes, 301
Halogen-metal exchange
 C(sp²)-X σ bonds, 86–100
 metal insertion, 98–100, 104–105
Halonium ions, 152–153
Hammond postulate
 and carbocations, 132
 and Markovnikov's role, 152
 on TSs, 24
Heck reaction, 388–389
Hemiacetals, 74, 166, 168t
Hemiaminals, 75
Hetero-ene reaction, 197
Heterolytic bond strength, 296
Hexachlorocyclopentadiene, 223
1,3,5-Hexatrienes
 cyclohexadiene equilibrium with, 203
 electrocyclic ring closings, 212
 MOs of, 202
Highest occupied molecular orbitals (HOMOs), 200
Hillman-Baylis reaction, 126
Hofmann-Loeffler-Freytag reaction, 305
Hofmann rearrangement, 113
Homogenesis, 297
Homolytic bond strengths, 268, 296
H shifts [1,3] thermal, 255
Hunsdiecker reaction, 316
Hybrid orbitals, 13–15
Hybridization
 molecular shape, 11–15
 sp, 14
 sp², 13, 14
 sp³, 14
 and stability of carbocations, 135, 136
Hydrates, 74

- Hydrazone, 74
 α -Hydride abstraction, 400–401
 β -Hydride abstraction, 372, 373–374
 α -Hydride eliminations, 362
 β -Hydride eliminations, 351, 360–361
1,2-Hydride shifts, 142–144
1,5-Hydride shifts, 141
Hydroboration, 358
Hydrochlorofluorocarbons (HCFCs), 333
Hydroformylation, 359
Hydrogen
 addition across π bonds, 319
 near reaction centers, 2
 tracking, 2
Hydrogenation, metal-catalyzed, 357
Hydrogenolysis, 384
Hydrolysis, acid-catalyzed, 164
Hydrometallation, metal-catalyzed, 356–359
Hydrosilylation, 358, 365–367
Hydrostannylation, 358
Hydroxylic solvents, 151
Hydroxyl radicals, 265
Hydrozirconation, 360
Hyperconjugation, 134
- I**
Imines, 74, 83, 288 *See also* Schiff bases
Iminium ions, 82, 169
Indole, 16
Insertions, transition metals, 350–352
Intermediates, of reactions, 24
Intersystem crossing, 332
Ipso directors, 159
Iron (Fe), 368–370
Isobutyl, abbreviation, 2, 2t
Isopropyl, abbreviation, 2t
Isotactic, 362–363
- J**
Jacobsen epoxidation, 364
Jacobsen-Katsuki epoxidation, 364
- K**
Ketals. *See* Acetals
Ketenes
 cycloaddition to alkenes, 245–246
 cycloadditions to cycloalkenes, 237–239
 production by β -elimination, 68
Ketones
 acylation of, 90
 addition of σ -bond nucleophiles to, 72
 conjugate reduction of, 320
 conversion to enol ethers, 167
 α -deoxygenation of, 323
 interconversions, 168t
 pinacol coupling of, 324
 reaction with peracids, 113–114
 structure of, 3
Ketyl radical anions, 290
KHMSD, 104
Kinetics, and thermodynamics, 22–25
Knoevenagel reaction, 82
Kulinkovich cyclopropanation, 374
Kumada coupling, 389–390
- L**
Lanosterol, 188
Lanthanide complexes, 362
LDA, 104
Leaving groups
 allylic, 64
 attached to C(sp³), 61–62
 differing abilities, 37–38
 and electrophiles, 36–39
 enolate as, 91
 order of abilities, 38t
 substitution by nucleophiles, 86–93
LeChâtelier's principle, 23
Lewis acid electrophiles, 36
Lewis acids
 acceleration of Diels-Alder reactions, 199
 in carbocation generation, 136–138
Lewis base donors, 345
Lewis bases, 343
Lewis structures, 4–10
 generation of resonance structures, 7–9
 rules for stability of, 6
Lewis theory, and hybridization, 11
Ligand addition reactions, 348–349
Ligand dissociation reactions, 348–349
Light, visible (*h ν*), 47, 240–241, 269
Lindlar catalyst, 356
Lithiation, 98
Lone pairs
 1,2-anionic rearrangements, 329–330
 ligands as electron, 345
 and stabilization of carbocations, 132–134
Lone-pair nucleophiles in S_N2 substitutions, 64
Lowest unoccupied molecular orbitals (LUMOs), 200
- M**
Magnesium (Mg), 86–100
Manganese (Mn), 363–365
Mannich reaction, 172, 262–263
Markovnikov's rule, 152

- McLafferty rearrangement, 317
McMurry coupling reaction, 371–372
Mechanisms *See also* Specific mechanisms
 classes of, 30
 conventions in drawing of, 25–26
 steps in drawing of, 50
Meier's rule, 136
Meisenheimer complex, 93
Mercury (Hg), 368
Mesyl, abbreviation, 2, 2t
Meta directors, 158
Metal hydrides, 72–92
Metal insertion
 C(sp²)-X σ bonds, 86–100
 halogen-metal exchange, 104–105
Metal-catalyzed reactions, 30
 addition reactions, 358–366
 alkene polymerization, 361–363
 cyclopropanation, 363
 cyclotrimerization, 380–383
 hydroformylation, 359
 hydrogenation, 356, 359
 hydrometallation, 356, 359
 nucleophilic addition to alkynes,
 368–370
 oxidation of alkenes and sulfides,
 368–370
 conjugate addition reactions, of Grignard
 reagents, 371
 elimination reactions, 405
 rearrangement reactions
 alkene isomerization, 402
 olefin metathesis, 402, 403
 substitution reactions, 384–401
 allylic substitution, 394–395
 Buchwald-Hartwig reaction, 391
 carbonylation of alkyl halides, 385–387
 Heck reaction, 388
 hydrogenolysis, 384–385
 Kumada coupling, 389–390
 Negative coupling, 389–390
 Sonogashira coupling, 389–390, 393
 Stille coupling, 389–390
 Suzuki coupling, 389–390
 Ullman reaction, 394
 Wacker oxidation, 396–397
 transition metals, 358
Metalla-ene reaction, 264
Metallaketenes, 346
Metallocenes, 361
Metals *See also* Transition metals
 calculation of d electron count, 347
 calculation of total electron count, 345
 reductions with, 319–323
1-Methoxybutadiene, 242–243
Methyl, abbreviation, 2t
Methylalumoxane, 361
Michael addition, 171
Michael reaction, 116–118, 130
Migration. *See* Rearrangements
Migratory insertion, 350
Mitsunobu reaction, 116–118
Mixed mechanism problems, 415–422
Molecular orbital (MO) theory, 11
Molecular orbitals (MOs)
 antibonding, 12
 bonding, 12
 frontier, 200
 polyene, 200–202
 symmetries of, 201–202
Molecular shape, hybridization, 11–15
Molybdenum (Mo), 403
Monsanto process, 387

N
Naphthalene, 18
Nazarov cyclization, 204
NBS, 301
Negishi coupling, 390
Neocarzinostatin, 292
Nickel (Ni), 363–364, 389–390
Nitrene insertion reaction, 331
Nitrenes
 generation, 287
 triplet, 330–331
Nitric oxide (NO), 245
Nitrile oxides, 226–227
Nitriles, 83, 165
Nitrilimines, 226
Nitrilium ions, 156
Nitrogen
 formal charge of, 4
 migration from C to, 113
 tetravalent, 9
Nitrones, 226, 294
Nitroso compounds, 294
Nitroxides, 245
Nitroxyls, 285
Nonaromatic compounds, and p orbitals, 17
Nonchain mechanisms, 297
Nonconcerted mechanisms, 199
Norcaradiene, 203
Norrish type I cleavage, 317
Norrish type II cleavage, 317
Nucleophiles
 addition reaction of carbocations, 139
 addition to electrophilic π bonds, 72–83
 carbon, 170–175

- classification as good or poor, 69–71
combination with carbenes, 109
heteroatom, 164–169
lone-pair, 31
 under acidic and basic conditions, 42
 in S_N2 substitutions, 64
 π -bond, 31
 under acidic and basic conditions, 43
 complex metal hydrides, 72
 Grignard reagents, 72
 organolithium, 72
 in S_N2 substitutions, 64
in polar reaction mechanisms, 31–41
 σ -bond, 32
 under acidic and basic conditions, 42–43
 in S_N2 substitutions, 64
 substitution for leaving groups, 82–85
Nucleophilic addition, 164–175
Nucleophilicities, 33–34
- O**
- Octet rule, 6
Olefin metathesis, 403
One-electron donors, 343
One-electron transfer, 298
Orbitals, 11 *See also* Atomic orbitals (AOs),
 Molecular orbitals (MOs)
 d orbitals, 12
 f orbitals, 12
 hybrid, 13–14
 overlap, 12
 p orbitals
 and aromaticity, 15
 description, 11, 12
 shape of, 12
 and sp hybridization, 14
 s orbitals, 11, 14
Organic acids, pK_a values, 19t, 19–20
Organic substructures, abbreviations for, 2t
Organolithium compounds
 addition to carbonyl compounds, 72
 in halogen-metal exchange, 105
 in imine production, 83
 reaction with esters, 91
 S_N2 reactions with alkyl halides, 99–100
Orthoester Claisen rearrangements, 247–249
Ortho–para directors, 158
Ortho–para rule, 233–234
Osmate ester, 365
Osmium (Os), 365, 367–370
Out-endo-cis rule, 243
Oxidation reactions
 of alcohols, 357, 365
 metal-catalyzed, 368–369
Oxidation state
 and d electron count, 347
 of a metal, 343
 electrons and, 347
Oxidative addition reactions, 349–350, 386
Oxime, 74
Oxime ethers, 74
Oxyallyl cations, 205
Oxy-Cope rearrangements, 199, 248–249, 269
Oxygen
 generation of free-radicals, 47
 migration from B to, 114
 migration from C to, 112–113
Oxygen diradical, 285
Ozone, 225, 227
Ozonolysis, 228
- P**
- Palladium (Pd)
 and addition of nucleophile to alkenes, 370
 allylic substitution, 394–395
 carbonylation of alkyl halides, 385–387
 Heck reaction, 388
 hydrogenation, 357–358
 hydrogenolysis, 384–385
 metal-catalyzed coupling reactions,
 390–391
 nucleophilic addition, 396
 nucleophilic substitution, 396–398
Paterno–Büchi reaction, 228
Pauson–Khand reaction, 375–377
1,3-Pentadiene, 18
Pentadienyl cations, 204
Pentadienyl π system, 202
Peracids, 112–113
Perchlorotriyl, 286
Pericyclic mechanisms, drawing, 268–269
Pericyclic reactions, 30, 193–281
 bond changes in, 198t
 classes of, 193–200
 features of, 48–49
 Woodward–Hoffmann rules for, 268
Periodic table, and nucleophilicity, 33
Periplanar orientation, 66
Peroxides, 306
Phenanthrene, 15
Phenol, industrial synthesis of, 305
Phenonium ion, 144
Phenyl, abbreviation, 2t
Phosphorus, and resonance structures, 10
Photoaffinity labeling, 331

- Photochemistry, carbonyl, 317–319
Photocycloadditions, 228, 246–247
Photo-Wolff rearrangements, 111, 332
Pi bond electrophiles, 36
Pi bond nucleophiles, 32
Pi bonds
 addition of hydrogen, 319–323
 additions by free radicals, 292–293
 electrophilic addition of nucleophiles, 72–83
 electrophilic addition to, 151
 and generation of resonance structures, 7–9
 nucleophilic substitution, 145, 154, 164
 photochemical excitation, 286
Pi complexes, 344
Pi system, 213
Pinacol coupling, 318, 324
Pinacol rearrangement, 143–144
p*K_a* rule, 39
p*K_a* values, 18–21
Platinum (Pt), 358–359
Polar aprotic solvents, 151
Polyene molecular orbitals, 200–202
Polar elimination mechanisms, 119t
Polar mechanisms, 31–43
Polar reactions, 30
 under acidic conditions, 131–191
 under basic conditions, 61–130
 conditions for, 39–43
Polar substitution mechanisms, 119t
Polyethylene, 308
Polymer chains, 308–309
Polymerization
 alkenes, 361–363
 dehydrogenative silane, 405
 ethylene to polyethylene, 308
 lanthanide complexes in, 362
Polymers, 308
Polysaccharides, synthesis of, 225
Porphines, 368
Potassium permanganate, 367
Potier–Polonovski rearrangement, 128
Precalciferol, 215, 253
Propargyl substitution, 401
Propyl, abbreviation, 2t
Protonation, 136–138
Pummerer rearrangement, 92
Pyridine, 17
Pyrrole, 17
Pyrilium, 17
- Q**
Quinones, 291
- R**
Radical anions, 289
Radical cations, 290
Radical chain mechanism, 94
Radical clocks, 315
Radical-radical combinations, 297
Radicals. *See also* Free radicals
 and one-electron transfer, 298
 orbital interaction diagram for, 284
Rate of reactions, 22
Reaction centers, 2
Reaction coordinate diagrams, 24
Rearrangements, 28–29
 alkene isomerization, 402
 allylic sulfoxide-sulfonate, 251–253
 1,2-anionic, 329–330
 anionic oxy-Cope, 248–249
 base-promoted, 109
 Beckman, 142
 benzylic acid, 110
 Claisen, 196, 247–249
 Cope, 247–249, 259–265
 Curtius, 109
 Favorskii, 111, 206–208
 Hofmann, 113
 McLafferty, 317
 olefin metathesis, 402
 orthoester Claisen, 247–249
 oxy-Cope, 199, 248–249, 269
 photo-Wolff, 112
 pinacol, 143–144
 Potier–Polonovski, 128
 reactions of carbocations, 139–144
 retro-Cope, 248–249
 semibenzylic acid, 111
 1,2-shifts, 141–144
 sigmatropic. *See*
 Sigmatropic rearrangements
 Stevens, 259, 329–330
 Wallach, 188
 Wittig, 252–253, 329
 Wolff, 109, 111, 229–231
Reductive coupling reactions, 323–326,
 371–375
Reductive elimination reactions, 349–350
Reformatsky reaction, 104
Regioselectivity
 of cycloadditions, 232–234
 of pericyclic reactions, 194
Resonance, and stabilization of carbocations,
 132–134
Resonance hybrids, 6
Resonance structure

- definition of, 6
- dominant, 6
- and double headed arrows, 6
- and energy of carbonyl compounds, 20
- generation of, 7–8
- rules for stability of, 6
- 11-cis-Retinal, 289
- 11-trans-Retinal, 289
- Retinal isomerase, 288
- Retro-aldol reactions, 82, 175
- Retro-cope rearrangements, 248
- Retro-cycloaddition reactions, 194–195
 - See also Cycloaddition reactions
 - [2+2], in olefin metathesis reactions, 403
 - [4 + 1], 195, 231, 241 See also Cheletropic reactions
- Retro-ene mechanisms, 266–267
- Retro-ene reaction, 175
- Retro-hetero-ene mechanisms, 267
- Retro-Michael reactions, 175
- Retrosynthetic arrow, 219
- Reversible reactions, 23
- Rhenium (Rh)
 - alkene isomerization, 402
 - carbonylation of alkyl halides, 385–387
 - decarbonylation of aldehydes, 406
 - hydroformylation, 359
 - late-metal-catalyzed hydrogenation, 358
 - metal-catalyzed cyclopropanation, 363
- Ring closures, 310 See also Electrocyclic ring closing
- Ring-closing metathesis reaction (RCM), 403
- Ring-opening metathesis polymerization (ROMP), 404
- Robinson annulation, 84, 129, 171
- Rose Bengal, 225
- Ruthenium (Ru), 405
- S**
- Sakurai reaction, 163
- Salens, 364
- Samarium diiodide, 323
- Sanger's reagent (2,4-dinitrofluorobenzene), 93
- Schiff bases, 74 See also Imines
- Schwartz reagent, 360
- Selenium dioxide, 264–265
- Selenoxide elimination, 266
- Semibenzilic acid mechanism, 206–207
- Semibenzilic acid rearrangement, 111
- Shapiro reactions, 106, 107
- Sharpless dihydroxylation, 367
- Sharpless epoxidation, 365
- 1,2-Shifts
 - addition-fragmentation mechanism, 144
 - alkyl shifts, 142–144, 256–257
 - anionic H shift, 255
 - and carbenes, 109
 - hydride shifts, 141–144
 - sigmatropic rearrangements, 253–255
- Sigma bond electrophiles, 36
- Sigma bond metathesis
 - and hydrozirconation, 360
 - in polymerization reactions, 362
 - reactions and transition metals, 353
- Sigma bonding nucleophiles, 31
- Sigma bonding patterns, 5
- Sigma bonds
 - and drawing of mechanisms, 26
 - and generation of free radicals, 47
 - homolysis and free radical generation, 286–287
 - and hybridization, 14
 - metal insertion, 98–100
 - and rearrangement reactions, 109–114
 - substitution and elimination, 61–71, 100–109
 - substitution at carbonyl C, 86–100
 - and tautomers, 22
- Sigma complexes, 344
- Sigmatropic rearrangements, 195, 247–264
 - [1,2], 195–196, 254–257, 329
 - anionic H shift, 255–256 See also Alkyl shifts; Hydride shifts; 1,2-Shifts
 - [1,3], 196, 253–256
 - photochemical suprafacial, 256–258
 - [1,5], 196, 251–254
 - around cyclopentadienyl group, 250, 251
 - of a diene, 261–262
 - [1,7], 253–254, 257–258
 - [2,3], 198, 253–255, 256–257
 - [3,3], 195, 254–255 See also Claisen rearrangements; Cope rearrangements
 - aza-Cope, 262, 263
 - frequency of use, 247–249
 - stereoselectivity, 259–263
 - stereospecificity, 254–258
 - typical reactions, 247–253
 - Woodward-Hoffmann rules, 258
- Simmons–Smith reagent, 106–107
- Six-electron donors, 345
- Sonogashira coupling, 389, 393
- Spin trapping reagents, 294
- Stabilization, and aromaticity, 18

- Stannanes, 315
- Stereochemistry, representations of, 3
- Stereoelectronic effects, 310
- Stereoselectivity
- cycloaddition reactions, 242–247
 - of electrocyclic reactions, 216–217
 - of pericyclic reactions, 193
 - sigmatropic rearrangements, 258–263
- Stereospecificity
- of Diels–Alder reactions, 235–236
 - electrocyclic reactions, 210
 - of electrocyclic reactions, 234–235
 - of pericyclic reactions, 193, 199–200
 - sigmatropic rearrangements, 253–258
- Stevens rearrangement, 259, 329
- Stiles reaction, 162
- Stille coupling, 390–392
- carbonylative, 392–393
- Strain, and group's leaving ability, 37–38
- Substitution mechanisms
- elimination-addition, 102–103
 - nonchain electron transfer, 332
 - polar, 119
 - S_N1 , 349
 - S_N2 , 349
 - $S_{RN}1$, 290
 - initiation by electron transfer, 332
 - in organometallic systems, 349
- Substitution reactions, 29
- addition-elimination mechanism, 102–103
 - at alkenyl C, 93–98
 - at aryl C, 93–98
 - at carbonyl C, 86–92
 - at $C(sp^3)-X$, 145–151
 - at $C(sp^3)-X$ σ bonds, 61–71, 100–109
 - for electrophiles with allylic leaving groups, 64
 - elimination-addition mechanism, 65
 - free-radical, 301–305
 - hydrogenolysis, 384–385
 - ligand, 348–349
 - metal-catalyzed reactions, 385–394
 - metal-mediated
 - decarbonylation of aldehydes, 406
 - oxidation of alcohols, 356
 - propargyl substitution, 401
 - Tebbe reaction, 400–401
 - Ullman reaction, 394 - modes of bond breaking, 119–120
 - nucleophilic, 61–63
 - prediction of, 70, 139
 - S_EAr mechanism, 154
 - S_N1 mechanism, 30, 145–148
 - S_N2 mechanism, 63–64
 - at $C(sp^3)-X$, 145–149
 - effect of leaving group ability of X^- , 71
 - leaving group abilities in, 36–37
 - organolithium compounds with alkyl halides, 100
 - at stereogenic S atoms, 64
 - S_N2' mechanism, 65
 - S_NAr mechanism, 93
 - $S_{RN}I$ mechanism
 - in aromatic substitution reactions, 30
 - on aryl rings, 94
 - radical cations, 299
- α -Substitution reactions, 164
- γ -Substitution reactions, 164
- Substitutions
- aromatic, 162–163
 - electrophilic aliphatic, 163–164
 - electrophilic aromatic, 154–161
 - ipso, 159
 - nucleophilic, 164–182
 - at nucleophilic π bonds, 154–164
 - prediction of, 151
- Sulfides, 368–370
- Sulfonate ester, 3
- Sulfone, 3
- Sulfoxide, 3
- Sulfur atoms
- formal charge of, 4
 - and resonance structures, 10
 - S_N2 substitution reactions at, 64
- Suprafacial reactions, 213, 214
- Suzuki coupling, 389–392
- Swern oxidation, 115–116
- Syndiotactic, 363
- Synperiplanar orientation, 66
- T**
- Z-Tachysterol, 215
- Tautomerism, 21
- Tebbe reaction, 400–401
- TEMPO, 285
- Thermodynamics, and kinetics, 22–25
- Thiophene, 16
- Three-electron donors, 344
- Thymine dimer, 229
- Titanium (Ti)
- hydrogenation, 367
 - in hydrosilylation, 367
 - oxidation reactions, 367–370
 - reductive coupling reactions, 371–372
 - silane polymerization, 405

- Tebbe reaction, 400–401
Torquoselectivity, 216–218
Tosyl, abbreviation, 2, 2t
Total electron count, calculation, 345
Transesterification, of esters, 87
Transformations, classes of, 28–29
Transition metals
 catalyzed and mediated reactions, 341–419
 chemistry of, 341–355
 ligand addition-dissociation reactions, 348
 and the octet rule, 6
 reactions catalyzed by, 49
 reactions mediated by, 49
 reductive elimination reactions, 350
Transition states (TS), 24
 Hammond postulate, 24
 in reaction coordinate diagram, 24
Transmetallations, 353
Transpositions, double-bond, 64
Tributyltin radical, 295
Triflyl, abbreviation, 2, 2t
Triphenylmethyl (tityl) radical, 284
Tropylium, 17
Tungsten (W), 402–405
Two-electron donors, 343
Two-electron transfer, 298
- U**
Ullman reaction, 394
- V**
Valence electrons, and valence AOs, 13
Vinyllogous esters, 166
Visible light ($h\nu$), 47
Vitamin D₂, 215
- W**
Wacker oxidation, 396–400
Wallach rearrangement, 188
Weinreb amides, 92
Wilkinson's catalyst, 356, 402
Wittig reactions, 230, 239
Wittig rearrangement, 252, 329
Wolff rearrangement, 109, 111, 229
Woodward-Hoffmann rules, 200
 for cycloadditions, 241
 for electrocyclic reactions, 213
 for pericyclic reactions, 268
 for sigmatropic rearrangements, 257–258, 329
 and the Wittig reaction, 239
 o-Xylylene, 203, 220
- Z**
Ziegler–Natta catalysts, 361–363
Zinc, 98
Zirconium (Zr), 371–372
Zirconocene, 361